


ILLINOIS J. LIBRARY  
AMERICAN METEOROLOGICAL SOCIETY

.5515  
512m

meteorological



abstracts and bibliography

Sponsored by  
AIR FORCE CAMBRIDGE RESEARCH CENTER

graphy on Natural and Artificial Radioactivity in the Atmosphere

May 1956

No. 5

# METEOROLOGICAL ABSTRACTS AND BIBLIOGRAPHY

## EDITORIAL STAFF

*Editor and Technical Supervisor:* MALCOLM RIGBY

*Corresponding Editor:* DR. C. E. P. BROOKS

## FULL TIME

ISADORE L. DORDICK, *Chief Analyst*  
MARY L. RICE, *Assistant Editor-Bibliographer*  
WILHELM NUPEN, *Assistant Analyst*  
DOROTHY M. GROPP, *Cataloguer*  
GEZA THURONYI, *Bibliographer*  
SOFIA ALEKSANDROV, *Technical Editor*

## PART TIME

ANDREW ASSUR, *Analyst*  
DORA M. BROOKS, *Cataloguer*  
WINIFRED SCHRAITL, *Cataloguer*  
MARINA SZE, *Indexer*  
ALEXIS M. POUCHKIN, *Analyst*  
KATHERINE MARTINOFF, *Assistant Technical Editor*  
MARIA A. SNOW, *Assistant Technical Editor*  
MARGARET A. MATTHEWS, *Cataloguer*  
SUSANNE MANOVILL, *Typist*

**\*EDITORIAL OFFICE:** Washington, D. C. **P.O. ADDRESS:** Box 1736, Washington 13, D. C. **Telephone:** REpublic 7-6278.

**ADMINISTRATIVE OFFICE:** American Meteorological Society, Office of Executive Secretary, 3 Joy Street, Boston 8, Mass.

\* Address all business communications, orders and inquiries to the Executive Secretary, Mr. Kenneth C. Spengler, 3 Joy Street, Boston 8, Mass. Exchanges and reprints may be sent direct to P. O. Box 1736, Washington 13, D. C.

METEOROLOGICAL ABSTRACTS AND BIBLIOGRAPHY is a monthly publication devoted to:

- A. Current Abstracts in English on important meteorological literature in every language.
- B. Bibliographic references to other items of interest to the profession.
- C. Selective, annotated bibliographies on subjects of immediate and special interest to meteorologists.

**SUBSCRIPTION RATE:** \$8.00 per year to members and non members. Single and back issues \$2.00. Back volumes, \$10 per volume.

This publication has been made possible through support and sponsorship extended by the Geophysics Research Directorate of the Air Force Cambridge Research Center, Air Research and Development Command, under Contract No. A. F. 19 (604)-302.

# METEOROLOGICAL ABSTRACTS AND BIBLIOGRAPHY

MALCOLM RIGBY, Editor

Vol. 7

MAY, 1956

No. 5



## SPECIAL FEATURE IN THIS ISSUE

An Annotated Bibliography on Natural and  
Artificial Radioactivity


by  
Geza Thuronyi

*(For complete table of contents see back cover)*

---

Published monthly at Prince and Lemon Streets, Lancaster, Pa., by the AMERICAN  
METEOROLOGICAL SOCIETY, 3 Joy Street, Boston 8, Mass.

Printed and issued by: Lancaster Press, Inc.



Digitized by the Internet Archive  
in 2025

## FOREWORD

Meteorological Abstracts and Bibliography is a monthly publication whose purpose is to bring to the attention of meteorologists current literature in their field and in related fields and to provide bibliographic information on various subjects, as interest demands.

Part I contains abstracts of current literature in the fields of meteorology, oceanography, etc., arranged according to the Universal Decimal Classification.

Part II of each issue comprises a special annotated bibliography of important references on a special subject. No attempt is made to prepare exhaustive bibliographies; instead, the aim is to include a representative cross section of the various aspects of a subject.

Bibliographies published in the successive issues were:

### Vol. I, 1950

- |                     |                         |                    |                  |
|---------------------|-------------------------|--------------------|------------------|
| 1. Atmos. Pollution | 2. Aerobiology          | 3. Cloud Physics   | 4. Hail          |
| 5. Tornadoes        | 6. Volcanic Dust        | 7. Climat. Changes | 8. Thunderstorms |
| 9. Icing            | 10. Acoust. Propagation | 11. Evaporation    |                  |

### Vol. II, 1951

- |                        |                          |                   |                        |
|------------------------|--------------------------|-------------------|------------------------|
| 1. Extended Forecast.  | 2. Long Range Forecast.  | 3. Soil Temp.     | 4. Constants, etc.     |
| 5. Clim. of Near East  | 6. Clim. of Middle East  | 7. Special Winds  | 8. Radar Storm Detect. |
| 9. Condensation Trails | 10. Clim. of N.E. Africa | 11. Mountain Met. |                        |

### Vol. III, 1952

- |                         |                      |                             |                       |
|-------------------------|----------------------|-----------------------------|-----------------------|
| 1. Clim. of N.W. Africa | 2. Carbon Dioxide    | 3. Clim. of Argentina, etc. | 4. Dew                |
| 5. Objective Forecast.  | 6. Stratus Forecast. | 7. Urban Climatology        | 8. Clim. of C. Africa |
| 9. Visibility           | 10. Glaze and Rime   | 11. Free Air Turbulence     |                       |

### Vol. IV, 1953

- |                      |                          |               |                             |
|----------------------|--------------------------|---------------|-----------------------------|
| 1. Turbulence Theory | 2. Turbulent Diffusion   | 3. Frost      | 4. Clim. of Australia, etc. |
| 5. High Level Winds  | 6. Winds in Stratosphere | 7. Jet Stream | 8. Radiation Bioclim.       |
| 9. Clim. of Pacific  | 10. Auroras              | 11. Sferics   |                             |

### Vol. V, 1954

- |                    |                        |                          |                    |
|--------------------|------------------------|--------------------------|--------------------|
| 1. Oceanog. Met.   | 2. Clim. of S.E. Asia  | 3. Auroral Physics       | 4. Tropopause      |
| 5. Balloons        | 6. Numerical Forecast. | 7. Radiation Data        | 8. Vertical Motion |
| 9. Clim. of Arctic | 10. Industrial Met.    | 11. Wind Waves and Swell |                    |

### Vol. VI, 1955

- |                          |                              |                              |
|--------------------------|------------------------------|------------------------------|
| 1. Bibliog. of Bibliog.  | 2. Texts & Monogr. Bibliogs. | 3. Storm Surges              |
| 4. Ionospheric Prop.     | 5. Photochem.—Upper Atmos.   | 6. Cloud Physics             |
| 7. Radar Cloud Physics   | 8. Atmos. Nuclei (1841-1950) | 9. Atmos. Nuclei (1951-1955) |
| 10. Weather Modification | 11. Cooling Power            |                              |

Bibliographies published this year are:

1. Synoptic Meteorology of the Arctic, Vol. 7, No. 1, Jan. 1956
2. Climate of Enclosed Spaces, Vol. 7, No. 2, Feb. 1956
3. Cosmic Rays in the Atmosphere (-1952), Vol. 7, No. 3, March 1956
4. Cosmic Rays in the Atmosphere (1953-1956), Vol. 7, No. 4, April 1956
5. Atmospheric Radioactivity, Vol. 7, No. 5, May 1956

Forthcoming bibliographies will be:

6. Tropospheric Inversions, Vol. 7, No. 6, June 1956
7. Snow Micrometeorology, Vol. 7, No. 7, July 1956

Other bibliographies in preparation are:

*Actinometers*  
*Climate of the Arctic*  
*Fog Forecasting*  
*Microwave Propagation*  
*Night Airglow*

*Ozone*  
*Singularities*  
*Snow Cover*  
*Synoptic Aerology*  
*Tropical Cyclones*

Part III contains a listing of the contents of those journals which are primarily meteorological. These are published in the earliest issue where space permits.

Part IV is made up of author, subject and geographical indexes. In the December issue cumulative author, subject, geographical and journal indexes are published.

## EXPLANATIONS

**Location of material:** For each entry, a symbol is given for at least one library where the material may be found. The Union List of Serials (Gregory) is the source of most of the symbols used. In some cases, where no symbol has been assigned to a library, one will be devised according to the principles of the Union List.

Library symbols used frequently may be found in the following list:

|        |                                                                  |
|--------|------------------------------------------------------------------|
| DA:    | U. S. Dept. of Agriculture Library, Washington, D. C.            |
| DBS:   | U. S. Bureau of Standards Library, Washington, D. C.             |
| DGS:   | U. S. Geological Survey Library, Washington, D. C.               |
| DLC:   | Library of Congress, Washington, D. C.                           |
| DN-HO: | U. S. Navy Hydrographic Office Library, Suitland, Md.            |
| DSG:   | U. S. Army Medical Library, Washington, D. C.                    |
| DSI:   | Smithsonian Institution Library, Washington, D. C.               |
| DWB:   | U. S. Weather Bureau Library, Washington, D. C.                  |
| GB-MO: | Great Britain, Meteorological Office Library, Harrow, England.   |
| MH-BH: | Harvard University, Blue Hill Observatory Library, Milton, Mass. |

Other symbols:

|   |                                                                               |
|---|-------------------------------------------------------------------------------|
| * | before an entry indicates a good data source.                                 |
| † | before an entry indicates a good bibliography.                                |
| § | before an entry indicates a synoptic case history study accompanied by charts |

**Geographic locations** are in the English form rather than the form used locally, for example Moscow for Moskva.

**Titles of articles or monographs** are in the language of the original article unless otherwise stated. Slavic (Cyrillic) titles are transliterated into the Roman alphabet according to the Library of Congress transliteration scheme.

**Abbreviations:**

*Titles of periodicals* are not abbreviated, as a rule.

The months of the year from March to July are not abbreviated. Other months are abbreviated as Jan., Feb., Aug., Sept., Oct., Nov., and Dec.

The word or abbreviation for Volume (Tom, Band, Jahrgang, Año, etc.), for Number (Heft, Fascicule, Vypusk, etc.) and for page or pages is omitted from most entries. Thus an entry will read as follows:

*Meteorologische Rundschau*, 2(5/6):146-151, May/June 1950.

This indicates that the article appeared in *Meteorologische Rundschau*, Jahrgang 2 (Volume 2), Heft 5/6 (No. 5/6), pages 146-151, May/June 1950.

## PART I. ABSTRACTS OF CURRENT METEOROLOGICAL MATERIAL

### MAJOR GENERAL WORKS

#### COLLECTED WORKS

7.5-1

551.594.7:551.510.52

†Norton, Kenneth A. and Wiesner, Jerome B., *The scatter propagation issue*. *Institute of Radio Engineers, N. Y., Proceedings*, 43(10):1174, Oct. 1955. DLC—This large issue of the *Proceedings* is devoted to about 35 papers on various aspects of tropospheric or ionospheric propagation of short radio waves beyond the horizon. The introduction by NORTON and WIESNER explains the phenomenon in terms of two contrasting theories, one that irregular "blobs" in the troposphere or cosmic dust clouds in the ionosphere are responsible for this anomalous propagation, the other that regular discontinuities could accomplish the same results (inversions or gradients producing refraction). Papers are abstracted separately and contents found in Pt. III, 7(3):398, *MAB*. *Subject Heading: 1. Tropospheric propagation.*—*M.R.*

#### BOOKS

7.5-2

551.579

Peterson, Elmer Theodore, *Big dam foolishness: the problem of modern flood control and water storage*. Introduction by Paul B. Sears, N. Y., Devin-Adair, 1954. 224 p. photos. DLC—This popular book is the result of the interest the author has maintained in promoting watershed control of runoff rather than control by means of big dams, since 1910, through publications of editorials, magazine and newspaper articles and speeches. The generalized statistics on rainfall, runoff, evaporation, transpiration and other aspects of the hydrologic cycle are cited in nearly every chapter. The main thesis is that floods and serious erosion are the exception rather than the rule when the hydrologic cycle is not disturbed by man. Many small dams on individual farms or creeks would aid the natural storage, whereas big dams destroy natural recreation areas and waste water, threaten downstream areas in case of bombing or overflow, will be obsolete for power production when atomic power is developed and, by claiming all the available money for construction, prevent erosion control projects from developing. The author is opposed to either multiple purpose projects, or to building both big dams and erosion control works. Even dams on mountain streams, where siltation is not a serious factor, may be harmful; but the large dams in the plains region (e.g., Kansas) are inexcusable. The Washita, Kansas program is cited as an example of a sensible approach to conservation. All objections and limitations to the thesis are countered with considerable fervor. Ten other watershed programs are mentioned. Instances are cited where 13.5", 13", 4.6", 6" and 4.57" rainfalls in 4 to 24 hrs or more were completely controlled by watershed projects such as the author recommends. *Subject Headings: 1. Hydrologic cycle 2. Conservation 3. Popular science books.*—*M.R.*

7.5-3

5(02) 551.5:37(02)

Gilman, Phil R. and Van Houten, L. F., *General science today*. N. Y., Rand McNally, 1954. numerous illus. (incl. photos). *Rand McNally Dynamic Science Series*. DWB—Unit 5 of this ultra-modern science textbook for high school students, is concerned with our most abundant resource—water, Unit 6 with the invisible ocean—air; and Unit 7 with the earth's changing atmosphere—weather and climate. A 9-page glossary gives good definitions of such terms as air, aneroid barometer, atmospheric pressure, climate, precipitation, etc. Illustrations of ice island weather stations, glaze damage to wires, snow surveying, rain and wind measuring in the field, radar balloon and rocket equipment for sounding, radar photo of tornado and thunderstorm, weather forecasting and briefing activities, etc. dramatize

the sciences concerned. Considerable space is given to defining the principles behind meteorology and hydrology as well as the observational and applied aspects. *Subject Headings:* 1. Elementary meteorology 2. Science textbooks.—*M.R.*

7.5-4

551.5(023) 551.509.21:621.394

Hornstein, R. A. (*Dominion Public Weather Office, Halifax, N. S.*), **Weather and why**. Illustrated by Norm Steinhaur. Toronto, Meteorological Div., 1954. 61 p. refs. DWB—A systematically arranged popular pamphlet giving answers to about 25 questions which are most frequently asked of meteorologists broadcasting in the "Meet Your Weatherman" program carried by the Maritime and Newfoundland networks and the "Ask the Weatherman" program of Trans-Canada Network of CBS. The 2 page illustrated articles are on auroras, atomic bombs and weather, crepuscular rays, dew, equinoctial storms, green rays, halos, zodiacal light, nacreous clouds, jet stream, Indian summer, St. Eilimo's fire, yellow snow etc., etc. *Subject Headings:* 1. Weather broadcasting 2. Popular meteorology 3. Canada.—*M.R.*

7.5-5

551.5:629.13(023)

Johnston, Harvey, **Weather ways**. Illustrated by Norm Steinhaur. Toronto, Meteorological Div., Dept. of Transport, Canada, 1953. 127 p. numerous illus. DLC—A standard type of text on general meteorology for pilots, comprising a complete revision of **A Pilot's Course in Weather** by D. B. KENNEDY which had been the basic text in meteorology for training pilots and other personnel interested in aviation in Canada. The treatment is non-mathematical and the diagrams and charts simple but accurate. The 19 chapters cover atmosphere, clouds, pressure, wind, moisture, stability, air masses, fronts, cold front weather, warm front weather, occlusions and upper fronts, precipitation and fog, visibility, icing, thunderstorms, turbulence, precipitation, static, etc. *Subject Headings:* 1. Meteorology textbooks for pilots 2. Aeronautical meteorology textbooks. I. Kennedy, D. B.—*M.R.*

7.5-6

551.5(023)

Holmes, David C. and Pitkin, Marvin, **On the wings of the wind**. N. Y., McBride Co., 1955. 204 p. diags., photos. DLC—A dramatic reconstruction of the various processes involved in meteorology, written for the nontechnical reader. The 13 chapters deal with (1) the atmosphere; (2) the solar source of energy; (3) air masses, clouds and fog; (4) fronts and associated weather; (5) the delicate radiation moisture and chemical balance of the atmosphere; (6) cyclones and tornadoes; (7) hurricanes; (8) weather observers, reports and networks; (9) radar and other modern mechanical means of observing or computing meteorological data; (10) military and naval meteorology; (11) the ionosphere, aurora and geomagnetic field; (12) high altitude investigations both on the earth and in the free air and (13) weather modification. A number of good photographs and some schematic drawings give some pictorial background to the literary presentation involved in this popular science book. This is essentially the same book as **Young People's Book of the Weather** (see 7.5-7) except for Chs. 4, 11 and 12 which do not appear in the latter. *Subject Heading:* 1. Popular meteorology.—*M.R.*

7.5-7

551.5:087.5

Holmes, David C. and Pitkin, Marvin, **Young people's book of weather**. N. Y., McBride Co., 1955. 179 p. diags., photos. DLC—**On the wings of the Wind**, by the same authors (see 7.5-6), contains all of the chapters in this book, except Ch. 9 on amateur observing. This book omits Chs. 4, 11 and 12 of the former, chapters on classical frontal theory, on the ionosphere and aurora, and on high altitude investigations, respectively. These chapters are slightly more technical but not beyond the grasp of a high school student, so one infers that by "Young People" the authors mean children in the 6th to 9th grades. The various chapters are entitled: (1) the majestic roof of air, (2) the atomic furnace (sun), (3) islands in the sky (clouds), (4) the imperfect balance (of the atmosphere), (5) the twisting winds, (6) the hurricane, (7) twenty-five thousand prophets, (8) the robot forecaster, (9) backyard weatherman, (10) the invisible army and (11) the garden planet. *Subject Headings:* 1. Popular meteorology 2. Juvenile literature.—*M.R.*

7.5-8

551.509.34(02)

Zharkov, Sergei Nikolaevich, *Narodnye primety i predskazanie pogody*. [Folklore and weather forecasting.] Moscow, Gos.uchebno-pedagog.izd-vo, 1954. 166 p. 36 figs. **DWB**—A popular edition (50,000 copies) on amateur forecasting, emphasizing the local signs and weather lore which are based on keen observations of the effect of the weather on man, animals, plants, etc. as well as on physical phenomena in the atmosphere. First the lore of various countries (proverbs and sayings) are classified according to type of phenomena observed or resulting weather; then effects of weather on living organisms; local indications from simple measurements of pressure, humidity, winds, clouds, optical or acoustical phenomena, and precipitation; then several chapters on horizontal and vertical movements of air, air masses and fronts giving a brief review of elementary synoptic meteorology. *Subject Headings*: 1. Amateur forecasting 2. Weather lore 3. Popular meteorology.—*M.R.*

7.5-9

551.586(211):613.1

†Burton, Alan C. and Edholm, Otto G., *Man in a cold environment: physiological and pathological effects of exposure to low temperatures*. London, Edward Arnold, 1955. 273 p. 75 figs., tables, numerous refs. *Monographs of the Physiological Society*, No. 2. **GB-MO**—This book covers the whole subject of exposure to cold in a very informative manner, both from the physical and medical viewpoints. Ch. 1, Homeothermy and history, deals with the advantages of warm-blooded animals, the reasons for the regulated temperature of 98.6°F, and the relation of health and civilization to mean temperature. Ch. 2, The problem of the homeotherm, the heat balance and physical laws, deals with the temperature and humidity of the skin, the "clo," a corresponding unit of 1 cm of "dead air" for vapor resistance, and heat production and losses. Ch. 3, The thermal insulation of the air, expresses  $IA$  as  $1/(0.61 + 0.19 V^{\frac{1}{4}})$  clo' ( $V$  in cm/sec). Ch. 4, The thermal insulation of clothing or fur, includes a number of practical suggestions for keeping warm. Ch. 5-12 are medical, Ch. 10 dealing with acclimatization to cold. Ch. 13 covers problems for future research. Bibliographies are given at the end of each chapter and on p. 248-265. *Subject Headings*: 1. Bioclimatology of cold regions 2. Medical climatology.—*C.E.P.B.*

7.5-10

551.46

†Smith, Frederick George Walton and Chapin, Henry, *The sun, the sea, and tomorrow: potential sources of food, energy and minerals from the sea*. N. Y., Scribner, 1954. 210 p. 22 figs., 3 tables, bibliog. p. 205-210. **DLC**—The ten chapters of this book about the food and energy resources of the sea, concern such aspects as salt, fish, minerals, power from tides, solar energy resources and relative importance of land and sea to supply the food and energy for the rapidly increasing population of the earth. Solar power from sea plants, land plants, direct heat, space heating, heat pumps, water power, wind power and sea heat as well as nonsolar power from coal and oil, nuclear fission, tides and earth heat is evaluated as to the use in 1950, maximum amount available and maximum use possible in 100 years. *Subject Headings*: 1. Solar energy resources 2. Sea resources.—*M.R.*

### MONOGRAPHS

See also: *Drift currents & permanent flow* (Hela), 7.5-37; *Dew formation* (Hofmann), 7.5-201; *Climate of Formosa* (Formosa Bank. Economy Res. Lab.), 7.5-222.

7.5-11

551.582.1(439.1) 63:91

Görög, László, *Magyarország mezőgazdasági földrajza*. [Agricultural geography of Hungary.] Budapest, Tervgazdasági Könyvkiadó, 1954. 179 p. tables, 71 maps and graphs in pocket, 20 refs. **DLC**—A chapter on climate (p. 54-68) contains a general description of the climate of Hungary, discussion of the climatic requirements of the principal crops grown in Hungary and a climatic classification of the different regions of Hungary from the point of view of these crops. The appended maps include agroclimatic information such as amounts and probabilities of rainfall, accumulated temperature, sunshine, date of last frost, and climatic regions in Hungary, based on data covering 30 to 40 years (Append. 5-10). Of particular interest are the maps (Append. 64-71) showing suitability for growing wheat, corn and potatoes,

on the basis of rainfall probability during the growing season, temperature and soil conditions.  
*Subject Headings:* 1. Climate of Hungary 2. Agricultural geography 3. Hungary.—G.T.

7.5-12

551.579 551.582.2 (494)

\*Lütschg-Loetscher, O.; Hauck, Theophil and Bohner, Rudolf, *Zum Wasserhaushalt des Schweizer Hochgebirges, Band 1, Teil 3, Allgemeines, Kapitel 10, Die Eis- und Scheeverhältnisse der Oberengadiner Sees insbesondere des St. Moritzer Sees.* [Water economy of the Swiss Alps, V. 1, Pt. 3, General, Ch. 10, The ice and snow conditions of upper Engadin lakes, especially Lake St. Moritz.] Zurich, Aschmann & Scheller, 1954. 173 p. 48 tables (some fold.), 54 figs., photos, numerous foot-refs. *Beiträge zur Geologie der Schweiz, Geoteknische Serie, Hydrologie*, No. 4. DWB—This monograph constitutes a comprehensive study of the changes in the state of water, ice and snow in the region of the Oberengadin lakes—especially that of St. Moritz Lake, which is no longer a natural lake but is now a water basing the levels of which change periodically as a result of the operation of hydroelectric plants of St. Moritz industry. This report contains (1) an account of the climate and presents meteorological data for St. Moritz for the period 1864-1945 and hydrological data dealing with the water balance of St. Moritz Lake (inflow and outflow, water levels and thermal characteristics of the water; and (2) a discussion of the freezing, thawing and duration of icing of the Oberengadin lakes during the period 1864-1945. Data on ice, snow cover and the associated meteorological conditions are given for selected years. Descriptions and illustrations of the methods of taking observations and the instrumentation and of various ice formations are presented. (For V. 1, Pt. 1, see 2.2-126, Feb. 1951, *MAB*.) *Subject Headings:* 1. Hydrologic data 2. Water level variations 3. Climate of St. Moritz 4. Swiss Alps 5. St. Moritz, Switzerland.—I.L.D.

7.5-13

551.524.4 (495)

†Makris, Geōrgios I., *Epi tēs metabolēs tēs thermokrasias tou aeros meta tou hypsous eis diaphorous periokhas tēs Hellados.* [Variation of the air temperature with height in various regions of Greece.] *Greece. Ethnikon Asteroskopēion Athēnon, Hypomnemata*, Ser. 2, *Meteorologia*, No. 4, 1955. 136 p. tables, 40 refs. In Greek; English summary between p. 133-134. DWB—Vertical temperature gradients are calculated for 7 respective areas of Greece, from observations made at surface stations in the valleys and in mountains during the 12 months of the year and for northerly and southerly winds, clear and overcast skies. Maximum and minimum temperature gradients as well as mean temperature gradients are analyzed. Gradients are greater in winter than in summer and in the north than in the south. Data are given in graphic as well as tabular form and analyzed at great length in the Greek text. *Subject Headings:* 1. Temperatures in Greece 2. Vertical temperature gradient 3. Greece.—M.R.

7.5-14

551.5:338.91 550.3

Manpower resources in the earth sciences: a study conducted jointly by the National Science Foundation and the U. S. Dept. of Labor Bureau of Labor Statistics. Wash., D. C. National Science Foundation, 1954. 75 p. numerous tables, 5 charts. DWB—An exceedingly intelligent and detailed analysis of >12,000 answers to questionnaires sent to about twice that number of professional geologists, geophysicists and meteorologists in the U. S. Of those who replied, more than 6500 were in the field of geology, 3000 in geophysics and 2800 in meteorology. The sex, income, age group, citizenship status, degree of education, specialty or field of greatest competence, and of actual employment in 1951, type of employment (government, industry, university, transportation, manufacturing, research and business), military status, type of activity (administration, research, teaching, consulting, technical writing, etc.) and major field in college. Analyses show interrelationships of all of these factors with each other, but for each of the 3 major fields there is a clearly presented perspective as to the most important relations or differences between the major fields (or the subgroups where significant relations appear). For instance, meteorology has the highest percentage working for the Government, the highest percentage without any academic degree, the highest percentage with low incomes and the highest percentage with training in other fields. Incomes in industry were substantially higher than in other fields; incomes of Ph.D.'s were highest,

Master's next, but those without degrees higher than those with Bachelor's degrees. Only 3% of the total were women (1% of geophysicists). Of meteorologists, 59% are in synoptic meteorology, 4% in climatology, 3% in instrumentation, 2% in physical meteorology and 2% in dynamic meteorology while 11% are in general meteorology. *Subject Headings:* 1. Meteorological manpower 2. Professional meteorologists 3. Meteorological education 4. Geophysical manpower. I. Shapiro, Solomon II. National Science Foundation III. U. S. Bureau of Labor Statistics.—*M.R.*

7.5-15

551.521.3

Volz, F. (Mainz), *Neue Ergebnisse über die Optik und Meteorologie der atmosphärischen Trübung*. [New data on the optics and meteorology of atmospheric turbidity.] *Berlin. Freie Universität. Institut für Meteorologie und Geophysik, Meteorologische Abhandlungen*, 2(4):99-115, 1955. 8 figs., 8 refs. DWB—A comprehensive analysis of the most important empirical data on spectral scattering functions of Alpine and valley sky light, obtained at Arosa and Frankfurt or Mainz. Three chief turbidity types can be determined easily by the color with the naked eye and are closely correlated with the air masses. Mountain and searchlight data are compared and the relation between scattering function and particle size of aerosol (theoretical), seasonal factors, relation to cloud physics and weather, and climatic factors are discussed and illustrated by means of scatter diagrams and curves. The work of CHR. JUNGE is especially considered as applicable to the cloud physics-aerosol aspects of this subject. *Subject Headings:* 1. Turbidity 2. Skylight color 3. Nuclei 4. Scattering function 5. Arosa, Switzerland 6. Mainz, Germany.—*M.R.*

## GENERAL GEOPHYSICS AND METEOROLOGY

### OBSERVATORIES

7.5-16

551.501.9(744)

Harvard University. Blue Hill Visiting Committee, *Report of the Committee to the Board of Overseers of Harvard College. Blue Hill Meteorological Observatory, Reprint*, No. 7, 1953. p. 37-43 (reprint from Harvard Univ., *Report of the President, 1952/1953?*). MH-BH—Activities, finances and history are outlined. The observatory has been continuously operating since 1884 and represents one of the best homogenous records available. *Subject Headings:* 1. Meteorological observatories 2. Blue Hill Observatory. I. Gross, Robert E.—*A.A.*

7.5-17

551.501.9(058)(744)

†Blue Hill Meteorological Observatory, [Report on] Blue Hill Meteorological Observatory. Reprinted from the *Report of the President of Harvard College and Reports of Departments, 1953/1954*. Its *Reprint* No. 1, 1955. 25 p. Publications of staff members, p. 23-25. MH-BH—Renewed contract activities of Blue Hill Observatory under sponsorship of the Weather Radar Unit of the Cloud Physics Section of AFCRC, GRD, on cloud physics and radar precipitation research; international activities (cloud atlas and 1940-49 edition of World Weather Records), damage and activities in connection with the hurricanes of 1954, library activities and publications of members of staff are among items covered. (For previous reports, see 4.5-32 and 7.1-5, May, 1953 and Jan. 1956, *MAB.*) *Subject Headings:* 1. Annual service reports 2. Blue Hill Observatory 3. Cloud physics 4. Radar research. I. Brooks, Charles F.—*M.R.*

7.5-18

551.58(058)(494) 551.521

Davos, Switzerland. Schweizerisches Forschungsinstitut für Hochgebirgsklima und Tuberkulose, *Tätigkeitsbericht, 1953/54*. [Annual report, 1953/1954.] pub. 1954. 12 p. DWB—Radiation research work in climatology and bioclimatology, personnel and publications, and a list of important guests are included in this report of the Physical-Meteorological Observatory at Davos, of which Dr. W. MÖRIKOFER is director. (For Reports, 1949-1952, see 5.5-194, May 1954, *MAB.*) *Subject Headings:* 1. Annual observatory reports 2. Radiation bioclimatology 3. Davos, Switzerland. Forschungsinstitut. I. Mörikofer, W.—*M.R.*

7.5-19

551.501.9(09)

**Memorial tablets at Kew Observatory.** *Meteorological Magazine*, London, 83(989):321-322, Nov. 1954. photo. DWB—Description with photo of tablets unveiled July 21, 1954, in memory of founding of Kew Observatory in 1769, with list of Observers and Superintendents. A smaller tablet recalls ROBERT BECKLEY, Assistant 1853-72 and designer of recording anemometer and rain gage. *Subject Headings:* 1. History of Kew Observatory 2. Kew Observatory, England.—C.E.P.B.

7.5-20

551.501.9(422)

Glasspoole, J., **Climatological observations at Greenwich.** *Meteorological Magazine*, London, 83(985):201-202, July 1954. table. DWB—The climatological station at Greenwich Observatory has been replaced by one at the National Maritime Museum, 125 ft lower. A comparison of the two sites is given, based on 15 months overlap. *Subject Headings:* 1. Meteorological stations 2. Greenwich, England.—C.E.P.B.

7.5-21

551.5:523.74

**Two major observatories join in solar studies.** *Science News Letter*, Wash., D. C. 27(21):327, May 21, 1955. DLC—The explosive energy of the sun and its impact on all atmospheric layers will be jointly studied by the Smithsonian Institution and Harvard University. The subject has great theoretical interest for astronomers and geophysicists and is of practical value in radio communication, weather forecasting and rocket flights. Headquarters of the Astrophysical Observatory is being moved from Washington, D. C., to Cambridge, Mass., as of July 1, 1955. *Subject Headings:* 1. Solar activity research.—W.N.

7.5-22

550.384

Fanselau, G., **Vorläufiger Bericht über die Beobachtungen am Adolf-Schmidt-Observatorium für Erdmagnetismus in Niemeck in der Zeit vom 1. September bis 31. Dezember 1954.** [Preliminary report on the observations at the Adolf Schmidt Observatory in Niemeck, Sept. 1-Dec. 31, 1954.] *Beiträge zur Geophysik*, 65(1):50-55, 1955. figs., tables. DWB—*Subject Headings:* 1. Magnetic variations 2. Niemeck, Germany.

## CONFERENCES

See also: Soil Mechanics Conference, Montreal, 7.5-164.

7.5-23

550.3:378.2

**Kandidatskie dissertatsii, zashchishchennyye na zasedaniiakh uchenogo soveta geofizicheskogo Instituta AN SSSR v 1953 g.** [Dissertations defended by candidates at the meetings of the Council of the Geophysical Institute of the U.S.S.R. held in 1953.] *Akademiya Nauk SSSR, Izvestiya, Ser. Geofiz.*, No. 2:205-208, 1954. DLC—Most of the dissertations, which are described with brief abstracts, deal with seismology and terrestrial magnetism. A few are concerned with oceanography, atmospheric physics and hydrodynamics. *Subject Headings:* 1. Geophysical conferences 2. U.S.S.R. Geophysical Institute.—I.L.D.

7.5-24

551.5:551.46:061.3(94)

Ramdas, L. A. (*Met. Office, Poona*), **The Pan Indian Ocean Science Congress at Perth, West Australia, August 17-23, 1954.** *Indian Journal of Meteorology and Geophysics*, Delhi, 5(4):363-365, Oct. 1954. DLC—A delegation of 8 Indian scientists including a meteorologist and an oceanographer, attended the Congress. Seasonal forecasting, agricultural meteorology, cosmic rays, rain making, etc. were subjects of symposia or discussions. Details of various papers or discussions are reviewed. The next meeting will be in Madagascar in 1957. *Subject Headings:* 1. Meteorological symposia 2. Pan Indian Ocean Science Congress 3. Perth, Western Australia.—M.R.

7.5-25

550.3:06

Sans Huelin, Guillermo, **Symposium internacional sobre Geofísica y Geodesia Geofísica.** [International Symposium on Geophysics and Geophysical Geodesy.] *Revista de Geofísica, Madrid*, 13(49):123-126, Jan./March 1954. DWB—Report on discussions held during

symposium at Columbus, Ohio in Nov. 1953. *Subject Headings: 1. Geophysical conferences*  
**2. Columbus, Ohio.—M.R.**

7.5-26

551.578.46:061.3

\*†Western Snow Conference, Salt Lake City, April 19-21, 1954, *Proceedings of the twenty-second annual meeting*. Austin E. Helmers, general chairman. Fort Collins, Colo., Colorado A. and M. College, Oct. 1954. 94 p. figs., tables, refs., eqs. Price: \$2.00 from the Western Snow Conference. DWB—Contains 14 papers (abstracted separately), together with discussion of each and purpose graphs, photos and tables. Subject matter included Weather Control Committee activities, rain making in Utah, snow melt, stream flow, long range forecasting, snow surveying, streamflow forecasting, etc., and contributors include H. T. ORVILLE, W. G. LANGBEIN, G. W. CRADDOCK, ROBERT D. ELLIOTT, CHARLES PENNYPACKER SMITH and others. (For list of papers, see Pt. III, 7(5):668, May 1956, MAB.) *Subject Headings: 1. Snow conference proceedings 2. Western United States.—M.R.*

## BIOGRAPHY AND BIBLIOGRAPHY

## BIOGRAPHY

7.5-27

551.5(09)

Hay, R. F. M., William Dampier's contribution to meteorology. *Weather*, 10(6):194-199, June 1955. photo. DWB—Dampier, born 1651, made numerous voyages in the tropics, including circumnavigations of the globe. His accounts contain accurate descriptions of meteorological phenomena. Those quoted include a typhoon off Hong Kong, a waterspout, the climate of Tonkin, and sea breezes. A portrait of DAMPIER is included. *Subject Heading: 1. History of meteorology. I. Dampier, William.—C.E.P.B.*

7.5-28

551.5:92

Hawke, E. L., Mr. J. Fairgrieve, M.A., F.R.G.S. *Royal Meteorological Society, Quarterly Journal*, 80(343):128, Jan. 1954. DWB—Born in Ayrshire March 14, 1870, died Barnet near London, Oct. 8, 1953. Specially interested in teaching geography. Made a detailed study of development and travel of rainfields. *Subject Headings: 1. Biography 2. Fairgrieve, J.—C.E.P.B.*

7.5-29

550.38:92

Davy, N., Carl Friedrich Gauss as a physicist. *Nature*, London, 175(4451):325-326, Feb. 19, 1955. 5 refs. DWB—GAUSS, born April 20, 1777 at Brunswick, became Director of the new astronomical observatory at Göttingen in 1807 and died there Feb. 23, 1855. He became interested in geomagnetism in 1831, and his fundamental work in geomagnetism is described, including theory, introduction of absolute units, and organization of a union of magnetic observatories. *Subject Headings: 1. Biography 2. Geomagnetism 3. Gauss, Carl Friedrich.—C.E.P.B.*

7.5-30

551.579:061.1:63

Rothamsted Experimental Station: Dr. R. K. Schofield [and] Dr. H. L. Penman. *Nature*, London, 175(4450):283, Feb. 12, 1955. DWB—Notes on appointment of SCHOFIELD as head of Chemistry Department and PENMAN as head of Physics Department, with an appreciation of their work on soil science, including soil moisture and water conservation. *Subject Headings: 1. Rothamsted Experimental Station 2. Soil moisture studies. I. Schofield, R. K. II. Penman, H. L.—C.E.P.B.*

7.5-31

551.5:92

Retirement of Mr. P. N. Skelton, M.B.E. *Meteorological Magazine*, London, 84(999):290-291, Sept. 1955. photo. DWB—Retired July 9, 1955, after 49 years in the Meteorological Office. In 1948 he became Head of the Instrument Supply Branch. In 1942 he received the M.B.E. *Subject Headings: 1. Biography 2. Skelton, P. N.—C.E.P.B.*

## BIBLIOGRAPHY

See also: Dew (Hofmann), 7.5-201.

7.5-32

551.5:8.03:016

†American Meteorological Society, Cumulative list of translations made by the American Meteorological Society Translating Unit, Jan. 11, 1952-Dec. 31, 1954. 48 p. Arranged alphabetically by author in four groups: 1. Complete translations. 2. Translations on tape. 3. Abstracts (of certain Russian periodicals and 2 books). 4. Translations received on exchange. MH-BH—A total of 284 titles are listed under the 4 categories. Original titles are given in Library of Congress transliteration scheme following the English title. Work is from Russian, German, Dutch, French, Greek, Hungarian, Italian, Spanish and Bulgarian sources. *Subject Headings:* 1. Translations 2. Russian meteorological literature 3. Bibliography of translations.—M.R.

7.5-33

551.579:016

†International Union of Geodesy and Geophysics. Association of Scientific Hydrology. [International Bibliography of Hydrology]. *Hydrologische Bibliographie, Deutschland* [Hydrological bibliography for Germany], 1951. pub. Coblenz, 1955. 119 p. 487 refs. DWB—Format similar to 1945-1950 issues. Sec. I (Hydrometeorology) contains 83 abstracts of German publications in the 4 fields of (1) rain, (2) snow, (3) evaporation and humidity and (4) applications. Sec. II, Streams; III, Lakes; IV, Glaciers; V, Ground water; VI, Hydrologic cycle (37 items); VII, Applications of other sciences to hydrology; VIII, General works (bibliographies, handbooks, glaciers, reports of meetings) and IX, Miscellaneous. Sec. X is an author index. Most of the items are from literature published in Germany in 1950 and 1951. For abstract of earlier issues, see 6A-85, Jan. 1955, *MAB.*) *Subject Headings:* 1. Hydrology bibliographies 2. Hydrometeorology 3. Germany.—M.R.

7.5-34

551.5:017

†Lange, Maxwell and Springer, Ltd., London, *Meteorology and cognate sciences*. Books mainly from the Library of the Royal Meteorological Society, London, with a section of periodical publications and current books. Its *Catalogue*, No. 11, Autumn 1954. 56 p. DWB—A list of 863 books and monographs, serials, etc. and prices for each, plus about 60 current books, the main part of a collection disposed of by the Royal Meteorological Society when their library was reorganized after World War II. Many old and valuable books and some long series of periodicals are included. *Subject Heading:* 1. Meteorology book catalogs.—M.R.

7.5-35

551.5(023):048.1

†Rigby, Malcolm (Ed., *Met. Abstracts, Wash., D. C.*), *Recent books on meteorology. Weatherwise*, 8(2):50-51, 56-57, April 1955. port. Also his: *Recent specialized meteorological books (1952-1954)*. *Ibid.*, 8(3):74-76, June 1955. DWB—Fifteen recent meteorological, climatological or geophysical texts or popular science books published in England or the U. S. (1953 and 1954) are reviewed noncritically for the amateur meteorologist or student in the first article. The second article contains popular reviews of 19 recent technical books on such varied subjects as aeronautical meteorology, micrometeorology, tropical meteorology, cloud physics, climatic changes, instruments, visibility, rocket research, physical meteorology, bioclimatology, statistical methods, oceanography and long range forecasting. *Subject Headings:* 1. Reviews of meteorology books 2. Bibliographies of textbooks.—M.R.

7.5-36

551.5:016(05)

*Terra, Helsinki*, vol. 66, No. 4, 1954. DLC—This issue includes the index for v. 41-65, 1929-1953, the third index since the beginning of this journal in 1888 as the *Tidskrift* of the Geografiska Föreningens, Helsinki. Index is divided into an alphabetical Author Index and a Subject Index (latter alphabetical by author under five subheads: General, Regional and Finnish Geography, Biography, and Congresses). Pages 125-126 and 139-140 touch on Meteorology and Climatology. With 13 references under the *Meteorology and climatology* and 8 references under *Hydrography*. p. 139-140. *Subject Headings:* 1. Author indexes 2. Subject indexes 3. Periodical indexes.—W.N.

## APPLIED METEOROLOGY

## MARINE METEOROLOGY AND OCEANOGRAPHY

7.5-37

551.556:551.465(261.3)

\*Hela, Ilmo, **Drift currents and permanent flow.** *Finska Vetenskaps-Societeten, Helsinki, Commentationes Physico-Mathematicae*, 16(14), 1952. 28 p. 9 figs., 25 tables, 2 refs. DLC—Supplementing PALMÉN's (1930) study of **Currents in the Gulf of Finland and the Baltic**, based on 1923-27 data, the observations made during 1928-1939 (16,920 current observations) at Lightships "Helsinki" and "Tallinn" are analyzed in every conceivable manner to show the relations between the wind and drift currents, and the permanent flow exclusive of drift currents. The speed and angle of deflection of drift currents with respect to wind is also treated. The characteristic current (sum of permanent and steady wind driven current) for each month is computed. This "characteristic" current plus the drift current gives the "resulting" current. Finally, the pure drift current is calculated by eliminating the "characteristic" current from the actual current. Coastal influences are shown in graphical form and discussed. *Subject Headings:* 1. Currents in Gulf of Finland 2. Wind driven currents 3. Gulf of Finland.—M.R.

7.5-38

551.46:37

Freeman, John C., Jr. (*Agr. and Mech. Col. of Texas*), **Oceanography in Texas.** *I.U.G.G. Association of Physical Oceanography, Rome, Sept. 14-25, 1954, Procès-Verbaux.* Bergen, 1954. p. 147. DWB—A Dept. of Oceanography was organized in the fall of 1949 at Texas A. & M. College. The report gives brief information on: the actual academic and research staffs (now 100 in number), the undergraduate program, the M.S. and Ph.D. degrees offered yearly in each of the 5 phases of oceanography, the contract research on 20 projects sponsored by the government and industrial agencies, and the annual budget of the department (\$7,500,000). *Subject Headings:* 1. Oceanographic research 2. Oceanographic education 3. Texas Agricultural and Mechanical College.—A.M.P.

7.5-39

551.46:06

Hachey, H. B. (*Canadian Joint Com. on Oceanog.*), **A review of Canadian oceanography.** *I.U.G.G. Association of Physical Oceanography, Rome, Sept. 14-25, 1954, Procès-Verbaux.* Bergen, 1954. p. 121-122. DWB—The organization of Canadian oceanography is described and discussed. It is headed by the Canadian Joint Committee formed in 1946 involving the Fisheries Research Board, the Royal Canadian Navy, the National Research Council and the Hydrographic Service. Its chief functions are: to further oceanographic research and to direct (through the Chief Oceanographer) the work of the Atlantic and Pacific Groups. In the Arctic, although the investigations are still of a reconnaissance nature; a comprehensive program is now getting underway, both in the eastern and western Arctic. *Subject Headings:* 1. Oceanographic services 2. Canada.—A.M.P.

7.5-40

551.46:06

†Hansen, Walter (*Deutsches Hydro. Inst., Hamburg*), **Physikalische Ozeanographie am Deutschen Hydrographischen Institut, 1951-1954.** [Physical oceanography at the German Hydrographic Institute, 1951-1954.] *I.U.G.G. Association of Physical Oceanography, Rome, Sept. 14-25, 1954, Procès-Verbaux.* Bergen, 1954. p. 123-130. bibliog. p. 127-130. DWB—Contains an inventory of results of investigations, papers and scientific achievements obtained by oceanographers of the German Hydrographic Institute in the fields of: morphology and geology of seas and oceans; currents and surface conditions of the sea (drift currents, slack water); periodical movements (tides and surface waves); oceanographic observation and instruments; physics and chemistry of the sea; and sea ice. A list of 51 references divided according to the several fields is added. *Subject Headings:* 1. Oceanographic research 2. German Hydrographic Institute.—A.M.P.

7.5-41

551.465

†Haurwitz, B. (*Dept. of Met. and Oceanog., N. Y. Univ.*), **Report of ocean wave research conducted at New York University.** *I.U.G.G. Association of Physical Oceanography, Rome,*

Sept. 14-25, 1954, *Procès-Verbaux*. Bergen, 1954. p. 150-153. bibliog. p. 152-153. DWB—A report of the work done in recent years by the Dept. of Meteorology and Oceanography on ocean wave research on the basis of empirical and theoretical studies. Principles of hydrodynamics, Fourier analysis, time series, and statistics were combined to achieve results which come close to representing actual wind generated gravity waves within the limitations of a linear theory. Explanation of the behavior of swell and the period increase observed in waves traveling out of the wave generating area are given. A theory adequately explaining the fact that a ship rolls with one average period and pitches with another average period has been developed. *Subject Headings*: 1. Ocean wave research 2. New York University 3. Ocean swell.—A.M.P.

7.5-42

551.5(263):551.4

Leipper, Dale F. (Head, Dept. of Oceanog., Texas A. & M. College), *Marine meteorology of the Gulf of Mexico: a brief review*. Texas. Agricultural and Mechanical College. Dept. of Oceanography, Collected Reprints in Oceanography and Meteorology, No. 1/30, 1950-1954. 279-288. 6 figs., table, 19 refs. DWB. Reprint from U. S. Fish and Wildlife Service. Fishery Bulletin, No. 89 (1952?) DA—A general but analytical review of meteorological conditions in the Gulf of Mexico, including discussion of extratropical cyclones, general circulation effects, average pressure and wind conditions, observing stations, typical upper air soundings at Swan Island, New Orleans and Brownsville; northers, meteorological and hurricane tides, hurricanes, applications of marine meteorology in the Gulf, and sources of information (pilot charts, and other Hydrographic Office-U. S. Weather Bureau publications). More knowledge of the underlying water surface in the Gulf is needed for development of marine meteorology of area. *Subject Headings*: 1. Marine meteorology 2. Gulf of Mexico.—M.R.

7.5-43

551.4

Panikkar, N. K. and Ramachandra Rao, M. B. (Central Bd. of Geoph., India), *Note on recent oceanographic work in India*. I.U.G.G. Association of Physical Oceanographers, Rome, Sept. 14-25, 1954, *Procès-Verbaux*. Bergen, 1954. p. 136-142. bibliog. p. 141-142. DWB—The oceanographic work carried out in India deals with: 1) physical oceanographic studies made by the Indian Navy, the India Meteorological Dept., the Andhra University and the Central Marine Fisheries Station at Mandapan; 2) tidal observations made by the Survey of India (Geodetic Branch); 3) marine biological studies carried out by the Central Marine Fisheries Station at Mandapan, fishery stations of certain maritime states and geological departments of universities situated on the seacoast. Plans and proposals for establishing a Central Institute of Oceanography at a suitable center have been taken up by the Oceanography Committee. *Subject Headings*: 1. Oceanographic research 2. India.—A.M.P.

7.5-44

551.463

Lednev, V. A., *Izmereniia gidrologicheskogo rezhima Azovskogo, Aral'skogo i Kaspiiskogo morei pri umen'shenii stoka rek*. [Variations in hydrologic regime of the Azov, Aral and Caspian seas during decrease of river discharge.] *Meteorologiya i Gidrologiya*, Leningrad, No. 4:13-20, July/Aug. 1955. 6 tables, eq. DWB—The limits of the possible variations of different elements of the hydrological regime of the seas were examined in order to obtain a basis for developing the fishing industry. This study contained an analysis of the mean salinity (in ‰) of the Sea of Azov in case of the annual renewal of 13.5 km<sup>3</sup> of water from the river flow; changes in the Sea of Aral in case of an annual withdrawal of 10 and 20 km<sup>3</sup> of water from the river flow; the effect of withdrawal of elements of the salt balance upon changes in the salinity of the Caspian and Aral Seas; area and volume of water during a drop in sea level for the Aral and Caspian Seas; and expected salinity of the Northern Caspian in case of a withdrawal of 50 km<sup>3</sup> from Volga River flow. *Subject Headings*: 1. Hydrologic regime 2. Salinity distribution 3. Azov Sea 4. Aral Sea 5. Caspian Sea.—I.L.D.

7.5-45

551.582(51):629.12

\*Great Britain. Hydrographic Dept., *Ch'ang chiang Pilot comprising the Ch'ang chiang from Wu-sung Bar to the head of Navigation, also Po-yang hu and the rivers flowing into it, Han chiang, Tung-ting hu and the rivers flowing into it, Chia-ling chiang and Min chiang*

7th ed. London, 1954. 49+394 p. 56 plates, tables. Meteorology, p. xxxiv-xlix; Climatic tables, p. 15-23. *Subject Headings: 1. Sailing directions 2. China.*

7.5-46

551.582:656.6(47)

\*U. S. Hydrographic Office, *Sailing directions for Northern U.S.S.R., vol. 1, Mys Nemetskiy to Mys Kamin Nos.* 1st ed. 1953. Its *H.O. Publication*, No. 137A, 1954. 402 p. 72 figs., charts (1 fold. in pocket). loose-leaf. "137B to be pub. Oct. 1954; 137 C, Feb. 1955." **DWB**—This is the most elaborate of the H.O. Sailing Directions, and the first to be put out in loose-leaf form. The charts are neat and well printed. In Sec. 1, Ocean and Coastal *Currents* are discussed on p. 29-48 (with many detailed charts), *Ice*, p. 48-116 (warming of Arctic seas, p. 61-62; dates of freezing and opening of ports and bays, p. 75; Ice terminology, p. 76-96); *Climatology*, p. 116-149 (wind, temperature, precipitation, snow, cloud, humidity, visibility, fog, wind roses and tabular data as well as charts); and *Sea temperatures*, p. 150-159. Some discussion of currents, weather, ice, etc. is included in separate sections on the various sectors of the White Sea (Ch. 2-6) on pages 161-374. Extensive climatic tables for 6 stations are appended. *Subject Headings: 1. Climate of White Sea area 2. Sailing directions 3. White Sea.—M.R.*

### AERONAUTICAL METEOROLOGY

*See also: Sub-tropical jet stream* (Hoyle), 7.5-122; *Jet stream* (N. Y. Times Mag.), 7.5-123; *Pacific jet stream* (Serebreny et al.), 7.5-124; *Jet stream over Pacific* (Serebreny), 7.5-125; *Jet stream navigation* (Stieflemaier), 7.5-126.

7.5-47

551.501.45:681.143:629.13

U. S. Air Weather Service, *Meteorological uses of the E6D computer.* Its *Manual* 195-46, Nov. 1954. 13 p. 21 figs. **DWB**—The E6D dead reckoning computer is a multi-purpose circular slide rule which has been made standard equipment for U. S. Air Weather Service Forecast units. The manual explains, illustrates and gives examples of the computer and its use in calculating: 1) true air speed (knots) from Mach number; 2) true air speed corrected for density; 3) true altitude correlated for temperature; 4) density altitude; 5) single drift correction; 6) course correction angle; 7) ground speed; 8) estimated time of flight; 9) wind factor and 10) conversions of units. *Subject Headings: 1. Dead reckoning computers 2. Aeronautical meteorology 3. Instrument manuals 4. Slide rules.—M.R.*

7.5-48

551.5:629.13

*Winter weather hazards. Weather maps prepared by Air Weather Service. Flying Safety*, Wash., D. C., 10(10):14-15, Oct. 1954. maps. **DWB**—Charts of U. S. show isolines of frequency of low ceilings and visibilities, % of time that snow, fog and rain falls in winter; and histograms of monthly number of major accidents to military aircraft in U. S. in which rain, snow and low ceilings (excluding fog) figured during 1947-53. The latter chart shows Dec. through March to be the most dangerous months and the former charts show the mountain areas and northern states to have the worst records. *Subject Headings: 1. Winter flying hazards 2. United States. I. U. S. Air Weather Service.—M.R.*

7.5-49

551.5:797.5(061.3)

Corby, G. A., *The fifth O.S.T.I.V. Congress, Buxton 1954. Weather*, 9(10):312-314, Oct. 1954. Also: Scorer, R. S., *O.S.T.I.V. 1954; Meteorology and gliding. Royal Meteorological Society, Quarterly Journal*, 80(346):631-634, Oct. 1954. 11 refs. Also: Murgatroyd, R. J., *Meteorological meetings of the fifth Congress of the Organisation Scientifique et Technique Internationale du Vol à Voile. Meteorological Magazine*, London, 83(989):343-344, Nov. 1954. **DWB**—Accounts of Congress at Buxton July 20-Aug. 5, 1954, with mention of papers presented on convection, turbulence, lee waves, etc. and brief summaries. *Subject Heading: 1. Gliding congresses.—C.E.P.B.*

7.5-50

551.5:629.13

Barnett, Kenneth Marshall and Reber, Carl M. (*U. S. W. B.*), *Weather and the private pilot.* [1948-1949] 17+ p. 8 figs., refs. Typescript. **DWB**—Elementary discussion of

weather phenomena for use by flyers with limited means. Weather factors significant in flight, such as visibility, ceiling, turbulence, precipitation, icing, etc. are described in general terms. A few practical hints on how to obtain weather information and on how to use it are given. Five references for further studies and a table of wind-force and state-of-sky specifications as used in Weather Bureau forecasts are appended. Six cloud photographs extracted from U.S.W.B. Circular S (see item 9-13, Sept. 1950, *MAB*) are attached. *Subject Heading: 1. Aeronautical meteorology.—G.T.*

## AGRICULTURAL METEOROLOGY

See also: *Agricultural geography* (Görög), 7.5-11.

7.5-51

551.510.42:57(66)

Cammack, R. H., *Seasonal changes in three common constituents of the air spores of Southern Nigeria*. *Nature*, London, 176(4496):1270-1272, Dec. 31, 1955. fig., 5 refs. DWB—Air spores at Federal Dept. of Agricultural Research, Ibadan, at 6000 ft on edge of lowland rain forest were sampled by spore trap 2 m above ground. Counts of 3 species showed a marked diurnal variation, with peak before noon in the dry season and after noon in the wet season. Temperature and humidity were important factors in the concentration. *Subject Headings: 1. Aerobiology 2. Ibadan, Nigeria.—C.E.P.B.*

7.5-52

551.526:6

Mihara, Yoshiaki, *Problems on the temperature arising from the standpoint of agricultural physics*. *Journal of Agricultural Meteorology*, 9(1):23-26, Dec. 1953. table. 1. Japanese. MH-BH—To increase the temperature of water in paddy fields in order to get a rich harvest of rice, some fundamental problems were discussed. This is the first article in the symposium on how to increase the water temperature in paddy fields (see also 7.1-245, Jan. 1956, *MAB*). Problems on temperature increases of water during the passage of irrigation water through the paddy field itself, and the prevention of evaporation are discussed. *Subject Headings: 1. Irrigation 2. Rice culture.—H. Arakawa.*

7.5-53

551.5:63:00

Hogg, W. H., *The work of a Meteorological Office attached to the National Agricultural Advisory Service*. *Worcestershire Agricultural Chronicle*, 23(3):185-191, May/Aug. 1955. 1. DA—An account of the work of the Office in Bristol. This includes advice on shelter belts, irrigation needs, relative frost risks, etc. *Subject Headings: 1. Agrometeorological service 2. Great Britain.—C.E.P.B.*

7.5-54

551.5:63

Baumann, H., *Agrarmeteorologie und Landwirtschaft*. [Agricultural meteorology and husbandry.] *Germany. Deutscher Wetterdienst in der US-Zone, Berichte*, No. 42:183-186, 1952. 5 refs. DWB—A plea for increased attention to agricultural meteorology in both agricultural colleges and meteorological services. *Subject Heading: 1. Agricultural meteorology.—C.E.P.B.*

7.5-55

551.5:63

Barth, H., *Die Bedeutung der Grundlagenforschung für die Beratung in der Landwirtschaft*. [The importance of basic investigation for agricultural evaluation.] *Germany. Deutscher Wetterdienst in der US-Zone, Berichte*, No. 42:325-326, 1952. DWB—Note on the necessity for cooperative agricultural meteorological research as a basis for more intensive agriculture. *Subject Heading: 1. Agricultural meteorology.—C.E.P.B.*

## FOREST METEOROLOGY

7.5-56

551.509.58:632.187

Graham, Howard E.; Nelson, Edward W. and Capell, John C., *Application of long wave theories to forecasting in the Portland Fire-Weather District*, Pt. 1-3. (In: U. S. Weather Bureau, [Papers presented at the Fire Weather meetings at Portland, Ore., Feb. (March?),

1955.] 3 pieces, separately paged 3+6+5 p. refs. Typescript.) DWB—Zonal wind time section charts and continuity charts are prepared twice a day at Portland in order to apply theory and research of others to 3 to 5 day forecasting of hot dry anticyclonic conditions which are serious for fire danger. These charts also aid in making 24-48 hr forecasts as they make the prognostic position of the anticyclonic centers more accurate for short range forecasting. It has been found that long waves do not progress regularly toward the E, but move  $10^{\circ}$  to  $150^{\circ}$ E when zonal flow is increasing in mid latitudes and retrograde when zonal wind maxima move well to the N or S. The third paper discusses problems encountered in applying the twice daily "canned" analyses from WBAN at Washington to local forecast requirements. *Subject Headings:* 1. Long wave theory application 2. Fire weather forecasting 3. Oregon.—M.R.

7.5-57

551.509.58:632.187

\*Lindquist, H. D. (WBAS, Seattle, Wash.), *Verification of the 1954 wind forecasts in the Washington Fire Weather District*. Paper dated March 1955. (In: U. S. Weather Bureau, [Papers presented at the Fire Weather meeting at Portland, Ore., Feb. (March?), 1955]. 7 p. map, table. Mimeo.) DWB—At the end of the 1954 fire season it was decided that wind forecasts for 33 stations in western, central and northern Washington State would be verified. The forecasts were made without any regard for verification and are thus unbiased in that respect. Wind direction and speed verification, according to the criteria set forth, range from 41% (Enumclaw) to 91% (Columbia Gorge) and 12% (Port Orchard) to 93% (Quilcene), respectively. Average winds, % of time, wind 10 mph or over, variability in wind speed, and % of time forecasts gave too high speeds are tabulated for each station. It shows that tendency is to forecast too high speeds (or else anemometers are in poor locations with respect to terrain, etc.). A questionnaire to determine if forecasts were satisfactory showed that dissatisfaction existed in those few places where winds were most variable and hence forecasts considered of little use anyway. *Subject Headings:* 1. Fire weather forecasts 2. Wind forecast verification 3. Washington State.—M.R.

7.5-58

551.509.58:632.187

\*Hanna, Ralph T. (WBAS, S. Francisco, Calif.), *Upper Sacramento River drainage wind survey*. (In: U. S. Weather Bureau, [Papers presented at the Fire Weather Meeting, Portland, Ore., Feb. (March?), 1955]. 6 p. 6 figs., table.) DWB—Charts show location of 11 stations in the drainage area, 8 a.m. and 3 p.m. wind flow in relation to topography and 8 a.m. and 3 p.m. wind roses at 10 stations. Data are analyzed for 9 stations for fire season of summer 1954 (34 to 77 days) and average hourly wind speeds from 7 a.m.-10 p.m. are given in a table. Brief rules derived from analysis of data are given for 10 stations, with respect to diurnal variations in wind patterns at each. Topographic variations are also discussed. *Subject Headings:* 1. Fire weather studies 2. Local wind surveys 3. Mountain-valley wind patterns 4. Upper Sacramento Basin, Calif.—M.R.

7.5-59

551.509.58:632.187

\*Hanna, Ralph T. (WBAS, S. Francisco, Calif.), *Report on the Big Creek Wind Survey, Sierra National Forest, season of 1954*. (In: U. S. Weather Bureau, [Papers presented at the Fire Weather Meeting, Portland, Ore., Feb. (March?), 1955]. 6 p. 7 charts, 2 tables. Typescript.) DWB—A wind survey program was inaugurated in 1954 in California forests to determine how winds affect fire behavior and to determine the feasibility of using forest service personnel to supply wind information for fire weather forecasts and other activities connected with fire fighting. In the Big Creek area—about 14 miles long—9 temporary stations were maintained, during period Aug. 15-Oct. 31, 1954, using Forest Service personnel. Charts show air flow patterns for morning, noon and late afternoon, and wind roses 3 times a day for 4 stations. Wind speed and gustiness data were also obtained and compared with synoptic charts. Conclusion is that data were too few for accurate statistical evaluation and wind recorders should be installed in area with proper exposures to obtain continuous records of direction and speed for several weeks. Also full-time personnel rather than part-time, as in this survey, should be used. *Subject Headings:* 1. Fire weather studies 2. Local wind surveys 3. Mountain-valley wind patterns 4. Big Creek Drainage, Calif.—M.R.

## METEOROLOGICAL OBSERVATIONS AND INSTRUMENTS

## METHODS OF OBSERVATION

See also: **Meteorological observatories** (Harvard Univ. Blue Hill Visiting Comm.), 7.5-16; **Annual service reports** (Blue Hill Met. Obs.), 7.5-17; **History of Kew Obs.**, 7.5-19; **Climatological obs. at Greenwich** (Glasspoole), 7.5-20; **Panama tornadoes** (Alpert), 7.5-129; **Water supply forecasts** (Strauss), 7.5-217.

7.5-60

551.501:551.509.314

Levick, R. B. M., **Mapping the weather.** *Weather*, 10(12):inset 412-413, Dec. 1955. colored plate. **DWB**—Sets out a method of plotting sequence of weather types for a whole year along a N-S line over Britain, using colored symbols. *Subject Heading: 1. Weather type symbols.*—*C.E.P.B.*

7.5-61

551.501.45:551.577.3 551.578.46

\*Abramova, E. I., **O dopuskakh, priniatykh pri obrabotke nabludenii nad osadkami vysotoi snezhnogo pokrova i oblachnost'iu.** [On the magnitude of errors acceptable in the working up of observations on precipitation, depth of snow cover and cloudiness.] *Leningrad. Glavnaia Geofizicheskaiia Observatoriia, Trudy*, No. 34(96):58-68, 1952. 6 figs., 6 tables. **DLC**—Permissible errors in working up any meteorological element are determined by the precision of interpolation which depends upon the spatial variations of the element. The method for determining the spatial variability of precipitation—number of days with precipitation, depth of snow cover involved, the selection of stations from among stations with similar physical geographic conditions in regions of dense station network is described. The mean monthly precipitation amount and number of days with precipitation, mean decadal depth of snow cover, deviations of individual stations from regional mean and frequency of various magnitudes of deviations were calculated. Tables are presented showing frequency of deviation of monthly amounts of precipitation from regional mean for Nov.-March, May-Aug. frequency of deviation of number of days with precipitation >0.1 mm from regional mean; frequency of distribution of depth of snow cover for each station from regional mean, etc. *Subject Headings: 1. Precipitation calculations 2. Snow cover depth 3. Precipitation variability.*—*I.L.D.*

7.5-62

551.501.45:681.177

Guss, H. (*Bad Kissingen*), **Die meteorologischen Lochkarten des Deutschen Wetterdienstes und ihre hauptsächlichsten Auswertungsmethoden.** [Meteorological punch cards of the German Weather Service and the principal method for their evaluation.] *Berlin. Freie Universität. Institut für Meteorologie und Geophysik, Meteorologische Abhandlungen*, 2(4):2-24, 1955. 3 figs., 4 refs. **DWB**—A complete illustrated summary of the uses of punched cards in the German Weather Service, and the kind and size of the various types of meteorological "decks." Included are marine, climatological, aerological and synoptic cards (cards and summaries reproduced as examples). Possibilities for complete mechanization of synoptic observation punching from teletype sequences is envisioned. *Subject Headings: 1. Punched card programs 2. Punched card methods 3. West Germany.*—*M.R.*

7.5-63

551.501.45:551.579.4

†Novotný, Jan, **Reálné podmínky možnosti výpočtů povrchového odtoku vody z dešťových srážek.** [Practical conditions required for calculating runoff from rainfall data.] *Meteorologické Zprávy*, Prague, 8(2):29-35, April 30, 1955. figs., 84 refs., eq. **DWB**—The correlation between rainfall and runoff is treated theoretically and graphically, assuming rainfall of uniform intensity over the whole catchment. Typical peak flow curves are presented. The extensive list of references is a good survey, especially of German, Russian and Czech literature on the subject. *Subject Heading: 1. Runoff evaluation.*—*G.T.*

7.5-64

551.501.45:519.24

Sneyers, R., **Sur l'analyse des répartitions statistiques discrètes.** [On the analysis of discrete statistical distributions.] *Archiv für Meteorologie, Geophysik und Bioklimatologie*,

Ser. B, 7(1):117-132, 1955. figs., 7 tables, 8 refs., 20 eqs. German, English and French summaries p. 117. **DWB**—In this highly mathematical paper the frequency distribution of discrete observations is shown to depend on 4 variables which readily reduce to 2. Cases studied are the binomial, Poisson, "negative binomial," logarithmic and geometric distributions. The theoretical expressions are applied to sequences of dry days at Paris, days with rain at Uccle, winter thunderstorms in Belgium, and hard frosts at Uccle. *Subject Headings:* 1. Statistical studies 2. Frequency distributions.—C.E.P.B.

7.5-65

551.501.7:551.557:551.590.25

Robertson, D. S.; Liddy, D. T. and Elford, W. G. (all, Adelaide Univ., Physics Dept., S. Australia), **Measurements of winds in the upper atmosphere by means of drifting meteor trails**, Pt. 1. *Journal of Atmospheric and Terrestrial Physics*, London, 4(4/5):255-270, 1953. 14 figs., 3 refs., eqs. Also: Elford, W. G. and Robertson, D. S., **Measurements . . .**, Pt. 2. *Ibid.*, p. 271-284. 9 figs., table, 9 refs., eqs. **DWB**—Pt. 1 describes some new radio techniques for the measurement of upper atmosphere winds by means of drifting meteor trails. A continuously recording Doppler-radar system operating on 27 mc is described and some typical records are analyzed. In Pt. 2 winds in the upper atmosphere have been deduced from the drifts of meteor trails by means of a continuously recording Doppler-radar system operating on 27 mc. Measurements of the average diurnal variations of the winds at known heights between 80-105 km have been obtained for each of the three months, Oct., Nov., and Dec., 1952. The winds are found to be essentially horizontal and analysis of the diurnal variations shows the presence of prevailing and periodic components of the wind. The 12 hr and 24 hr harmonic components represent anticlockwise rotation of the wind vectors; the 12 hr component is consistent with the phase of a semidiurnal tidal wind as deduced from barometric oscillations. While, at any time, the direction of the wind remains the same over the height range investigated, the mean velocity of the wind increases with height. *Subject Headings:* 1. Upper air wind measurement 2. Meteor trail drift.—Authors' abstract.

7.5-66

551.501.8:551.557:551.507.2(261)

Harrison, D. N., **Radar wind comparisons on the Ocean Weather Ships (second series)**. Great Britain. *Meteorological Research Committee, M.R.P.* 928, Aug. 8, 1955. 7 p. 4 tables, ref. Mimeo. **DWB**—Trials were made in 1953-4 to assess the improvement in radar wind accuracy since 1949 by comparing observations of pairs of ships. A small improvement was found. *Subject Headings:* 1. Radar wind accuracy 2. Weather ship data.—C.E.P.B.

7.5-67

523.5:551.501.81

Hines, C. O., **Diurnal variations in the number of shower meteors detected by the forward-scattering of radio waves**, Pt. 1, Theory. *Canadian Journal of Physics*, Ottawa, 33(9):493-503, Sept. 1955. 8 figs., table, 5 eqs., refs. **DWB, DLC**—Various observational factors affect the number of shower meteors which can be detected, in a given time interval, by the scattering of radio waves from the ionized meteor trails. The pertinent factors in the case of forward-scattering, where the transmitter and receiver are widely separated, are expressed approximately as functions of the position of the shower radiant. In combination, they provide an observational weight factor which may change appreciably as the radiant moves in the course of a day. The consequent diurnal variation in the occurrence of scattered signals may then be determined, and distinguished from variations due to random changes in the incidence rate of the meteors. *Subject Headings:* 1. Radio meteor observation 2. Radio echoes from meteors.—Author's abstract.

7.5-68

551.501.81:551.57

Robinson, N. P., **Measurements of the effect of rain, snow and fogs on 8.6 mm radar echoes**. *Institution of Electrical Engineers, London, Proceedings, Pt. B*, 102(5):709-714, Sept. 1955. 4 figs., table, 18 refs., 12 eqs. **DLC**. Summary in *Institution of Electrical Engineers, London, Journal, n.s.*, No. 10:645, Oct. 1955. **DLC**—A radar set has been used to investigate the propagation of 8.6 mm radiation through various types of weather. Measurements have been made of the attenuation caused by the precipitation particles and of the intensity of radiation scattered back. No attempt has been made to correlate the results

obtained with drop size distribution, but the results are plotted against precipitation rate. The attenuation caused by rain and the intensity of radiation scattered back by rain agree well with theoretical predictions. The echo intensity from fogs was too low to be detected but the attenuation of a corner reflector echo was measured in several fogs of different visibilities. While the results were of the same order as those predicted by theory, there was some variation, especially for fogs causing low visibility. The attenuation caused by dry snow has not been measured, but moist snow produced attenuation two and half times greater than rain of similar precipitation rate. The echo intensity returned from the "radar bright band," composed of melting snow, was 14-19 dB more than the echo intensity from the dry snow above it, and 2-8 dB more than the echo intensity from the rain below it. *Subject Headings:* 1. Precipitation effects on radar echoes 2. Radar echoes.—*Author's abstract.*

7.5-69

551.501.9(712) 551.506.1(712)

\*Canada. Meteorological Division, **Annual meteorological summary for Regina, Saskatchewan for 1954**. Prepared by the Aviation Forecast Office, Regina Airport, Regina, Saskatchewan. [1955?] 23 p. numerous tables. DWB—Brief history of meteorological observations at Regina (begun 1884), and 24-hourly observations (begun at Airport in 1938). topography, climate, instrumentation in detail, description of weather in year 1954 and each month; summarized data (averages, extremes, etc.) for 1954 and tables of monthly and annual temperature, precipitation, snow, relative humidity, sunshine, wind, pressure, and daily, maximum minimum precipitation and snow for 1954. Comparative records for each month for total period are also given for these elements (temperature since 1884, degree days since 1940, rainfall and snow since 1890, wind speed since 1938 and sunshine for each month since 1930 (with a few breaks). *Subject Headings:* 1. Annual meteorological data summaries 2. Comparative climatological data 3. Regina, Saskatchewan.—*M.R.*

7.5-70

551.501.9(711) 551.506.1(711)

\*Canada. Meteorological Div., **Annual meteorological summary, 1954, Vancouver Airport [and] Vancouver City**. [1955] 28+14 p. numerous tables. Looseleaf. Also: **Annual meteorological summary for Vancouver Airport [and Vancouver City]**. 1955. Vancouver, B. C., Meteorological Service of Canada, [1956]. 13+28 p. mostly tables. DWB—The first report contains a history of weather observations at Vancouver Airport, a description of the topography of the location of the stations and of the climate, a list of the instrumentation and a descriptive summary of the weather for 1954 and of the weather for each month. Table gives the monthly means and extremes of the various meteorological variables, the daily temperature, precipitation, snowfall and long term records of the meteorological variables for Vancouver City. A supplement contains an account of the Port Meteorological Office at Vancouver City and data on the individual meteorological variables recorded during 1954. The second report contains standard description of station and summary of data for Vancouver Airport for 1955 with comparative data for 1937-1955 and same for City for 1899-1955 and for 1955. Extreme variations in precipitation within City make consolidation of records inadvisable (average at airport 40", in City 58", and in hilly section of N. Vancouver about 130" a year). The extreme temperature ranges are +2.3°F to 92.4°F. Description of station and surroundings, climate and month by month summaries of 1955 weather for both airport and Port (City) are very complete. Data tables of month-by-month precipitation, snow, temperature etc. are also very extensive. (For 1951 summary, see 3.10-42, Oct. 1952, *MAB*.) *Subject Headings:* 1. Climatic data summaries 2. Annual meteorological data summaries 3. Vancouver, Canada.—*I.L.D., M.R.*

7.5-71

551.501.9:551.578.4(494)

de Quervain, Marcel; Roche, Andre and Zingg, Th., **The Federal Institute for the Study of Snow and Avalanches**. *World Meteorological Organization, WMO Bulletin*, 3(1):27-28, Jan. 1954. photo. DWB—This Swiss institute with 6 scientists and 8 assistants, located on the Weissfluhjoch (2670 m) performs a remarkable amount of research work on the climatology and mechanics of snow in addition to a routine avalanche warning service. Cold laboratories are provided for basic research. *Subject Headings:* 1. Snow research institutes 2. Avalanche warning service 3. Weissfluhjoch, Switzerland.—*A.A.*

## OBSERVATIONAL DATA

See also *Annual met. summary bulletins* (Canada. Met. Div.), 7.5-69; *Annual met. summaries* (Canada. Met. Div.), 7.5-70; *Marine observation* (Roll), 7.5-79; *Radiation flux measurem.* (Houghton, Brewer), 7.5-142.

7.5-72

551.506:551.57(058)

\**Annuaire Hydrologique de la France d'Oùtre-Mer, année 1952.* [Hydrological annual for Overseas France, 1952.] Paris, Office de la Recherche Scientifique et Technique Oûtre-Mer, 1954. 413 p. figs., tables. DWB—This yearbook contains data from 73 stations as against 46 in 1951 yearbook) in French West and Central Africa, etc. Monthly mean maximum and minimum temperatures are given for 1952 and for period of record for about 60 stations in Mauritania, Senegal, Sudan, Nigeria, Guinea, Ivory Coast, Haute-Volta, Dahomey, Togo, French Equatorial Africa, Cameroons, Madagascar, Reunion, Guadeloupe, Martinique and Guiana. Monthly and annual, or annual precipitation data are included for most stations. Several scientific articles on Evaporation; the Intertropical Front, Precipitation and Runoff in French colonies are included and are abstracted separately (contents listed in *MAB*, (7):1052, July 1955). *Subject Headings:* 1. Hydrometeorological data 2. Hydrology yearbooks 3. French Overseas colonies 4. French Africa. I. Société Hydrotechnique de France 4. Electricité de France.—*M.R.*

7.5-73

551.506.1(415/9)

\*Eire. Meteorological Service, *Monthly Weather Report, 1948-?* Latest issue seen, Jan. 1956. numerous tables. Issued in parts, in one binding, separately paged. DWB—Recent issues contain in Pt. I: 1) Summary of weather during the month (pressure, wind, temperature, sunshine, precipitation, fog and thunderstorms). 2) Observational data on temperature of air, grass and earth (at 2, 4, 8, 12, 24 and 48" depths), rainfall, weather and sunshine for 50 places in Ireland; 3) Summary of observations at fixed hours (pressure, dry and wet bulb, vapor pressure and relative humidity, cloud amount, wind force and direction) for 15 stations; 4) Visibility data for various fixed hours at 12 airports; 5) Summary of autographic wind records for 9 places. Pt. II gives rainfall in mm, and as per cent of average for 1881-1915 at several hundred stations in the 25 counties; Pt. II, hourly values of pressure, temperature, relative humidity, rainfall and sunshine, wind direction and speed for 7 stations; Pt. IV, aeronautical data (ceiling, visibility and wind frequency data, etc.), for Dublin and Shannon airports; and Pt. V, upper air pressure, height, temperature and relative humidity and radar wind data for each day for standard surfaces or significant points for Valentia Observatory, Ireland. (For summary of earlier issues, see 3.11-40, Nov. 1952, *MAB*.) *Subject Headings:* 1. Observational data 2. Monthly data bulletins 3. Airways climatic data 4. Radiosonde data 5. Rawin data 6. Ireland 7. Valentia, Ireland.—*M.R.*

7.5-74

551.506.1(728.4) 551.582.2(728.4)

\*El Salvador. Centro Nacional de Agronomía. Sección de Meteorología, *Informe anual, 1948-1949.* [Annual Report, 1948-1949.] 2 pieces (each, separated sheets from unidentified source). tables. DWB—Monthly and annual values of sunshine, wind, pressure, rainfall, temperature, humidity and vapor pressure for San Andrés, Santa Tecla, and Santa Cruz Porrrillo in El Salvador for 1948-49 are given in tables and discussed briefly. Comparative data for rainfall from 1944-48 are also given. A histogram shows annual variation in monthly mean precipitation for 1944-48, followed by a discussion thereof. *Subject Headings:* 1. Climatic data 2. Climate of El Salvador 3. El Salvador.—*M.R.*

7.5-75

551.506.1(485)

\*Uppsala. Universitet. Meteorologiska Institutionen, *Bulletin mensuel de l'Observatoire Meteorologique.* [Monthly bulletin of the Meteorological Observatory.] vol. 85, 1953. pub. Uppsala, 1955. 76 p. entirely tables. DWB, DLC—A collection of 12 monthly reports and 2 pages of annual summary of basic meteorological data, including hourly pressure, temperature, cloudiness, precipitation, wind and hydrometeors. *Subject Headings:* 1. Annual meteorological data summaries 2. Observational data 3. Monthly data bulletins 4. Uppsala University, Sweden. I. Köhler, Hilding.—*M.R.*

7.5-76

551.506.3 (261):551.507

\*Hay, R. F. M., Five year means of meteorological observations made at the ocean weather stations Item and India, Jig and Juliett, 1948-52, *Great Britain. Meteorological Research Committee, M.R.P.* 923, July 30, 1955. 22 p. 13 tables, 4 refs. Mimeo. DWB—Monthly 5 year averages at Stations I (mean position 59°29'N, 19°29'W) and J (53°6'N, 19°25'W) are tabulated and discussed. Tables include mean wind velocity (with other windy stations for comparison showing that averages of 17.7 and 18.3 kn were exceeded only by Adélie Land) wind frequencies by direction and force, pressure, air and sea temperature, days of phenomena, frequencies of visibility and low cloud height. Some values of diurnal variation are included. *Subject Headings:* 1. Weather ship data 2. Marine meteorological data 3. North Atlantic.—C.E.P.B.

7.5-77

551.506.8:551.583.2 (5)

Arakawa, Hidetoshi (*Met. Res. Inst., Tokyo*), Twelve centuries of blooming dates of the cherry blossoms at the city of Kyoto and its own vicinity. *Geofisica Pura e Applicata*, Milan, 30(1):147-150, Jan./April 1955. 3 tables, 2 refs. MH-BH—Blooming dates of the cherry blossoms at the city of Kyoto (old capital of Japan) and its own vicinity are given in chronological order extending over twelve centuries. Examination of this documentary evidence in Japan shows a long period from 11th century until 14th century colder than the average while the years since have been characterized by earlier blooming even though there is a definite sequence of fluctuation between late and early ones. *Subject Headings:* 1. Cherry blossom phenology 2. Historical climates 3. Kyoto, Japan.—Author's abstract.

## INSTRUMENT CARRIERS

See also: Radar wind comparisons (Harrison), 7.5-66; Marine met. observations (Hay), 7.5-76.

7.5-78

551.507.1:551.584.4

Berger-Landefeldt, U. (*Berlin-Charlottenburg Tech. Univ.*), Der Pflanzenklima-Messwagen [Plant climate measuring truck.] *Geofisica Pura e Applicata*, Milan, 30(1):195-204, Jan.-April 1955. 3 figs., 10 refs. English summary p. 195. MH-BH—The use of modern measuring instruments and methods in the field requires a suitable field laboratory with facilities for either physical or chemical research work. For this purpose a Combi-Volkswagen was fitted out accordingly to be used as a plant climate measuring car; and the pertinent description is here given in detail. *Subject Headings:* 1. Mobile weather stations 2. Plant climate measuring truck.—Author's abstract.

7.5-79

551.507.2:551.506 (261)

Roll, H., Fischereischutzboot "Meerkatze": ein Rückblick auf die ersten 50 Reisen [Fishery protection boat "Meerkatze." Looking back on the first 50 voyages.] *Wetterlotse* No. 94/95:208-215, Nov.-Dec. 1955. 5 figs. DLC—The "Meerkatze" completed her 50th voyage on Nov. 1, 1955 after 5½ years' service in the North Sea, Iceland and Norwegian waters. The frequencies of strong winds, gales and "storm waves" are shown and some figures given of observations made and reported by radio. *Subject Headings:* 1. Marine meteorological observations 2. "Meerkatze."—C.E.P.B.

7.5-80

551.507.321.2:551.558

\*Morasca, Nicola, Le componenti verticali del vento nella libera atmosfera determinate mediante il sondaggio con due teodoliti ed errori dei comuni sondaggi per effetto di tali componenti. [Vertical components of the wind in the free atmosphere determined by sounding with two theodolites and the errors of usual sounding resulting from this component.] *Rivista di Meteorologia Aeronautica*, 13(4):19-25, Oct./Dec. 1953. 3 figs., 2 tables. Italian, French, English and German summaries p. 19-20. MH-BH—Single and double theodolite wind soundings made at 10:35 on 4/28/53 at Palermo Airport (base line of 3725 m) are compared in a number of ways and the trajectory shown on a schematic cross section, indicating that a higher than usual ascent rate occurred the first 6 min. as the balloon approached Mt. Pellegrino.

506 m) and a lower or descending rate on the lee side of the mountain. Errors in speed, altitude and even direction are noted and recommendations made that 2 theodolite runs be used at airports. These would give added information about turbulence, descending winds and vertical motion. *Subject Headings:* 1. Double theodolite soundings 2. Upper air wind measurement 3. Pilot balloon accuracy 4. Vertical wind velocity 5. Palermo, Sicily.

7.5-81

551.507.362:629.19(09)

Rosen, Milton W., *Influence of space flight on engineering and science.* *Nature*, London, 76(4495):1190-1193, Dec. 24, 1955. 8 refs. DWB—A short history of the theory and experiments in space travel, especially rockets, scientific uses of rockets, and artificial satellites. *Subject Headings:* 1. Interplanetary flights 2. Satellite observatories 3. Rockets.—C.E.P.B.

## INSTRUMENTS

*See also:* Instrument manuals (U. S. A. W. S.), 7.5-47; Dew recorders (Hofmann), 7.5-201; Lightning discharge observed by electrostatic fluxmeter (Kitagawa et al.), 7.5-247; Lightning counters (Pierce), 7.5-250; Radio fading instruments (Hirao, Maruyama), 7.5-258.

7.5-82

551.508:581.11 551.508.71

Andersson, Nils Elvir and Hertz, Carl Hellmuth (*both, Fysiska Inst., Lund, Sweden*), *Positive Spitzenentladung als Hygrometer geringer Trägheit.* [Positive point discharges as a hygrometer of small lag.] *Zeitschrift für angewandte Physik*, Berlin, 7(8):361-366, Aug. 1955. 5 figs., 18 refs. DLC—An electrical discharge hygrometer, to be used for accurate and rapid measurements of transpiration from plant leaves into the surrounding air, is described in theory and in detail as to the construction, calibration, properties of the hygrometer and applications. Continuous records made for half an hour to one hour of transpiration from leaves of tomato and *Thunbergia alata*, show the sudden variations occurring when a leaf which has been illuminated for a long period is suddenly cut at its base (sharp rise followed by an even more marked drop in relative humidity of air which issues from orifice of sensitive instrument and variations which occur during normal illumination, respectively). *Subject Headings:* 1. Transpiration meters 2. Electric hygrometers 3. Corona discharge hygrometer 4. Plant transpiration measurement.—M.R.

7.5-83

551.508.21:551.508.822

Albrecht, Hans J. (*Melbourne, Australia*), *A sensitive electronic tele-pyranometer with temperature-compensated capacitance bolometers.* *Geofisica Pura e Applicata*, Milan, 30(1):93-105, Jan./April 1955. 11 figs., 8 refs., 3 eqs. English and German summaries p. 93. MH-BH—The paper deals, in detail, with the writer's principle of a complete electronic telepyranometer system whose remote unit comprises a radiation-sensitive oscillator, a temperature-compensating oscillator, and the transmitting section operating on a frequency equal to the intermediate frequency of the two. As the writer developed this pyranometer especially for airborne use as a radiation radiosonde, the remote unit may be as far as 200 to 1000 mi from the base station, the maximum distance being solely governed by the capability of the transmitting section and by the ionospheric propagation conditions. Comments are also made on the base station for the reception and actual reading of the pyranometer signal. In addition, various applications for the new capacitance bolometer principle are mentioned in anticipation of detailed descriptions of other apparatus based upon the principle, at a later date. *Subject Headings:* 1. Telepyranometers 2. Bolometers 3. Solar radiation instruments 4. Radiosonde pyranometers.—*Author's abstract.*

7.5-84

551.508.21:551.521.12

Andreeva, N. A. and Marshunova, M. S., *Primenenie termoelektricheskikh balansomerov i pirgometrov dlia opredeleniia effektivnogo izlucheniia.* [Application of the thermoelectric balance meter and pyrgeometer to determine effective radiation.] *Meteorologiya i Gidrologiya*, Leningrad, No. 4:46-48, July/Aug. 1955. table, eqs. DWB—It is shown that effective radiation increases with increasing diffuse radiation and the dependence of the former upon

the latter for different latitudes is expressed by an empirical equation and illustrated data are shown in a table. The inadequacy of the diurnal measurements of effective radiation to be sought in the selective sensitivity of the apparatus, the differences in the pyrgeometric and pyrheliometric scales, etc. The characteristics of the balance meter and its use in measuring effective radiation are discussed. *Subject Headings: 1. Pyrgeometers 2. Pyrheliometers 3. Effective radiation.—I.L.D.*

7.5-85

551.508.21:551.508.1

\*O'Connor, T. C. (*Dublin Inst. for Adv. Studies*), **On the measurement of global radiation using black and white atmometers.** *Geofisica Pura e Applicata*, Milan, 30(1):130-133, Jan./April 1955. fig., 2 tables, 6 refs. English and German summaries p. 130. MH-BH—The difference in the evaporation from black and white Livingston atmometers was compared with the global radiation as measured by a Bellani spherical pyranometer. Results show that one unit ( $\text{cm}^3$ ) of difference in the evaporation corresponds to  $20 \pm 3 \text{ cal/cm}^2$  of global radiation. The total of 95 daily values of radiation measured by pairs of atmometers differed from the corresponding Bellani figure by 2.3%. The operation of the atmometers and the accuracy of the results are discussed. The method is considered sufficiently accurate for general climatological purposes. *Subject Headings: 1. Evaporimeters 2. Bellani pyranometer 3. Global radiation measurement.—Author's abstract.*

7.5-86

551.508.21:535.5

Sakayanagi, Yoshimi and Sato, Yoshiki (*both, Inst. for Optical Res., Tokyo*), **Near infrared spectrometer using a plane grating.** *Tokyo. University of Education. Institute for Optical Research, Science of Light*, 3(2):84-89, March 1955. 5 figs., 7 refs. DWB—A near infrared grating spectrometer based on the Littrow mounting is described, in which a PbS cell is used as the detector. The grating has 576 lines/mm and the focal length of the collimating mirror is 60 cm. The amplifier is constructed on the basis of the principle of Wilson's feedback with a total gain of 120 db, and the band-width variable from 100 to 5 cps. The source for the synchronous motor for rotating the chopper is supplied by the output of an RC-oscillator. *Subject Heading: 1. Grating spectrometers.—Authors' abstract.*

7.5-87

551.508.29:551.508.71:551.58

Berger-Landefeldt, U., **Fast recording of temperature and vapour pressure or dew-point.** *Weather*, 10(12):405-409, Dec. 1955. 4 figs., 10 refs. DWB—The Askania high-speed remote control temperature and vapor pressure recorder is described and illustrated. The sensing element includes two dry 0.04 mm platinum wires and two covered by a fine wetted thread. Recording is by galvanometer and is automatically corrected to give vapor pressure or dew point. A specimen record shows numerous fluctuations of temperature and vapor pressure over a period of 10 min. *Subject Headings: 1. Resistance thermometers 2. Dew point hygrometers 3. Micrometeorological instruments.—C.E.P.B.*

7.5-88

551.508.53/4 551.554

Thornthwaite, C. W., **The development of anemometers for observing wind gradients.** *Johns Hopkins Univ. Laboratory of Climatology, Publications in Climatology*, 7(2):271-276, 1954. 4 figs., 2 refs. MH-BH—Difficulties experienced with conventional anemometers are distorted by turbulent fluctuations, stalling at low speeds and varying calibration curves. Careful efforts to overcome these difficulties are described. Same results of concurrent wind profile measurements on adjacent masts are given. *Subject Headings: 1. Anemometers 2. Wind profile measurement.—A.A.*

7.5-89

551.508.72:551.579.4

Gur'ev, A. I., **Gidravlicheskiĭ printsip uvelicheniia masshtaba zapisi urovnei vody.** [Hydraulic principle to increase the scale of registration of water levels.] *Meteorologiya i Gidrologiya*, Leningrad, No. 4:49-51, July/Aug. 1955. fig., 9 eqs. DWB—The author describes an apparatus for measuring evaporation from open reservoirs—namely a floating evaporimeter, the principle of which can be used to determine the variation of water level at a given point or variations in the difference of the levels without the interruption of cumbersome mechanical

devices. The apparatus is described with the aid of a diagram; its physical principles are analyzed mathematically; and the results of experimental tests are presented. *Subject Headings: 1. Evaporimeters 2. Water level variations.—I.L.D.*

7.5-90

551.508.822

Malet, L. M., **The regional comparison of radiosondes at Brussels.** *World Meteorological Organization, WMO Bulletin*, 3(4):154-155, Oct. 1954. Also in: *Ibid.*, 4(2):80-81, April 1955. Photo, diagr. DWB—The first article describes the implementation of Recommendation No. 22 (CIMO-1) of the Commission for Aerology (Toronto, 1953) which became WMO Executive Commission Resolution 50(EC-IV). The Dutch, German Graw H50, American AN/AMT 2 and 4 and British Kew MKII type radiosondes were to be tested at an airfield at Evere near Brussels in Oct. 1954. The French type was not included. The second article describes the various types of radiosondes used in Western Europe and North America which were launched in comparative tests (13 daytime and 16 at night) and checked with radar sets and radio theodolites near Brussels (Evere) on Nov. 5-18, 1954. Final results of the comparison are not yet available, but preliminary examination of the results show that systematic differences exist between the various types. A diagram showing the variations with time of the height of the 100 mb surface as indicated by different instruments and a photo of a launching are included. *Subject Headings: 1. Radiosondes 2. Radiosonde comparisons 3. WMO. Aerology Commission 3. Evere, Belgium.—M.R., A.M.P.*

7.5-91

551.508.822

\*Kitaoka, T. and Matsuyama, T., **Accuracy of Japanese radiosonde**

|   |    |    |    |
|---|----|----|----|
| { | S  | 50 | L  |
|   | or | or | or |
|   | RS | SZ | M  |

  
*Journal of Meteorological Research*, Tokyo, 7(1):16-33, March 1955. 12 tables, 6 refs., eqs. In Japanese; English summary p. 16. DWB. Also in: *Tateno, Japan. Aerological Observatory, Journal*, 5(4):245-259, March 1954. In English. MH-BH—This study contains a statistical analysis of the errors of pressure heights and temperatures at standard levels essential for drawing and analyzing upper charts. Examples of pressure corrections for particular test ascents, the results of twin soundings for each pressure, and temperature comparison of temperature between soundings, etc., are presented in tables. *Subject Headings: 1. Radiosonde errors 2. Radiosonde corrections 3. Japanese radiosondes.—Based on authors' abstract.*

## SYNOPTIC ANALYSIS AND FORECASTING

See also: **Weather forecasting** (Zharkov), 7.5-8; **Long wave theory application** (Graham et al.), 7.5-56; **Fire weather forecasts** (Lindquist), 7.5-57; **Fire weather studies** (Hanna), 7.5-58; **Fire weather studies** (Hanna), 7.5-59; **Mapping the weather** (Levick), 7.5-60; **Discontinuity surfaces analysis** (Emsalem), 7.5-134; **Long range forecasting** (Nagao), 7.5-150; **Forecasting techniques** (Iwata), 7.5-158; **Water supply forecasts** (Strauss), 7.5-217.

7.5-92

551.509(02)

Canada. Meteorological Div., **MANTEC: Manual of technical procedures and practices for forecast office operation.** 1st ed. effective Jan. 1, 1955. Its CIR-2562, 0-42, Jan. 1, 1955. 119 p. forms. Price: \$2.00. DWB—A comprehensive manual for plotting surface, constant pressure, thermodynamic, wind-shear hydrograph, frontal contour, tropopause and other charts; for analyzing most of these as well as pressure change and height change charts; for preparation of charts for facsimile and ozalid reproduction, for constructing surface and upper air prognostic charts, for coding and decoding analyses, and for displaying or issuing charts and weather maps. Symbols, specifications, analyses, and samples of analyzed charts are appended. *Subject Headings: 1. Synoptic chart preparation 2. Forecasters manuals.—M.R.*

7.5-93

551.509.4

Great Britain. Meteorological Office. **Handbook of weather messages**, pt. 1, Transmission schedules and station index numbers. 2nd ed. London, H.M.S.O. 1955. 114 p. 2 figs., mainly tables. At head of t.p. M.O. 510a. GB-MO—Includes transmission schedules for all issues from U.K., including shipping and aviation, Gibraltar, Malta, Cyprus and O.W.I. and J. Station numbers are given for Europe, Middle East, Canada, U.S.A. and Atlantic Islands. *Subject Headings*: 1. Synoptic transmissions 2. Synoptic networks.—C.E.P.B.

7.5-94

551.5(09) 551.509.4

Tannehill, Ivan (U. S. W. B.), **The meteorological year of 1954**. *Weatherwise*, 8(1):3-10, Feb. 1955. 3 photos. DWB—The author mentions some 1954 weather anomalies such as temperature extremes, tornadoes, drought, etc., various events in the development of meteorology such as the start of the Joint Numerical Weather Prediction Project in the United States, preparation of daily synoptic charts for the Southern Hemisphere in South Africa, development of climatic relations in the United States, etc. *Subject Headings*: 1. Progress in meteorology 2. Joint Numerical Weather Prediction Project 3. Southern Hemisphere Project (South Africa).—I.L.D.

7.5-95

551.509.34

Bolotinskaia, M. Sh., **K voprosu ispol'zovaniia 20% amplitudy v kachestve kriteriia otsenki opravdyvaemosti dolgosrochnykh prognozov pogody**. [Utilization of 20% amplitude as a criterion for evaluating the reliability of long range weather forecasting.] *Meteorologiya i Gidrologiya*, Leningrad, No. 1:28-30, Jan./Feb. 1955. table, 3 refs. DWB—For series of observations up to 25 years the 20% amplitude may differ considerably from the mean square deviation. With increasing number of observations new extreme years may appear so that the magnitude of the amplitude may change sharply; the reliability of forecasts changes then independently of the quality of the forecasts. This criterion is not always practical since it demands greater precision but permits forecasts with very large errors. *Subject Headings*: 1. Long range forecasting 2. Forecast accuracy.—I.L.D.

7.5-96

551.509.33

Namias, Jerome, **Long range weather forecasting by high-speed computing methods**. *Science Progress*, 44(173):71-81, Jan. 1956. 3 figs., 3 refs. DWB—Long range forecasters have to deal with time averages rather than individual perturbations. A Northern Hemisphere map of mean 700 mb contours for Jan. 1950, and tracks of 700 mb and sea level heights from Nov.-Dec. 1949 to March 1950 are shown. The movement of 5 day or 30 day centers from map to map is similar to the daily movement of disturbances. The causes are not understood but trends can be estimated in various ways and extrapolated to give a prognostic chart. Vorticity redistribution can be computed by high speed machines, which can also interpret the prognostic charts in terms of weather. *Subject Heading*: 1. Long range forecasting.—C.E.P.B.

7.5-97

551.509.33

Philipps, H., **Az időjárás közepes és hosszabb időtartamú előrejelzésének kérdéseiről**. [Problems of extended and long-range forecasting.] *Időjárás*, Budapest, 58(6):363-372, Nov./Dec. 1954. Russian and French summaries p. 363. Transl. by István Kleszky. DWB—Also: complete German version: **Allgemeine Betrachtungen zum Problem der mittel- und langfristigen Witterungsvorhersage**. *Acta Agronomica*, Budapest, 5(1/2):129-143, 1955. Russian and English summaries p. 142-143. DA—The author critically reviews the long-range forecasting methods hitherto used. He finds that no satisfactory results are obtained from methods based either on exact mathematical-physical principles, those derived from analogy, or from singularities. Some improvement may be expected from a combination of such methods, but especially from large-scale dynamics based on classical theories. The author emphasizes that actual close collective operation is one of the principal conditions of better results. *Subject Headings*: 1. Long range forecasting. I. Kleszky, István (Trans).—Trans. of author's abstract.

7.5-98

551.509.33:551.553.21(54)

†\*Ramdas, L. A.; Jagannathan, P. and Gopal Rao, S. (all, *Met. Office, Poona*), **Prediction of the date of establishment of southwest monsoon along the West Coast of India.** *Indian Journal of Meteorology and Geophysics*, Delhi, 5(4):305-314, Oct. 1954. 4 figs., 6 tables, 23 refs. **DLC**—Dates of establishment of southwest monsoon are tabulated for 1891-1950 for 4 sections of the West Coast of India, and the data analyzed statistically and shown graphically. The variability in time of onset averages about a month between extreme cases, and the standard deviation is about a week. Correlation coefficients work out for 1899-1950 with Seychelles rain (April), Agro winds (first half of May), Darwin pressure (April), S. Rhodesia rain (Oct.-April) and (April), Java rain (Oct.-Feb.), etc. Combinations of these are used to establish a formula and results of calculations from formula are shown graphically for each year (1891-1950) in comparison with actual observation. Only about 7 cases out of 60 were over a week off one way or another. Forecasts for 1951-54 are given and verification discussed. *Subject Headings*: 1. Monsoon forecasting 2. Southwest monsoon onset 3. India. —M.R.

7.5-99

551.509.33:551.509.318

§Topor, N., **A távídőjelzés kutatása a Román Népköztársaságban.** [Research on long-range forecasting in Rumania.] *Időjárás*, Budapest, 58(6):380-396, Nov./Dec. 1954. 34 figs., 2 tables. Russian and French summaries p. 380. Transl. by L. Avjeszky. **DWB**—Also: complete German version: **Die langfristige Wettervorhersage in der Volksrepublik Rumanien.** *Acta Agronomica*, Budapest, 5(1/2):163-186, 1955. Russian and English summaries p. 186. **DA**—In Romania systematic research on long range forecasting was started in 1951 by a small research group. A card file was prepared from Romanian observational data for the period 1889-1951. Sixteen pressure and circulation types were determined on the basis of U. S. Weather Bureau Historic Weather Maps (1889-1939) and Romanian synoptic weather maps (1939-1951). This paper contains a detailed description of the 16 circulation types and their frequency distribution in Europe, with particular reference to their effect on weather in Romania. *Subject Headings*: 1. Long range forecasting 2. Synoptic types 3. Rumania. I. Aujeszky, László (Trans.).—G.T.

7.5-100

551.509.58:551.576.1

James, D. G., **Investigations relating to cirrus cloud.** *Great Britain. Meteorological Research Committee, M.R.P.* 933, Sept. 1, 1955. 10 p. 6 figs., 13 tables, 9 refs. **Mimeo.** **DWB**—Observations of cirrus from aircraft over the British Isles were analyzed for frequency distribution of tops and bases relative to tropopause, heights of base and thickness. Ten cases (in 220) had tops above 40,000 ft. The surface charts, upper air soundings, 1000-500 mb thicknesses, advection vorticity at 300 mb and 300 mb contours were also examined. Cirrus was associated with the area ahead of surface fronts, the high pressure side of the jet stream, thermal ridges, high humidities at 500-300 mb, winds between S and W at 500-300 mb (advection of warm air) and positive cyclonic vorticity at 300 mb. *Subject Heading*: 1. Cirrus forecasting.—C.E.P.B.

7.5-101

551.509.59:551.54

Bontrond, E. A. (*Service Mété. de Metropole et d'Afrique du Nord, Paris*), **Contribution à l'étude d'un problème de prévision barométrique. Rapports des profondeurs de noyaux de variation de pression d'intervalles différents lorsque l'onde de variation ne peut être assimilée à une sinusoïde simple.** [Contribution to the study of the problem of barometric forecasting. Relationships of the depths of the centers of pressure variation of different intervals when the wave of variation cannot be assimilated to a single sine wave.] *Journal Scientifique de la Météorologie*, Paris, 6(22):49-58, April/June 1954. 6 figs., 5 refs., 7 eqs. **DWB**—The French method of barometric forecasting utilizes the relationships existing among the depths of the nuclei of pressure variations at different intervals on the assumption that the wave of pressure variation is a sine wave. This article is a study of the extent to which these relationships are modified when the wave of variation is considered as the superposition of a sine wave variation over a linear variation or as of two sine wave variations of different periods

and amplitudes. *Subject Headings:* 1. Pressure forecasting 2. Pressure variations.—*Trans. of author's abstract.*

7.5-102

551.509.67:514

Jenkinson, A. F., Some statistical aspects of a rain-making experiment. *Great Britain Meteorological Research Committee, M.R.P.* 931, Sept. 14, 1955. 15 p. 18 figs., 13 tables, 7 refs. Mimeo. DWB—The problem is to test results of seeding with silver iodide on Salisbury Plain. The location of the plume and vertical and horizontal extent of effective seeding in cloudy frontal conditions are discussed. From rainfall statistics on 92 selected occasions in 1945-54 it is concluded that if the trials are made with 5 generators on a line of 20-25 miles on suitable occasions, a difference of 13% between rainfall of known seeded and control areas would be significant at 1% level. If the seeded area is not known, a difference of 25-30% would be required. *Subject Headings:* 1. Cloud seeding evaluation 2. Statistical techniques 3. Salisbury Plain, Eng.—*C.E.P.B.*

## STRUCTURE AND PHYSICS OF THE ATMOSPHERE

### ATMOSPHERIC POLLUTION

*See also:* Aerobiology (Cammach), 7.5-51; Freezing nuclei measurem. (Smith et al), 7.5-200; special bibliography on Atmospheric Radioactivity, p. 616.

7.5-103

551.510.42:551.593.55:551.524.4

Bigg, E. K., Detection of atmospheric dust and temperature inversions by twilight scattering. *Nature*, London, 177(4498):77-79, Jan. 14, 1956. 3 figs., 3 refs. DWB—Apparatus was set up at Alice Springs, Australia, for measuring  $dI/Idt$  ( $I$ =red and infrared twilight illumination) for different heights of the earth's shadow. There was a large maximum at 15 km (temperature inversion and dust boundary), and a smaller one near 80 km. This also coincides with a temperature inversion and is attributed to meteor dust, the maxima coinciding with meteor showers. *Subject Headings:* 1. Dust layers 2. Twilight phenomena 3. Upper air temperatures 4. Alice Springs, Australia.—*C.E.P.B.*

7.5-104

551.510.538

Brewer, A. W., Ozone concentration measurements from an aircraft in N. Norway. *Great Britain Meteorological Research Committee, M.R.P.* 946, Nov. 22, 1955. 3 p. 4 figs., 1 ref. Mimeo. DWB—Ascents with a thermometer, dew point hygrometer and ozone sampler were made to 40,000 ft from Trondheim on June 27 and 28 and July 3 and 11, 1955. The results, shown graphically, indicate a 3-fold increase in ozone concentration above the tropopause. *Subject Headings:* 1. Ozone distribution in upper atmosphere 2. Norway.—*C.E.P.B.*

### UPPER ATMOSPHERE-IONOSPHERE

*See also:* Scatter propagation (Norton, Wiesner), 7.5-1; Upper air temp. periodicities (Morton), 7.5-159; Stratospheric winds (Bannon, Jones), 7.5-191; Tropospheric refraction (Tao), 7.5-260.

7.5-105

551.510.534:551.557.3

Dütsch, H. U., Das atmosphärische Ozon als Indikator für Strömungen in der Stratosphäre, I, Die photochemischen Grundlagen. [Atmospheric ozone as an indicator of currents in the stratosphere, Pt. 1, Photochemical basis.] *Archiv für Meteorologie, Geophysik und Bioklimatologie, Ser. A*, 9(1):87-119, 1956. 12 figs., 12 tables, 34 refs., 15 eqs. German; English and French summaries p. 87-88. DWB—A radiation chart is developed for evaluating the number of dissociating photons/cm<sup>2</sup>/sec. With this the ozone distribution, in equilibrium or nonequilibrium, due entirely to photochemical processes is calculated from 15-50 km and 0-80° lat. (summer and winter) using stratosphere temperatures given by rockets and calculated by PENNDORF. These are compared with rocket and balloon measurements of ozone. They show the course of variation to be expected in an atmosphere without meridional or

vertical currents or turbulence. The photochemically induced diurnal variation, and the nocturnal increase in 50–80 km due to secondary  $O_3$  formation from atomic O, are also calculated. *Subject Headings:* 1. Ozone variations 2. Stratospheric winds.—C.E.P.B.

7.5–106

550.385:551.510.535:551.594.13

Wiese, Horst, *Die ionosphärischen Stromwirbel erdmagnetischer Baistörungen.* [The ionospheric ring current of geomagnetic bay disturbances.] *Beiträge zur Geophysik*, Leipzig, 65(1):70–85, 1955. 14 figs., 19 refs., 6 eqs. DWB—The course of various bay disturbances is generalized synoptically. There are wandering whirls, roughly analogous to the electric dipole postulated by FUKUSHIMA (1953). Given the latitude of the dipole the geomagnetic longitude of the dipole can be calculated from the disturbance at any place. For 64 bay disturbances investigated in this way a position and direction of motion of the dipole was found, dependent on the time of day. Deviations of the bay current system from the dipole system can be minimised by assuming an additional  $S_V$  field. In contrast to the dipole there is also outside the auroral zone a ring-like band of increased current density. Possible origins of bay disturbances are considered. *Subject Headings:* 1. Geomagnetic disturbances 2. Ionospheric currents.—*Transl. of author's abstract.*

## MECHANICS AND THERMODYNAMICS OF THE ATMOSPHERE

See also: Dynamics of atmos. (Sutcliffe), 7.5–119; Atmos. radiation measurem. (Roach), 7.5–139; Solar energy transformation (Budyko), 7.5–141; Mean winter and summer isobaric field (Mironovitch), 7.5–169; Moisture exchange in atmos. (Budyko, Drozdov), 7.5–193.

7.5–107

551.511:551.554

Arkhangel'skiĭ, V. L., *O vysote urovnia treniia v usloviakh srednegornogo rel'efa.* [The height of the friction level in hilly country.] *Meteorologiya i Gidrologiya*, No. 2:26–28, March/April, 1955. 3 tables, 4 refs. DLC—Pilot balloon observations from various points of eastern Siberia were used to determine the height of the friction level in a region of moderately high mountains. The friction layer was taken as the height at which the increase in wind velocity diminishes and the rotation of the wind to the right ceases. It is shown that most frequently friction is most effective at a height of 750–900 m and that the mean coefficient of exchange in the friction layer in the moderate latitudes of eastern Siberia is 50 g/cm sec. *Subject Headings:* 1. Friction layer 2. Wind profiles 3. Orographic influences 4. Eastern Siberia.—I.L.D.

7.5–108

551.511:551.513.1

Böhme, W. (*Met. and Geogr. Inst., Humboldt Univ., Berlin*), *Die Abhängigkeit der charakteristischen Größen einer thermisch bedingten Zirkulation von den die näheren Umstände beschreibenden Parametern im Falle gewisser quasistationärer Zirkulationen.* [Dependence of characteristic magnitudes of a thermally induced circulation upon parameters describing the more immediate conditions in the case of certain quasi-stationary circulations.] *Zeitschrift für Meteorologie*, 8(10):289–303, Oct. 1954. 3 tables, 13 refs., 97 eqs. DWB—As in the previous paper (see 6.1–123, Jan. 1955, *MAB*), the author considers circulations which are produced in a resting and isothermal atmosphere by periodic heat sources distributed periodically at the earth's surface. An approximate solution is presented for these cases where a transition from a nonstationary periodic solution to a quasi-stationary (periodic) solution is possible and where simultaneously the factor  $W/H$  can be neglected over against  $D_2W$ . Formally this transition is allowed by neglecting the local time observations from the initial differential equations. The quasi-stationary time dependent solution simply represents a series of stationary states so that the thermally produced circulation can be treated theoretically with the aid of large scale exchange in circulations having cells of large horizontal extension, the transition of Guldberg-Mohn friction to turbulence friction, considerations of the spherical stage of the earth, etc. *Subject Headings:* 1. Atmospheric circulation theory 2. Dynamic meteorology 3. Quasi-stationary circulation.—I.L.D.

7.5-109

551.511:551.552

\*Businger, J. A.. On the structure of the atmospheric surface layer. *Journal of Meteorology*, 12, 6:553-561, Dec. 1955. 3 figs., 2 tables, 22 refs., 35 eqs. DWB—Starting with L. PRANDTL's theory of mixing length, leading to the logarithmic wind profile, the work of G. HAMEL, etc., the 2 equations of transfer of momentum and heat are reduced to forms containing 3 unknowns,  $K$ ,  $\bar{u}$  and  $\bar{\theta}$ . The possibility of finding the necessary third equation is approached by introducing a nondimensional stability number. This is tested by wind profiles for various stabilities observed by N. E. RIDER. *Subject Headings*: 1. Turbulence in the frictional layer 2. Wind profile theory.—C.E.P.B.

7.5-110

551.511:551.552

Demiańczuk, P. P.. Nota odnośnie rozwiązania całki określającej pionową energię chwiejności powietrza. [A note concerning the solution of the integral determining the vertical energy of air instability.] *Poland. Państwowy Instytut Hydrologiczno-Meteorologiczny. Wiadomości Stałej Hydrologicznej i Meteorologicznej*, 3, 4:297-302, 1954. figs., 3 tables, 14 eqs. Russian and French summaries p. 301-302. DLC—A highly theoretical paper in which, after having questioned the correctness of the solution of the integral determining the vertical energy of air instability introduced by T. KOPCIEWICZ in his book *Physics of the Atmosphere*, the author presents a general solution of the integral, as well as two special solutions resulting from the general solution. The first of them pertains to the case of division of the air surface comprised between the actual curve and the curve of virtual temperature for moist air in layers of 100 mb thickness, by interval lines crossing the isobars 1000 mb, 900 mb, 800 mb, etc. The second solution has a very simple mathematical form and can be easily solved on a thermodynamic diagram. *Subject Headings*: 1. Instability criteria 2. Integral equations.—A.M.P.

7.5-111

551.511:551.576.2:551.5777

Davedal, T.. Relation between horizontal advection, total amount of cloudiness and precipitation. *Archiv für Meteorologie, Geophysik und Biometeorologie, Ser. A*, 9(1):19-21, 1956. 7 tables, 6 refs. German and French summaries p. 19-20. DWB—At Stockholm and Letchars, 1952-53, horizontal advection was computed from winds at 950 and 500 mb and compared with cloud amount. It is found that overcast sky and precipitation are usually but not always associated with advection of warm air, little or no cloud with cold air. Therefore warm air advection or cold air above warm air usually implies ascent, cold air or warm air above cold air, subsidence. The relation is less marked in summer than in other seasons. *Subject Headings*: 1. Tropospheric advection 2. Advection effects on cloudiness.—C.E.P.B.

7.5-112

551.511:551.552

Estoque, Mariano A. *Johns Hopkins Univ.*, The spectrum of large-scale turbulent transfer of momentum and heat. *Tellus*, Stockholm, 7, 2:177-185, May 1955. 4 figs., 1 table, 13 refs., 27 eqs. DLC—A method for obtaining the spectrum of turbulent transfer of a fluid property is presented based on cross-correlations and Fourier transforms. An application to large-scale eddy transfers of momentum and heat at 850 mb over the southeastern part of the United States shows that most of the transfers may be attributed to disturbances of periods from 0 to 10 days, the most important transfers occurring in the neighborhood of 4 days. Some implications of these results on the problem of the general circulation are discussed. *Subject Headings*: 1. Turbulent transfer of heat 2. Turbulent transfer of momentum 3. Turbulence spectrum.—Author's abstract.

7.5-113

551.511:523.74:538.7

Lehnert, B. *Royal Inst. of Techn., Stockholm*, Magnetohydrodynamic waves under the action of coriolis force, Pt. 2. *Astrophysical Journal*, Chicago, 121, 2:481-490, March 1955. 7 refs., 72 eqs. DLC—The phase velocity of a single plane magnetohydrodynamic wave in a rotating liquid is independent of the amplitude. The nonlinear interactions between the components of the spectrum of a complex traveling disturbance vanish only in a nonrotating fluid without dissipation. A criterion for the approximate validity of the principle of superposition is given for small values of the Coriolis force and the dissipation. In a rotating

medium in a magnetic field a disturbance will not necessarily travel along the magnetic field lines. The anisotropic group velocity for a wave packet is given. In solar physics the effect of anisotropic dispersion and nonlinearity are significant for disturbances with wave lengths of the order of a hundredth of the solar radius, if a dipole field with a polar strength of less than 5 gauss is assumed. *Subject Headings:* 1. Magneto-hydrodynamic waves 2. Coriolis force. —*Author's abstract.*

7.5-114

551.511:551.515.11

Raethjen, P., **The five types of vorticity-variation and cyclogenesis.** *I.U.G.G. Association of Meteorology, Brussels, 1951. Proces-Verbaux des Séances. Mémoires et Discussion.* 78-80. pub. Brussels, Dec. 1953. eqs. DWB—Applying BJERKNES' circulation theorem and STOKES' integration theorem and assuming a nearly geostrophic wind, the author derives an equation for the change of relative vorticity with time, which shows five components due to variations in latitude, horizontal convergence, frontal shear, gliding exchange and vertical wind gradients. All components contribute to cyclogenesis. *Subject Headings:* 1. Cyclogenesis 2. Vorticity equations.—A.A.

7.5-115

551.511:551.521

Robinson, G. D., **The energy balance of surface and atmosphere at Kew, May 1953 to April 1954.** *Great Britain. Meteorological Research Committee, M.R.P.* 929, Sept. 10, 1955. 48 p. 3 figs., 6 tables, 24 refs. Mimeo. DWB—Trial measurements from the ground of the radiation flux over the whole atmosphere were made in preparation for the International Geophysical Year. Determination of the albedo (photometric, visual and UV, and infrared) under various assumptions as to absorption, etc. gave estimates of: year 0.475, summer 0.46, winter 0.525. Terrestrial radiation at the limit of the atmosphere is set at  $20 \pm 3$  mw.  $\text{cm}^{-2}$ . Terms in the energy budget are computed for year, summer and winter. It is concluded that measurements during the I.G.Y. can be made with useful accuracy, which can be improved by measurements in the air, but in view of the year-to-year variations some stations should operate for at least 5 yrs. *Subject Headings:* 1. Energy balance 2. Kew Observatory, London. —C.E.P.B.

7.5-116

551.511:551.552

Sawyer, J. S., **Dynamical similarity in an incompressible fluid model of two-dimensional airflow over a ridge.** *Great Britain. Meteorological Research Committee, M.R.P.* 935, Sept. 16, 1955. 7 p. 3 refs., 21 eqs. Mimeo. DWB—To overcome the difficulty that air is compressible, to simulate a flow of air over a range of hills a model is examined in which an incompressible fluid flows through a narrow channel tapering upwards. *Subject Heading:* 1. Air flow models.—C.E.P.B.

7.5-117

551.511:523.72

Skumanich, Andrew (*Princeton Univ. Observ.*), **On thermal convection in a polytropic atmosphere.** *Astrophysical Journal*, Chicago, 121(2):408-417, March 1955. 3 figs., 4 tables, 2 refs., 21 eqs. DLC—Thermally induced convection is investigated in an atmosphere with a strong density variation from top to bottom, such as is found in the hydrogen convection zone of the sun. The atmosphere is assumed to be initially stratified in horizontal planes and to follow the polytropic law,  $P\alpha\rho^\Gamma$ . Viscosity and heat conduction are ignored, the perturbations are assumed to be adiabatic, and the perturbation equations are linearized. It is found that in a polytropic atmosphere—in contrast to the classical case of a homogeneous atmosphere—the speed of development of a perturbation increases persistently with decreasing horizontal wave length of the perturbations, even for wave lengths shorter than the thickness of the atmosphere. Thus in the solar hydrogen convection zone, small element sizes are to be expected to predominate. *Subject Headings:* 1. Convection 2. Solar atmosphere.—*Author's abstract.*

7.5-118

551.511

Wippermann, F., **Numerische Untersuchungen zur zeitlichen Änderung der Spektralverteilung kinetischer Energie für eine zweidimensionale, divergenz- und reibungsfreie**

**Strömung.** [Numerical investigations of the time-change of the spectral distribution of kinetic energy for a two-dimensional, divergence- and friction-free current.] *Archiv für Meteorologie, Geophysik und Bioklimatologie, Ser. A*, 9(1):1-18, 1956. 9 figs., table, 7 refs. 12 eqs. German, English and French summaries p. 1-2. DWB—Changes of the wave length spectrum of kinetic energy are calculated by a process of step integration of the vorticity equation, using a latitude zone between 22.8° and 79.4°N, and beginning with several arbitrary distributions. The energy is provided by the potential energy of cyclones and anticyclones and dissipated at the short wave end. After about 4 days a double maximum appears, in agreement with CHARNEY's observations. Energy transfer oscillates between basic currents and disturbances in a period of 3½-4 days. *Subject Heading: 1. Kinetic energy spectrum of atmosphere.—C.E.P.B.*

## GENERAL CIRCULATION

*See also: Atmos. circulation theory (Böhme), 7.5-108.*

7.5-119

551.513:551.514

Sutcliffe, R. C., **Large-scale weather processes.** *Nature*, London, 177(4499):113-114, Jan. 21, 1956. DWB—Summary of 3 lectures. He first described 3-dimensional structures including the upper air pressure field and jet streams. He then turned to variability in middle latitudes, divergence and vertical motion. The direct approach through divergence is impracticable but the dynamics can be built up through vorticity. This led to the conception of large-scale instabilities and exponential growth of disturbances as the normal state of the atmosphere. The third lecture dealt with problems of the general circulation, balance of heat, water and momentum, and mechanism, including the relative importance of steady mean circulations and irregular motions. *Subject Headings: 1. Atmospheric circulation 2. Dynamics of the atmosphere.—C.E.P.B.*

7.5-120

551.513.1:551.542

\*South Africa. Weather Bureau, **Southern Hemisphere Project**, Sept., Oct., Nov., 1953. **Tables, diagram and charts.** Its *Notos*, 3(4):294-362, 1954. DWB—Usual extensive tabulation of daily and monthly mean sea level pressure for 10° long strips 0-350°E at lat. 15°, 20°, 25°, 30°, 40°, 45°, 50°, 55°, 60°, 65° and 70°S; mean monthly geopotential of 500 mb surface; mean monthly 1000-500 mb thickness; daily sea level zonal index and meridional index; plus monthly and seasonal mean charts for Southern Hemisphere of sea level pressure (with inset showing meridional profile), 500 mb geopotential and 1000-500 mb thickness. The project was organized by the South Africa Weather Bureau and combined with M.I.T. Southern Hemisphere Project in 1953(?). *Subject Headings: 1. Southern Hemisphere Project (South Africa) 2. Monthly mean pressure charts 3. Meridional profiles 4. Zonal index.—M.R.*

7.5-121

551.513.2:551.557(567, 62)

Harding, J., **The profile of jet streams in the Middle East.** *Great Britain. Meteorological Research Committee, M.R.P.* 932, Aug. 31, 1955. 11 p. 16 figs., 4 refs. Mimeo. DWB—Ground photos from airplanes between Habbaniya and Bahrain, Port Said and Wadi Halfa and air speed gave wind direction and speed. Eleven "Windy Runs" are discussed. "The strong westerly winds over the Middle East in winter, at heights approximating to those of maximum wind speeds, contain a belt of very strong winds which may be as wide as 200 nautical miles or more, and in which horizontal gradients of wind speed are small or negligible." Surface and 200 or 300 mb charts and wind profiles showing winds of 100-200 kn are given for Jan. 28 and Feb. 6, 1953, Jan. 16 and Feb. 25, 1954 and March 5, 1955. *Subject Headings: 1. Jet stream profiles 2. Iraq 3. Egypt.—C.E.P.B.*

7.5-122

551.513.2:551.557(266)

Hoyle, H. D., **The sub-tropical jet-stream of the eastern North Pacific in January and April 1952.** *Great Britain. Meteorological Research Committee, M.R.P.* 924, June 28, 1955. 8 p. 16 figs., 8 refs. Mimeo. DWB—A thorough analysis is made of the 2 jet streams in the N. Pacific. Daily schematic charts, 60-15°N, 180-120°W show the positions of jets (> 100 kt) at 300-400 mb near the polar front and 200 mb 1000 mi south. Vertical cross sections in

10-150°W show (by isovels, isotherms and fronts) 3 types of probable structure (strong W-E jet near Hawaii, weaker jet with N component, and subtropical jet displaced northward). The 250 or 300 mb and 60 mb isotherms, contours of various surfaces, and mean surface isobars are also plotted as means for month and for different types. The jets show pronounced meander and are associated with 3 tropopause levels, tropical (90 mb), subtropical (200 mb) and polar (300 mb). *Subject Headings: 1. Jet stream variations 2. Subtropical jet stream 3. Pacific jet stream 4. Eastern Pacific.—C.E.P.B.*

7.5-123

551.513.2:551.557:629.13

**The jet stream.** *New York Times Magazine*, Section 6, p. 40, Jan. 2, 1955. DWB—A concise summary of the nature and cause of the jet stream and its use in Pacific and Atlantic air navigation. The Atlantic jet stream is said to be too irregular for much aid in flying, though the Pacific jet has proved to be very useful in eastbound flights from Tokyo. *Subject Headings: 1. Jet stream flying 2. Atlantic jet stream 3. Pacific jet stream.—M.R.*

7.5-124

551.513.2:551.557

\*Serebreny, Sidney: Wiegman, Eldon J. and Carlson, Wilbur F., **Characteristic properties of the jet stream over the Pacific, Case history No. 1, Pt. 2.** Pan American World Airways. Pacific-Alaska Div. Meteorology Dept., Contract N189s-96835, Technical Report, No. 4, Sept. 1954. 161 p. 66 figs. (1 fold.), 12 refs. Also their: **Characteristic properties of the jet stream over the Pacific, Case history No. 2, Pt. 2.** *Ibid.*, Technical Report, No. 3, Aug. 1954. 157 p. 66 figs. (1 fold.), 4 tables, 14 refs. DWB—These two elaborate case history studies (Case I for a high index and Case II for a low index case) cover the periods Feb. 7-15, 1953, and Feb. 25-March 5, 1953, respectively. The Polar Front model of BERGGREN (1953) is verified in analyses of surface, 300, 200 and 100 mb level for the Pacific area. The Polar front is shown to reverse itself above 250 mb level equatorward. Absence of horizontal temperature gradients at the Jet Stream core and stable lapse rates south of the Polar Jet are noted. The trajectories of the Polar and Subtropical Jet across the Pacific are noted and soundings, isotach and other charts used to illustrate these movements. Periodic intrusions of Polar air from Siberia were shown to reinforce and sustain the Polar Jet Stream at relatively low latitudes as far east as Midway during the period Feb. 7-15. *Subject Headings: 1. Pacific jet stream 2. Polar fronts 3. Pacific Ocean.—From authors' abstract.*

7.5-125

551.513.2:551.557

\*Serebreny, Sidney M. (*Pan American World Airways*), **The jet stream structure over the Pacific.** *Navigation*, Los Angeles, 4(6):231-241, June 1955. 10 figs., 2 tables. DLC—A table gives location, temperature, wind and D-values for 8 positions of a PAA trip on Feb. 3, 1954 at 25,000 ft. from 150°E to 161°W, showing a broad band over 720 miles wide (12°) with winds 106 to 132 kn. The Polar Jet stream (as distinct from the sub-tropical or Arctic jet stream) is the most concentrated. In this region (the zone of Maximum Concentration) which is called the ZOMCOT is designated by the area at 500 mb where temperature is from 3° warmer to 7° colder than the standard temperature for the level. On Feb. 10, 1953 a change in wind speed of 55 kn in 24 miles on the north side was reported at 22,000 ft (temperature change was 11°C), whereas similar data for Feb. 15, 1953 shows a more gradual change (2°C and 35 knots in 90 mi). On Dec. 28, 1954, a complete log (shown in tables and cross section as well as on a chart) gave a change of 100 kn (185 to 85 kn) in 1,000 ft elevation (23.2 to 24.2 thousand feet) but only 2°C change in temperature although D-value changed from 275 to 925. The Polar Jet is wider the higher you go, reaching a maximum from 35 to 40 thousand feet and diminishing above 45,000. Turbulence is more intense above than below the core, and in strong than weak gradients, or winds. The wind shear is also much greater above than below the core. Several schematic models of jet stream features are included. *Subject Headings: 1. Jet stream structure 2. Jet stream navigation 3. Western North Pacific.—M.R.*

7.5-126

551.513.2:551.557:656.7(265)

Stieflemaier, C. A. (*Pan American World Airways*), **Operational aspects of the jet stream.** *Navigation*, Los Angeles, 4(6):227-231, June 1955. fig. DLC—On the Tokyo-Honolulu air

route, Pan American pilots use several specially designated routes to make the best use of the westerly jet stream when it is present. The pilot can locate the jet stream by watching carefully the readings from a vortex thermometer which tells him when he encounters a sudden change in temperature at a given level, thus allowing him to change course slightly so as to stay in the jet. By so doing, tail winds up to 150 kn are frequently employed to save 5 hr (average) flying time from Tokyo to Honolulu in 220 flights, or a saving of half a million dollars, not to mention time saved. Details of analysis and flight planning as well as of navigation are touched on in this article. *Subject Headings: 1. Jet stream navigation 2. Air navigation 3. Tokyo-Honolulu air route.—M.R.*

7.5-127

551.513.2:551.513.3

Wolff, Paul M., **Quantitative determination of long waves and their time variations**. *Journal of Meteorology*, 12(6):536-541, Dec. 1955. 10 figs., 11 refs. DWB—Averaging data from hemispherical 500 mb contours over 20° diamonds was found to be the best way to separate long and short waves. Specimen space-mean charts and isopleths of 24-hr changes (total long wave, short wave) are given. A method of quantitative perturbation analysis is described. *Subject Heading: 1. Waves in the westerlies.—C.E.P.B.*

### ATMOSPHERIC DISTURBANCES

See also: **Vorticity-variation & cyclogenesis** (Raethjen), 7.5-114; **Waves in the westerlies** (Wolff), 7.5-127; **Wind & storms** (Currie), 7.5-172.

7.5-128

551.515.3

Gião, Antonio, **Relations entre le creusement et le comblement des perturbations et leur déplacement**. [Relations between the deepening and filling of disturbances and their displacement.] *Geofisica Pura e Applicata*, 28:171-189, 1954. 4 figs., 2 tables, 2 refs, numerous eqs. MH-BH—The deepening and filling (development) of a function  $p(\varphi, \lambda, t)$  of time  $t$  and the points  $(\varphi, \lambda)$  of a regular closed surface  $\sigma$  is first of all defined, in respect to a given advection or transfer velocity field  $\vec{H}\sigma(\varphi, \lambda)$  tangent to  $\sigma$ , as the variation of  $p$  on any fictitious particle moving constantly and everywhere with the velocity  $\vec{H}\sigma$ . For a given  $p(\varphi, \lambda, t)$  and to any  $\vec{H}\sigma$  there corresponds a well defined development field  $\mathfrak{C}(\varphi, \lambda, t)$  with certain restrictions. A general formula of the differential geometry and kinematics of  $p(\varphi, \lambda, t)$  is then derived, giving the velocity of any center and col of a  $p(\varphi, \lambda, t)$  as a function of the advection vector  $\vec{H}\sigma$  and the corresponding development field  $\mathfrak{C}(\varphi, \lambda, t)$ . This formula can be transformed and takes the form of a general relation between the deepening (and filling) of a center (or a col) of a  $p(\varphi, \lambda, t)$  and its displacement velocity, the advection vector  $\vec{H}\sigma$  appearing no more explicitly. A detailed analysis of the consequences of these formulas is then given for the following cases: 1) circular perturbations in the vicinity of a center; 2) perturbations having, in the vicinity of a center, an axis of symmetry normal or tangent to the velocity of the center; 3) normal evolution of the tropical cyclones. Finally, the relations between the development  $\mathfrak{C}(\varphi, \lambda, t)$  of a field  $p(\varphi, \lambda, t)$ , the advection velocity vector  $\vec{H}\sigma$  and the configuration of the iso-lines in the vicinity of a center are analyzed. Theoretical results give a rational explanation of several well known properties of the behavior of the perturbations in different geographic regions. *Subject Headings: 1. Cyclone development 2. Cyclone dynamics.—From author's summary.*

7.5-129

551.515.3(862):551.509

Alpert, Leo (*Capitol Res. and Dev. Corp., Arlington, Virginia*), **Panama tornadoes**. *American Meteorological Society, Bulletin*, 36(4):171-172, April 1955. 3 figs. DWB—With the aid of photographs, the author describes two tornadoes observed by him in Panama on June 10, 1943 and in July 1942. The rainfall in both cases was behind the tornado clouds. The "collar" phenomena was not observed. *Subject Headings: 1. Tornado observation 2. Panama.—I.L.D.*

7.5-130

551.515.33(767)

\*Asp, M. O. (*U. S. W. B., Little Rock, Arkansas*), **Tornado paths in Arkansas**. U. S. Weather Bureau, Nov. 10, 1954. 2 p. Typescript. Fig. 1: Headrick, W. E., [Map of] **Tornado paths in Arkansas, 1829-1952**. DWB—Large chart showing tornado paths for 1829-1900, 1901-1940 and 1941-1952, respectively, was prepared by W. E. HEADRICK, cartographer of the Arkansas Highway Department. Data were obtained from plots of Federal Land Surveys from 1815-date (mostly 1830-1859). Recent data (1946-1952) was obtained by direct surveys made by the Arkansas Highway Department. Most data were obtained from timber falls from  $< \frac{1}{4}$  mi to 1 mi wide. General direction is SW to NE. Only longer paths are shown on map; in the NW part of state paths are mostly from NW to SE with sharp recurvature (in mid-state) toward NE. *Subject Headings: 1. Tornado track charts 2. Long period records 3. Arkansas.*—M.R.

7.5-131

551.515.4:551.579.4(53)

Thomas, A. C., **Thunderstorm at Sharjah on November 14, 1954**. *Meteorological Magazine*, London, 84(1001):355, Nov. 1955. 2 photos. DWB—A storm of hail and rain on this Arabian airfield gave 2.21" in 45 min. Photos of flooding are shown. The average annual rainfall is 4.61". *Subject Headings: 1. Thunderstorms 2. Floods 3. Sharjah, Arabia.*—C.E.P.B.

7.5-132

551.515.41

Douglas, C. K. M., **Night storms and some related diurnal effects**. *Weather*, 10(10):356, Oct. 1955. DWB—Description of synoptic conditions of Cannington storm of Aug. 18, 1924, when over 9" of rain fell in cold air. Sea was warmer than air and convection extended to high levels. Further inland afternoon weather in such conditions is fine and warm. *Subject Heading: 1. Thunderstorm dynamics.*—C.E.P.B.

7.5-133

551.515.71:551.521.64:523.74

Péczely, György, **Az anticiklonok felépülésének kérdése kapcsolatban a naptevékenység változásáival**. [On the structure of anticyclones in relation to the variations of solar activity.] *Időjárás*, Budapest, 58(6):407-417, Nov./Dec. 1954. 11 figs., 5 refs. Russian and French summaries p. 407. DWB—Also: complete German version: **Über den Zusammenhang zwischen dem Aufbau der Antizyklogen und den Änderungen der Sonnentätigkeit**. *Acta Agronomica*, Budapest, 5(1/2):201-218, 1955. Russian and English summaries p. 217-218. DA—The development of polar, Azorean and Scandinavian anticyclone systems and their connections are investigated. The effect of polar anticyclones on the regeneration of Azorean anticyclones and in turn on the development of Scandinavian anticyclones is discussed in each phase of the process. The results are applied to extended forecasting. A correlation is found between the intensity of polar anticyclones and solar corpuscular radiation. During magnetic disturbances accompanying corpuscular streams the temperature increases over the magnetic pole. This temperature increase propagates from the pole concentrically. At the same time the surface pressure increases and eventually sets off the outbreak of cold air from the Arctic Basin. *Subject Headings: 1. Polar outbreaks 2. Anticyclone structure 3. Corpuscular radiation 4. Solar activity.*—*Trans. of author's abstract.*

7.5-134

551.515.8:551.509.31

§Emsalem, René, **Pour la mise en évidence de surfaces de discontinuité au niveau des latitudes moyennes**. [Method of analysis of discontinuity surfaces in middle latitudes.] *Revue de Géographie de Lyon*, 30(4):369-378, 1955. 7 figs., 4 refs. DWB—Discontinuity surfaces are defined as boundaries separating lower descending air from upper ascending air (and not necessarily two air masses of different origin). A method is developed whereby such discontinuity surfaces may be identified on upper air charts. The method is applied to the synoptic situation over Western Europe on Feb. 27, 1953, using 700 and 500 mb charts on which vertical temperature gradients serve to illustrate regions of rising or descending air. The discontinuity lines thus obtained are found to correspond to rainfall areas. The average

precipitation level for the synoptic type analyzed is about 3000 m. *Subject Headings: 1. Synoptic case histories 2. Discontinuity surfaces.—G.T.*

7.5-135

551.515.8:551.589(548)135

§Jayamaha, G. S., *A synoptic analysis of Ceylon weather.* *Weather*, 11(1):10-15, Jan. 1956. 5 figs., table, ref. DWB—The air masses of Ceylon are listed and mapped, and the northern and southern convergence zones limiting the equatorial westerlies. The monsoon and inter-monsoon seasons, the "burst" of the monsoon and surges in the monsoon are described, with 2 synoptic charts. *Subject Headings: 1. Air masses 2. Synoptic climatology 3. Ceylon.—C.E.P.B.*

7.5-136

551.515.8:551.541:551.5136

Mosetti, Ferruccio, *A proposito di una questione sulle onde microbariche caratteristiche dei fronti.* [On the problem of microbaric waves connected with fronts.] *Annali di Geofisica*, 7(3):463-468, July 1954. 2 figs., 15 refs. English summary p. 468. MH-BH—Previous authors, using instruments poorly suited for the purpose, found some connection between short period microbaric waves and frontal passages over the station. On the basis of examples here illustrated (Sept. 2B-29, 1951 and March 6-7, 1952), the author shows that microbaric waves connected with fronts have a long period. *Subject Headings: 1. Microbaric waves 2. Frontal passage effects.—M.R.*

7.5-137

551.515.86

Suraud, P., *Le front intertropical en Afrique Occidentale.* [Intertropical front in West Africa.] *Annuaire Hydrologique de la France d'Outre-Mer*, 1952. Paris, pub. 1954. p. 29-33. 4 figs. DWB—The seasonal variations in the position of the intertropical front across Africa are illustrated by full page maps for Jan. and July, showing the wind regimes of the Harmattan or trade wind belt to the N, and of the monsoon belt to the S, and the cyclonic and anticyclonic centers of each zone. Vertical structure, time of passage and rainfall regimes are illustrated and described. *Subject Headings: 1. Intertropical front 2. Tropical meteorology 3. Africa.—M.R.*

7.5-138

551.515.138

§Sanders, Frederick, *An investigation of the structure and dynamics of an intense surface frontal zone.* *Journal of Meteorology*, 12(6):542-552, Dec. 1955. 18 figs., table, 14 refs., 3 eqs. DWB—An intense front over the U. S. on April 17-18, 1951, is studied in 3 dimensions. Surface and 700 mb charts, isochrones and cross-sections are given. The front became diffuse above a few thousand feet. Frontogenetical processes are 10-100 times more intense near the ground than in the free air. The frontal zone is composed of air initially in the warm sector which has been entrained into the zone by intense frontogenesis and is then subjected to intense frontolysis as it rises within the zone. It appears that the motion of this type of frontal zone at the surface is controlled by the motion of the adjacent cold air. *Subject Headings: 1. Frontal development.—C.E.P.B. and author's abstract.*

## RADIATION AND TEMPERATURE

### RADIATION

See also: Optics and met. of atmos. turbidity (Volz), 7.5-15; Radiation bioclimatology (Davos, Switz. Schweizerisches Forschungsinstitut), 7.5-18; Effective radiation (Andreeva, Marshunova), 7.5-84; Energy balance (Robinson), 7.5-115; Corpuscular radiation (Péczeley), 7.5-133.

7.5-139

551.521:551.5139

Roach, W. T., *Measurements of atmospheric radiation and the heat balance at the ground at Kew, May, 1953-May, 1954.* *Great Britain. Meteorological Research Committee M.R.P.* 936, Oct. 18, 1955. 18 p. 10 figs., 2 tables, 11 refs., 11 eqs. Mimeo. DWB—The theory of heat balance on a grass surface is discussed and the instrument set up described.

of photographic records of surface temperature, radiation flux and flux of heat at 6 cm in soil were obtained over a complete year; specimen records are shown. Values of net vertical flux of total, short wave and long wave radiation, downward flux of long wave radiation, surface temperature, heat flux into ground, flux of water vapor and rainfall are tabulated for each month. Appendices describe calibration of instruments and a standard black body cavity radiator. *Subject Headings:* 1. Heat balance 2. Radiation balance 3. Kew Observatory, London.—C.E.P.B.

7.5-140

551.521.16

\*Steinhauser, F., *Die Veränderlichkeit der Globalbeleuchtungsstärke in Wien*. [The variability of global illumination in Vienna.] *Archiv für Meteorologie, Geophysik und Bioklimatologie, Ser. B*, 7(1):60-73, 1955. 2 figs., 2 tables, 4 refs. German, English and French summaries p. 60-61. DWB—Observations of global illumination with a selenium photocell adjusted by filters to eye sensitivity, were made at Vienna, 1937-46. Mean values in kilolux are shown by isopleths: 9 h values exceeded 15 h April-Dec., but were less Jan.-March. For hours 5-6, 8-9, 11-12, 15-16, 18-19 means, extremes and mean departures are tabulated for each month and frequencies shown by histograms, the class interval being half the mean deviation for the month. *Subject Headings:* 1. Illumination intensity 2. Vienna, Austria.—C.E.P.B.

7.5-141

551.521.3:551.511

Budyko, M. I., *O preobrazovanii solnechnoi energii na poverkhnosti Zemli*. [The transformation of solar energy on the earth's surface.] *Akademiia Nauk SSSR, Izvestiia, Ser. Geograf.*, No. 1:7-14, Jan./Feb. 1954. DLC—Contents and results of a series of studies carried out at the Leningrad Geophysical Observatory during the last few years concerning geographical regularities of solar energy transformation on the earth's surface and the influence of these transformations on natural processes of the heat balance are presented and discussed. The investigations were influenced by the work of A. A. GRIGOR'EV who used the quantitative balance method which includes the utilization of data on the heat balance. *Subject Headings:* 1. Solar radiation transformation 2. Heat balance. I. Grigor'ev, A. A.—A.M.P.

7.5-142

551.521.32:551.506.7

Houghton, J. T. and Brewer, A. W., *Measurements of the flux of long wave radiation in the upper air 1953-1954*. *Great Britain. Meteorological Research Committee, M.R.P.* 914, April 28, 1955. 5 p. 4 figs., 7 refs. Mimeo. DWB—Upward and downward fluxes of long wave radiation at night were measured by radiometer in an airplane at 3000 ft intervals up to 40,000 ft. Temperature and humidity were also measured. The downward flux below 30,000 ft agreed with ELSASSER's chart with a pressure correction and YAMAMOTO's chart for radiation from CO<sub>2</sub>, multiplied by 1.2. The upward radiation was affected by cloud. Dense clouds had 100% emissivity, thin clouds down to 10% and ground 90-95%. A clear atmosphere cooled by 1-2°C/day. Observations in the stratosphere were disappointing. *Subject Headings:* 1. Radiation flux in upper air 2. Airplane soundings.—C.E.P.B.

7.5-143

551.521.61:535.3

Godson, W. L., *The computation of infrared transmission by atmospheric water vapor*, Pt. 2. *Journal of Meteorology*, 12(6):533-535, Dec. 1955. 2 figs., table, 3 refs., 28 eqs. DWB—The calculation of transmission for a model spectrum requires the adoption of a distribution function for line intensity. In the case of the infrared water-vapor spectrum (random model), a logarithmic ogive distribution for line intensity is very realistic and produces smaller transmission and cooling-rate errors than other functions previously proposed. These results apply also when experimental data are assumed available and the requisite parameters are obtained by curve fitting. (For Pt. 1, see 6.9-181, Sept. 1955, MAB.) *Subject Heading:* 1. Infrared transmission calculations.—Author's abstract.

7.5-144

551.521.61:551.578.11

Johnson, John C. and Terrell, James R. (both, M.I.T.), *Transmission cross sections for water spheres illuminated by infrared radiation*. *Optical Society of America, N. Y., Journal*,

45(6):451-454, June 1955. 2 figs., 3 tables, 6 refs., 5 eqs. **DLC**—The Mie theory is used in the computation of several transmission cross sections for absorbing spheres. For each sphere a complex index of refraction is selected such that cross section corresponds to that of a water sphere illuminated by infrared radiation of mean wavelength less than 14 microns. The real part of the index is a value between  $1.14 \leq m \leq 1.42$  and the imaginary part, the absorption index, lies between  $0 \leq mk \leq 0.40$ . Also included is a study of the change in the transmission cross section as the absorption index is varied. For these computations, the real index of refraction is kept constant at  $m=1.29$ . *Subject Headings: 1. Mie theory 2. Infrared transmission through raindrops.*—*Authors' abstract.*

7.5-145

551.521.63:551.521.38

Verkholantzeff-Wegener, Antonie, **Der Umkehreffekt von Götz. Messungen des Zenithhimmelslichts mit dem Multiplier.** [The Umkehr effect of Götz: measurements of the zenith sky light with the multiplier.] *Archiv für Meteorologie, Geophysik und Bioklimatologie, Ser. B*, 7(1):96-116, 1955. 9 figs., 8 tables, 12 refs. English and French summaries p. 96-97. **DWB**—Measurements of diurnal variation of absorption by ozone of zenith light of different UV wave lengths at Zurich with an electron multiplier, are described with instrumental set up. Ratio  $3110/3290 \text{ Å}$  is tabulated for zenith distances  $75-92.5^\circ$ ; these showed a minimum at  $86^\circ 33'$  with ozone 0.185 cm increasing to  $86^\circ 56'$  with 0.230 cm. The effective wave length in different spectral regions is calculated for zenith distance  $40-90^\circ$ . Measurements are given on 3290, 3110, 3052, 3024 and  $2997 \text{ Å}$  from 16-18 h and ratios calculated for ozone amounts of 0.211, 0.176 and 0.191 cm, showing the Umkehr effect. *Subject Headings: 1. Ultraviolet radiation 2. Umkehr effect.*—*C.E.P.B.*

7.5-146

551.521.7:550.38

Jennison, R. C., **Corpuscular streams.** *Observatory*, London, 75(886):125-126, June 1955. **DLC**—Suggests that corpuscular eruptions form shock waves travelling at 1500 km/sec, the most probable ionizing agent being the electrons in the front. This agrees with the sudden commencement of magnetic storms. *Subject Headings: 1. Corpuscular radiation 2. Magnetic storms.*—*C.E.P.B.*

7.5-147

551.521.7 551.594.0

Kawakami, Kinnesuke; Takahashi, Tatsu and Onoue, Michio, **A method of discriminating disturbances in VHF solar noise observation.** *Japan. Radio Research Laboratories, Tokyo Journal*, 2(8):111-124, April 1955. 16 figs., 2 refs. **DWB**—A method to discriminate various disturbances from the solar noise has been developed by making use of the difference of the waveforms. By means of this method, satisfactory results have been obtained in a solar noise observation at 200 mc, giving a solution to one of the most important problems in the solar noise observation. *Subject Headings: 1. Radio noise 2. Solar radio noises.*—*Authors' abstract.*

7.5-148

551.521.7:523.75:629.396.8

§Owren, Leif, (Carnegie Inst., Wash., D. C.), **Observations of radio emission from the sun at 200 Mc/sec and their relation to solar disk features.** Cornell Univ. School of Electrical Engineering, Contract N6onr-264(06), Radio Astronomy Report, No. 15, May 1, 1954. 219 p., 32 figs. (incl. photos). 5 p. refs. appended. **DWB**—A voluminous report giving results of solar radio frequency radiation observations at 200 Mc/sec, from April 1950-Dec. 1952, with a radiometer and radio interferometer at McMath-Hulburt and at Cornell Univ. Observatories. Measurement of random noise; actual radiometer observations; and radio interferometer observations in relation to solar features, comprise the first 3 chapters (Pt. I). Pt. II consists of two chapters covering radio emissions associated with solar flares, and enhanced emissions associated with active solar regions. Pt. III covers relationships between radio emissions from sun and solar disk features, and the origin of major bursts and fading in enhanced radiation. The appendix describes the D.T.M. solar radio interferometer. *Subject Headings: 1. Solar radio frequency radiation 2. Solar disturbances 3. Radio astronomy 4. Radio interferometer observations.*—*M.R.*

## TEMPERATURE

See also: Air temp. variation with height (Makris), 7.5-13; Upper air temps. (Bigg), 7.5-103; Rainfall spells & temp. (McIntosh), 7.5-208; Upper air temperature (Kamiyama), 7.5-248.

7.5-149

551.524.2(73/9) 551.577.2(73/9)

\*U. S. Weather Bureau, Daily temperature, degree day and precipitation normals, based on, or adjusted to, the 1921-1950 period. Asheville, N. C., Dec. 1953 (some stations rev. March 1954). loose-leaf, unpagd. entirely tables. Data for 48 states, District of Columbia, Alaska, Hawaii, Pacific Islands and West Indies. Price: \$.05 per single stations; \$15.00 for assembled set. DWB—The temperature and precipitation normals are effective Jan. 1, 1953 and degree days normals, base 65°F, are effective July 1, 1953. The tables give daily values and monthly totals of maximum, minimum and average dry bulb temperature, daily and monthly totals of degree days and daily and monthly totals of precipitation. *Subject Headings:* 1. Temperature normals 2. Precipitation normals 3. Degree days 4. Observational data 5. United States 6. United States possessions.—I.L.D.

7.5-150

551.524.3:551.543:551.509.33(73)

Nagao, Takashi, Characters of weather group and its application to long-range weather forecasting, Pt. 5. *Journal of Meteorological Research*, Tokyo, 6(7):254-263, Sept. 1954. 17 figs. In Japanese; English summary p. 254. Pt. 6. *Ibid.*, 6(9):433-442, 1954. 21 figs. In Japanese; English summary p. 433. DWB—In Pt.5 the author discusses relation between the distribution of interdiurnal variability of air temperature, monthly range of air pressure and monthly mean temperature, using climatological data in each month from Jan. to June in the United States. Results obtained are: 1) charts of monthly range of air pressure were prepared, and the center of the maximum value is in the middle part of the United States; 2) charts of the interdiurnal variability of air temperature were prepared, and the maximum value is in the middle part of the United States; the value of the interdiurnal variability of temperature is large in areas with large value of monthly range of air pressure; 3) the monthly mean temperature charts were compared with charts of distribution of interdiurnal variability of air temperature, and the results show that the gradients of monthly temperature over the United States are large in the case of large value of the interdiurnal variability of temperature. In Pt. 6 the author discusses the relation between the distribution of interdiurnal variability of air temperature, the monthly range of air pressure and the monthly mean temperature, using the climatological data for the months from July to Dec. in the United States. The results obtained are: 1) charts of monthly range of pressure were prepared and the center of maximum value was in the middle part of the United States; 2) charts of diurnal variability of temperature were prepared and the center of maximum value was in the middle part of the United States; the values of diurnal variability of temperature were large in the areas with large values of monthly range of pressure; a correlation diagram was obtained; 3) some characters of charts for each month are discussed. *Subject Headings:* 1. Temperature variations 2. Pressure variations 3. Long-range forecasting 4. United States.—*Author's abstract.*

7.5-151

551.524.31:551.551

Staley, D. O., The diurnal temperature wave for quadratic and exponential variation of the Austausch coefficient. *Archiv für Meteorologie, Geophysik und Bioklimatologie, Ser. A*, 9(1): 25-35, 1956. 2 figs., table, 10 refs., 39 eqs. German and French summaries p. 25-26. DWB—The heat conduction equations are solved for the cases  $K(=A/\rho$ , where  $\rho$  is density and  $A$  is Austausch coefficient) $=K_0=K_{1z}+K_{2z}^2$  and  $=K_0e^{bz}$ , constant with time. Numerical examples show that both amplitude and phase of the diurnal wave are critically dependent on Austausch and tend to be smaller the more strongly it increases with height. *Subject Headings:* 1. Austausch coefficient 2. Diurnal temperature variations.—C.E.P.B.

7.5-152

551.524.32

Bayer, Karel (Czechoslov. Acad. of Science, Clim. Div.), Singularity teploty na Milešovce v období 1910-1939. [Temperature singularities at Milešovka during 1910-1939.] *Meteorologické Zprávy*, Prague, 8(2):35-42, April 30, 1955. 6 figs., 2 tables, 12 refs., 2 eqs. Rus-

sian and German summaries p. 35. **DWB**—In the annual temperature curve for Milešovka there is a number of periods in which warming or cooling regularly occurs. These disruptions of the continuity in temperature development clearly indicate the existence of weather singularities, as appears from a comparison with temperature development on Hohenpeissenberg and precipitation and thunderstorm conditions on Milešovka. A comparison with the frequency of circulation types does not in every case produce satisfactory results. A more detailed analysis will be necessary of those cases in which the frequencies of circulation types did not reflect the occurrence of weather singularities. *Subject Headings: 1. Temperature singularities 2. Circulation type frequencies 3. Milešovka, Czechoslovakia.*—*Trans. author's abstract.*

7.5-153

551.524.33:551.590.23

\*Xanthakis, John, *Study of the mean monthly air temperatures during the successive sunspot cycles.* *Archiv für Meteorologie, Geophysik und Bioklimatologie, Ser. A*, 9(1):54-71, 1956. 13 figs., 10 tables, 11 refs., 22 eqs. German and French summaries p. 54-56. **DWB**—From 6 records in central and N.W. Europe (131-169 yrs) the following were analyzed for differences between consecutive 11-year sunspot cycles: a) (May to Aug.)-(Sept. to Feb.); b) July-Jan., June-Dec.; c) (Sept.+Oct.-March+April); d) Differences b)-c). A number of relations with annual sunspot numbers are found. The investigation is then extended to E. Europe and the Middle East, and finally to other parts of the world. *Subject Headings: 1. Temperature cycles 2. Sunspot effects on temperature.*—*C.E.P.B.*

7.5-154

551.524.35:551.57

§Yoshioka, T., *Air temperature decrease due to precipitation, Pt. 1.* *Journal of Meteorological Research*, Tokyo, 6(1/3):52-56, March 1954. 3 tables, 5 refs. In Japanese; English summary p. 52. **Pt. 2.** *Ibid.*, 7(2):112-114, March 1955. 5 figs., 3 tables, 5 refs. In Japanese. **DWB**—In the first report temperature variation throughout precipitation interval at Aikawa is investigated and results obtained are: 1) Air temperature at the time of rainfall is 0.5-1.3°C smaller than the temperature 1 hour before its beginning both in Jan. and July. 2) Air temperature 1 hour after rainfall ending increases by 0.3°C in July and 0.5°C in Jan. over that at rainfall time. 3) Air temperature 1 hr after rainfall ending is smaller by 0.3-1.0°C in July and 0.5-1.0°C in Jan. than the temperature 1 hour before rainfall beginning. 4) Frequency of air temperature increase at rainfall time in comparison of the temperature 1 hour before rainfall beginning, is 18% in July and 30% in Jan., respectively. 5) At the time of snowfall, total temperature decrease of 1.5-2.0°C results. The second report includes a synoptic chart for 18 h Jan. 22, 1945 and automatic records for Jan. 22-23, 1945, wind direction and temperature graph and other data in tables and charts. *Subject Headings: 1. Temperature-precipitation relationships 2. Temperature variations 3. Aikawa, Japan.*—*Author's abstract*—*M.R.*

7.5-155

551.524.36:519.241(497.1)

\*Dobrilović, Borivoje N., *Primer primene zakona normalne raspodele na jedan klimatoloski niz.* [Example of an application of the law of normal distribution to a climatological series.] *Yugoslavia. Midrometeorološka Služba, Vesnik*, 3(3/4):90-98, July/Dec. 1954. 3 figs., 3 tables, 3 refs., 7 eqs. **DWB**—The mathematics of Gaussian distribution are explained and applied to a classification of 07 h temperature values obtained at Belgrade in Jan. during the period 1936-1954. A table is presented, giving observed and calculated frequencies for seven categories of deviations ranging from extremely subnormal (exceeding -12.6) through normal ( $\pm 4.2$ ) to extremely above normal (over +12.4). *Subject Headings: 1. Temperature frequencies 2. Statistical studies 3. Belgrade, Yugoslavia.*—*G.T.*

7.5-156

551.524.37(52)

\*Arakawa, Hidetoshi (*Met. Res. Inst., Tokyo*), *Remarkable winters in Japan from the seventh century.* *Geofisica Pura e Applicata*, Milan, 30(1):144-146, Jan./April 1955. 1 fig., 1 table, 7 refs. **MH-BH**—A chronological list of severe and of mild winters in Japan from 402 A.D. to 1954 is discussed and comparison made with similar data for Europe (Central England and Berlin). Graph shows summer temperature in Tohoku District (North Japan) compared with that in Central England (MANLEY, 1953, see items 4.9-40, Sept. 1953 and

55.3-63, March 1954, *MAB*) from 1883-1953. Both in winter and summer the correspondence between Japan and W. Europe is not close, though some remarkable coincidence of extreme years in both senses (positive and negative correlation) are noted. *Subject Headings*: 1. Severe winters 2. Long period records 3. Northern Japan 4. Central England. I. Manley, Gordon.—*M.R.*

## UPPER AIR TEMPERATURES

7.5-157

551.524.4

Ånason, G. and Vuorela, L. (both, *Stockholm Univ.*), A two-parameter representation of the normal temperature distribution of the 1,000-500 mb layer. *Tellus*, Stockholm, 7(2):189-203, May 1955. 10 figs., 13 refs., 5 eqs. **DLC**—Height normals for 1000, 700 and 500 mb, published by U. S. Weather Bureau, have been used to study the normal temperature fields of the 1000-500 mb layer by means of a simple model. In this model the normal temperature-height curve is replaced by one having a temperature lapse-rate independent of height in such a way that the thicknesses of the sub-layers 1000-700 and 700-500 mb are correctly represented by the model. As a consequence, the temperature as well as its horizontal gradient and the thermal wind all have a linear variation with height and may be described in terms of two parameters, the temperature lapse-rate  $k$  and a "representative" 1000 mb temperature  $\tau_0$ . Hemispheric maps for these parameters as well as the thermal wind at 1000 and 500 mb have been prepared for the months Jan. and July. The major frontal zones of the atmosphere appear clearly on the  $\tau_0$ -maps in position which agree essentially with those shown earlier by a number of meteorologists. The July map reveals, however, a strong baroclinic zone in high latitudes, surrounding the polar cap, not shown clearly in earlier presentations of the low-level baroclinity. The  $k$ -charts disclose large horizontal variation in the temperature lapse-rate, and the charts for the thermal wind show that its variation with height is very pronounced in middle and high latitudes. *Subject Headings*: 1. Vertical temperature gradient 2. Numerical forecasting 3. Northern Hemisphere normal temperature charts.—*Authors' abstract.*

7.5-158

551.524.7:551.509.31

Iwata, I., Application of upper air temperature. *Journal of Meteorological Research*, Tokyo, 5(10/12):790-793, Jan. 1954. 3 figs. In Japanese; English summary p. 790. **MH-BH**—The isopleth of daily temperature departure from preceding 5-day mean was drawn at each standard pressure level for radio-sonde observations at Wakkanai, and some important relation was found between the temperature departure and weather. As is seen in Figs. 1, 2 and 3, variation of its sign corresponds very well with that of weather, and could be used for practical forecasting with good result. It is also pointed out that the isopleth graph shows appreciable negative correlation between the sign at troposphere and that at stratosphere. *Subject Headings*: 1. Forecasting techniques 2. Upper air temperature variations.—*Author's abstract.*

7.5-159

523.746:551.524.7:551.510.535:550.385

\*Morton, William C., III, An investigation of periodicity in selected indices of solar activity. Weather Services, Inc., Boston, Contract AF 19(604)-449, Scientific Report, No. 5, Aug. 1954. 7 p. 4 figs., 4 tables, 35 refs., eqs. **MH-BH**—An investigation was made to determine whether or not a periodicity in 700 mb temperatures was accompanied by a similar periodicity in solar activity as measured by the Zurich Sunspot Number, the critical frequency of the F2 layer, and the planetary geomagnetic disturbance index ( $K_p$ ). Harmonic analysis was carried out by FUHRICH's auto-correlation method. *Subject Headings*: 1. Sunspot cycles 2. Upper air temperature periodicities 3. F2 critical frequency anomalies 4. Geomagnetic disturbances.—*Author's abstract.*

7.5-160

551.524.7:551.571.7

\*Müller, Hans Gerhard, Die Zustandswerte in der freien Atmosphäre bei Schauerniederschlägen. [The conditions in the free air during showers.] *Archiv für Meteorologie, Geophysik und Bioklimatologie*, Ser. A, 8(3):237-245, 1955. 4 figs., 2 tables, 6 refs. English and French summaries p. 237. **DWB**—Results of 1664 radiosonde ascents at Munich 1949-53 on rainless days and days with showers, thunderstorms and hail are analyzed. On days with thunderstorms the moist adiabatic and the 0°C level are higher than on rainless days; days with rain within 6 hrs are intermediate. Thunderstorms are rare on days of low relative

humidity but a few occur at high temperatures. The number of days with hail shows little relation to mean temperature at 850 and 500 mb (minimum at  $-5$  to  $-1^{\circ}\text{C}$ ) but the area of Bavaria affected grows rapidly with increasing temperature. The critical relative humidity for showers within 6 hrs is  $185-5(T_{850}-T_{500})$ . *Subject Headings:* 1. Thunderstorm forecasting 2. Hailstorm conditions 3. Shower conditions 4. Munich, Germany.—C.E.P.B.

## SOIL TEMPERATURE

7.5-161

551.525.4:551.2

Penta, F. and Conforto, B., *Sulle misure di temperatura del sottosuolo nei fori trivellati in presenza di acqua e sui relativi rilievi freaticometrici in regioni idrotermali.* [Measurements of the temperature of the subsoil in hot springs in the presence of water and the relative gradients in the topography of the hydrothermal region.] *Annali di Geofisica*, 4(1):43-93, Jan. 1951. 29 figs., 2 tables. **MH-BH**—Results of numerous measurements of temperature of hot springs and geysers at various depths are given in tables and diagrams and are analyzed. Measurements were made in fumaroles and springs in the island of Ischia and at Campi Flegri (Naples). Methods of measurement and necessary corrections are discussed. *Subject Headings:* 1. Earth temperatures 2. Geysers 3. Italy.—M.R.

7.5-162

551.525.5:551.578.4

Nagasawa, Shingo and Makino, Kinken, *Ground temperature (soil temperature) under snow cover.* *Seppyo (Snow and Ice)*, Tokyo, 11(5):161-167, 1950. 7 figs., tables, foot-references. In Japanese; English summary p. 11. **DWB**—To find the mechanism of avalanches the ground temperatures were measured by a self-registering electric resistance thermometer on a slope near Itaya station along Ou-line from Jan. to March in 1948. Under snow the temperature of the ground surface remained  $0^{\circ}\text{C}$  all through this interval and that below the surface decreased steadily. Theoretical explanations are given and the thermal effect of a rod to which the thermo-elements of the thermometer are fastened is discussed theoretically. *Subject Headings:* 1. Soil temperature under snow 2. Resistance thermometers 3. Japan.—Authors' abstract.

7.5-163

551.525.5:001

Ray, Louis L., *Permafrost.* *Arctic*, 4(3):196-203, Dec. 1951. 16 refs. **DLC**—Basic knowledge on the subject is summed up. Definitions are given, nomenclature discussed, various forms of permafrost classified and results of research mentioned in general terms. *Subject Headings:* 1. Permafrost 2. Definitions.—G.T.

7.5-164

551.525.5:631.4

Soil Mechanics Conference, Dec. 1950, Montreal, *Proceedings. National Research Council of Canada. Associate Committee on Soil and Snow Mechanics. Technical Memorandum* No. 19, April 1951. 58 p. Mimeo. **DWB**—Report on Conference held Dec. 14 and 15, 1950 in Montreal. Besides papers on regional problems (in various provinces of Canada), papers on soil mechanics as related to the Winnipeg flood, to frost heaving and to soil moisture are of incidental interest to applied meteorology. *Subject Headings:* 1. Soil mechanics 2. Frost heaving 3. Canada.—M.R.

## WATER TEMPERATURE

See also: Irrigation (Mihara), 7.5-52.

7.5-165

551.526.6(261.3) 551.48:639.222.2

†\*Ehnholm, Gunnar, *Studier över strömmingen i Östra Kvarken.* [Studies on the small Baltic herring in East Kvarken.] *Finland. Merentutkimuslaitos, Julkaisu*, No. 149, 1951. 94 + 21 p. 21 figs., 68 tables, bibliog. p. 92-94. German summary p. 86-90. **DWB, DLC**—This study on the biology of the small herring *Clupea Larengus v. membrus* L. contains a description of the hydrography of the Gulf of Bothnia including its shape, depth conditions and salt content. Water temperature and water contents of the Gulf of Bothnia as a whole and the temperature, salt content and density of the water within the Kvarken and adjoining areas during 1938-39. Also the distribution of the zooplankton within the Kvarken at various levels is described. Maps showing the area studied, current in the Gulf of Bothnia, and

table with temperature distribution with depth at Hernösand are presented. *Subject Headings:* 1. Sea temperature data 2. Hydrography 3. Gulf of Bothnia.—*I.L.D.*

7.5-166

551.526.6:551.464

\*Grangvist, Gunnar. Regular observations of temperature and salinity in the seas around Finland, July 1946-June 1950. *Finland. Merenmuikinsuulaitos, Julkaisu*, No. 150, 1951. 35 p. almost entirely tables. DLC—The contents of this paper include the following: monthly averages of surface temperatures and salinities at 14 h. at the year stations; annual averages of the surface temperatures and salinities at the year station; monthly averages of surface and salinities at the light vessels at 7 h, 14 h and 21 h; daily temperatures at different depths at 9 h. at the light vessels in summer 1949; temperatures and salinities at different depths, three times monthly, at the year stations; and temperatures and salinities in different depths, three times monthly, at the light vessels, at 14 h. The localities where the measurements were made are listed. *Subject Headings:* 1. Sea water salinity data 2. Sea temperature data 3. Finland.—*I.L.D.*

7.5-167

551.526.6:551.464(265)

Nagai, Masawo. On the annual variation of sea water temperature and chlorinity at Gotonada. *Oceanography and Meteorology*, Nagasaki, 6(2.4):129-136, (p. 951-958 at top), Dec. 1954. 4 figs., 8 tables, 6 refs. In Japanese; English summary p. 146. MH-BH—The annual variations of the sea-surface temperature and chlorinity at Gotonada, the sea area west of Kyushu, show a negative correlation and are considered to be divided into 2 parts: the variations due to the meteorological processes, such as the heat exchange between sea and atmosphere, evaporation and precipitation, and the variations due to advection. When the meteorological processes are taken into account and the advective factor is estimated, the negative correlation becomes positive: the correlation between the heat transported by the advection and the observed minus calculated chlorinity difference, is positive. *Subject Headings:* 1. Annual sea water temperature variations 2. Chlorinity 3. Heat exchange sea-atmosphere 4. Gotonada, Japan.—*Author's abstract.*

7.5-168

551.526.8:551.48:551.588.4

\*Eckel, O. Beitrag zum Studium des Wärmeumsatzes in Seen. [Contribution to the study of the heat balance in lakes.] *Archiv für Meteorologie, Geophysik und Bioklimatologie*, Ser. A, 9(1):120-157, 1956. 5 figs., 14 tables, 9 refs., eqs. English and French summaries p. 120-121. DWB—Records of temperature, vapor pressure and wind were made on the surface of Lake Traunsee and 8 m above the shore, in 1953-54, and the diurnal and annual variations of evaporation  $W$  and heat exchange  $Q$  computed. "In 62% of all hours the heat flux as well as water vapor current were directed from the water surface upwards, in 31% humidity was transferred to the air and at the same time heat to the water, and only in 7% both currents were directed to the water." In the second part, putting  $\Delta T$ =temperature difference water-air, and  $\Delta e$ =vapor pressure difference, curves of  $\Delta e$ ,  $\frac{1}{2}\Delta T$  and sum of both are shown for clear, overcast or misty, and stormy weather and the annual variation of the daily means shown. The water receives heat from the air in March through July, and gives heat to the air in Aug.-Feb., especially in winter. The data are set out in numerous tables. *Subject Headings:* 1. Lake influences 2. Heat balance of lakes 3. Lake Traunsee, Austria.—*C.E.P.B.*

## PRESSURE AND WIND

### PRESSURE

*See also:* Monthly mean pressure charts (S. Africa. Weather Bur., 7.5-120; Microbaric waves (Massett), 7.5-134; Pressure variations (Nagai), 7.5-150; Geostrophic wind field (Obukhov), 7.5-179; Wind speed maxima (Clodman), 7.5-181; Upper air pressure (Clodman), 7.5-192; Atmospheric influences (Neuwirth), 7.5-234.

7.5-169

551.542:551.513(99)

Mironovitch, V. Champ isobarique moyen d'hiver et d'été dans l'Hémisphère Sud. [Mean winter and summer isobaric field in the Southern Hemisphere.] *La Météorologie*,

Paris, 4th Ser., No. 31:187-192, July/Sept. 1953. 3 figs., 18 refs. French and English summaries p. 187. **MH-BH**—Two original mean seasonal isobaric charts of the Southern Hemisphere, based on all data available up to 1952, are presented and discussed. The main feature emphasized is the complex rather than (as heretofore presumed) simple circulation system over and adjacent to the Antarctic continent—an area shown on a chart of Europe to be equal in magnitude to Europe without the Italian Peninsula. The center of the continent is anticyclonic both seasons (Dec.-Feb. and June-Aug.), but there are lobes separating 3 or 4 cyclones, each in the lee of one of the major Antarctic promontories. These cyclones are semipermanent like the Aleutian and Iceland lows. The circulation in the belt from 40° to 60°S is still considered regular on the mean charts. *Subject Headings:* 1. Antarctic circulation charts 2. Mean seasonal pressure charts for Southern Hemisphere 3. Antarctic.—M.R.

7.5-170

551.543.1

Loewe, F. and Scorer, R. S., **Barograph antics.** *Weather*, 10(11):395, Nov. 1955. **DWB**—Both correspondents discuss the comparison between pressure waves and those produced by the Siberian meteorite. **SCORER** calculates that the total energy of the latter equalled 10,000 atomic bombs. *Subject Heading:* 1. Pressure oscillations.—C.E.P.B.

7.5-171

551.543.3:523.1

Pava, R. (Bucharest), **Adalékok a légköri árapály kutatásához.** [Contribution to the study of atmospheric tides.] *Időjárás*, Budapest, 58(6):445-446, Nov./Dec. 1954. Russian and French summaries p. 445. Transl. by L. Aujeszký. **DWB**—Also: complete German version: *Beiträge zur Forschung der atmosphärischen Gezeiten.* *Acta Agronomica*, Budapest, 5(1/2):261-264, 1955. Russian and English summaries p. 263-264. **DA**—On the basis of U. S. Weather Bureau Historic Weather Maps, the author examined the possible influence of long lunar periods (i.e., the synodical and draconical lunar months) on atmospheric pressure oscillations. This paper contains a brief report of his findings (a detailed report containing the entire data material is under publication in the transactions of the Romanian Academy of Science). For the equatorial region only a very weak effect of long lunar periods on atmospheric pressure can be detected, but this effect increases with latitude and at the poles it reaches an average amplitude of 8 mb for a synodical and 6.5 mb for a draconical lunar month. The largest amplitude found was 27 mb. For 52°N lat. the average amplitude for the synodical period is 2.6 mb, or 90 times the value identified by **CHAPMAN** for the daily lunar tide. The oscillations follow the gravity changes with a lag of 2-3 days. They are stronger in winter than in summer. *Subject Heading:* 1. Lunar monthly tides. **I. Aujeszký, László** (Trans.)—G.T.

## WIND

7.5-172

551.55:551.515(712)

\*Currie, B. W., **Wind and storms.** *Saskatchewan. Univ. Physics Dept. Prairie Provinces and Northwest Territories: Climatic Studies*, Pt. 6, 1955? 28 p. 9 figs., 7 tables. **DWB**—Normal wind speeds, maximum winds, excessive winds, prevailing directions and direction of strong winds, thunderstorms, hail and dust storms, tornados, wind erosion, chinooks, based on data for representative stations in Alberta, Saskatchewan, Manitoba, Yukon Territory and N.W. Territory of Canada. Extensive discussion of each type of storm and selected and well arranged analytical data presented in tables, wind roses and graphs. *Subject Headings:* 1. Wind conditions in Canadian Arctic 2. Storms in Canadian prairies 3. Prairie Provinces, Canada 4. Canadian Arctic.—M.R.

## TURBULENCE

See also: **Turbulence spectrum** (Estoque), 7.5-112; **Austausch coefficient** (Staley), 7.5-151.

7.5-173

551.551:629.13

Radok, U. (Met. Dept., Melbourne Univ.), **Nocturnal low-level turbulence near Cambridge Aerodrome.** *Australian Meteorological Magazine*, Melbourne, No. 6:5-17, May 1954. 4 figs., table. **DWB**—Aircraft taking off at Cambridge Airport, Tasmania have several times

and trouble or crashed because of horizontal changes in wind speed, rather than vertical gusts or motions. Evidence from many sources is cited to support this theory. Both of the incidents which are described, and a previous one, occurred during calms or lulls when winds above the surface were contrary to those expected. Such wind gradients are due to topographic and radiation conditions peculiar to the area. Topography is shown on chart and records of wind and upper air temperature reproduced. *Subject Headings: 1. Low level turbulence 2. Turbulence in the frictional layer 3. Wind shift line 4. Aeronautical meteorology 5. Tasmania. 6. M.R.*

7.5-174

551.551:551.558.21

Scorer, Robert S., **Turbulence generated in standing waves.** *Royal Meteorological Society, Quarterly Journal*, 81(350):619, Oct. 1955. 4 eqs. DWB—Correction to an argument in his paper (*R.M.S. Q. J.*, 80:629, 1954; see 6.3-160, March 1955, MAB). *Subject Heading: 7. Turbulence.*

7.5-175

551.551:533.6

Shenton, L. R., **A semi-infinite random walk with discrete steps.** *Cambridge Philosophical Society, London, Proceedings*, 51(3):442-448, July 1955. 5 refs., 27 eqs. DLC—Deals with the probability of a given position at any step of a particle executing a random walk over all possible positions  $x=0, 1, 2 \dots$  with initial position  $x \geq 0$  and a given probability of absorption at  $x=0$ . A random walk with drift in the presence of a reflecting barrier is also considered. *Subject Headings: 1. Random walk 2. Turbulence theory.—C.E.P.B.*

7.5-176

551.551:523.72

Uberoi, Mahinder S. (*Mich. Univ., Dept. of Aeron. Engr.*), **Investigation of turbulence in the solar atmosphere.** *Astrophysical Journal*, Chicago, 121(2):400-403, March 1955. 4 figs., 5 refs., eqs. DLC—The correlation and the spectrum of solar granules are measured by a simple technique, and the results are compared with data obtained by orthodox methods. Published data are analyzed to give a direct evidence of convective heat transfer in the solar atmosphere. *Subject Headings: 1. Solar atmospheric turbulence 2. Convective heat transfer.—Author's abstract.*

7.5-177

551.551:533.17

Van Isacker, J., **La notion d'échelle en mécanique des fluides turbulents.** [Idea of scale in mechanics of turbulent fluids.] *Ciel et Terre*, 70(11/12):425-431, Nov./Dec. 1954. fig., 13 eqs. DLC—The author discusses various aspects of the "scale of turbulence," starting with the formulation of the concept to permit a statistical treatment of the motions involved, and going on to develop the theory as an extension of the conclusions of Laufer. *Subject Headings: 1. Scale of Turbulence 2. Turbulent flow 3. Reynolds Number.—M.R.*

## WIND DISTRIBUTION AND VARIATION

See also: **Wind profile measurem.** (Thornthwaite), 7.5-88; **Monsoon forecasting** (Ramdas et al), 7.5-98; **Pressure forecasting** (Bontrand), 7.5-101; **Friction layer** (Arkhangelskii), 7.5-107; **Structure of atmos. surface layer** (Businger), 7.5-109; **Air flow models** (Sawyer), 7.5-116.

7.5-178

551.558.2:551.552:551.43

Corby, G. A. and Wallington, C. E., **Airflow over mountains: the lee wave amplitude.** *Great Britain. Meteorological Research Committee, M.R.P.* 939, Sept. 19, 1955. 7 p. 5 figs., 4 refs., 19 eqs. Mimeo. DWB—Theoretical considerations (sufficient decrease of  $l^2$  with height) suggest that lee waves should be common over the British Isles, but they are rarely reported by aircraft. This is because, to produce waves of large amplitude, large mountains need strong winds with an increase of speed and/or decrease of stability with height, and the airstream characteristics must be favorable. The maximum amplitude and vertical velocity of lee waves in given conditions, and the variations of lee wave amplitude and length, are calculated; they are very susceptible to small changes of conditions. *Subject Headings: 1. Air flow over mountains 2. Lee waves.—C.E.P.B.*

7.5-179

551.552:551.542

Obukhov, A. M., *A nagyiterjedésű légköri mozgások dinamikájának néhány kérdése* [A few problems in the dynamics of large-scale atmospheric motion.] *Időjárás*, Budapest, 59(1):1-6, Jan./Feb. 1955. 6 refs., 17 eqs. Russian and French summaries p. 1. Transl. by Mrs. L. Faragó. DLC. Also: complete German version: *Einige Fragen der Dynamik von ausgedehnten atmosphärischen Bewegungen*. *Acta Agronomica*, Budapest, 5(1/2):155-160, 1955. Russian and English summaries p. 162. DA—Two closely connected problems of the theoretical meteorology are being dealt with in this paper: 1) why is the wind under natural conditions approximating the geostrophic wind? and 2) what processes are being excluded from the sphere of observation by applying equation systems simplified on the basis of quasi-geostrophic approximation? By an analysis of the equation system of the two-dimensional barotropic model it is shown that atmospheric pressure and wind-field anomaly can coexist but for a short period of time. By the quasi-geostrophic approximation applied to the study of natural atmospheric processes, only the fast-moving waves are excluded from the sphere of observation, the baric field adapting itself to the velocity field. In this paper the procedure is illustrated by an example. *Subject Headings*: 1. Geostrophic wind field. I. Faragó, Lászlóné (Trans.).—*Author's abstract*.

7.5-180

551.552:551.588.3:551.465 (26)

van Dijk, W., *An investigation of the vergence field of the wind and ocean currents of the Indian Ocean*. *Archiv für Meteorologie, Geophysik und Bioklimatologie, Ser. A*, 9(1):158-177, 1956. 10 figs., 3 tables, 14 refs. German and French summaries p. 158-159. DWB—Charts of sea temperature and "vergence" (convergence or divergence) of wind over the Indian Ocean to 50°S in Jan. are studied. A significant relation is found with convergence over the relatively warm and divergence over the relatively cold areas, especially in lower latitudes (correlation 0.56 in 25-2°N, 0.2 in 32-48°S). The vergence of the surface current is also analyzed and DEFANT's circulation scheme confirmed. *Subject Headings*: 1. Convergence and divergence 2. Sea temperature 3. Ocean currents 4. Indian Ocean.—C.E.P.B.

7.5-181

551.553:551.542

Clodman, J., (Canadian Met. Service, Toronto), *The interrelationship between wind-speed maxima, fronts and certain contour heights on isobaric surfaces*. *American Meteorological Society, Bulletin*, 35(10):464-467, Dec. 1954. 5 figs., 2 tables, 9 refs. DWB—Taking the three-frontal model developed for the North American area by the Canadian Meteorological Service, the normal properties of the three main frontal surfaces and their associated air-mass temperatures the author shows that the axes of wind maxima at 700 mb and 500 mb are associated with preferred contour heights. Good agreement between these results (namely, that the main wind maximum at 500 mb is at 18,200 ft and at 700 mb, 8900 ft) and those of FLETCHER support the correctness of this analysis. *Subject Headings*: 1. Wind speed maximum 2. Isobaric surfaces 3. Air masses.—I.L.D.

## SPECIAL WINDS

7.5-182

551.555.3

Frey, K. (Olten, Switzerland), *Der Übergang einer antizyklonalen in eine zyklonale Föhnlage und weitere Beiträge zur Kenntnis der räumlichen Temperatur-, Druck- und Windverteilung bei Süd- und bei Nordföhn*. [Transition of an anticyclonic to a cyclonic föhn situation and further contributions to a knowledge of spatial temperature, pressure and wind distribution during south and north föhn.] *Berlin. Freie Universität, Institut für Meteorologie und Geophysik, Meteorologische Abhandlungen*, 2(3):173-188, 1954. 5 figs., 3 tables, 11 refs. DWB—The transition from an anticyclonic to a cyclonic föhn stage is illustrated by means of a specific example. It is shown that the development of a marked solenoidal field on the lee side is of decisive importance for the descent of föhn into valleys. Further indications on the characteristics of spatial fields during south and north föhn situations are analyzed on the basis of an analysis of the mean values of temperature and geopotential differences obtained from radiosonde ascents at Brent, Friedrichshafen and Milan.

ROSSMAN and SCHWEITZER's views on the development of föhn are discussed. *Subject Headings: 1. Föhn development 2. Föhn weather.*—Based on author's abstract.

7.5-183

551.555.3

\*Orlicz, Michał, *A stosunkach anemometrycznych na szczytach tatrza skich*. [Wind conditions on the peaks of Tatra Mountains.] Poland. Państwowy Instytut Hydrologiczno-Meteorologiczny, *Wiadomości Służby Hydrologicznej i Meteorologicznej*, 3(4):316-337, 1954. figs., 28 tables, 37 refs. Russian and French summaries p. 336-337. **DLC**—The characteristics of the winds are described on the basis of data of two stations: "Kasprowy Wierch" in the Western Tatras in Poland (2002 m altitude) and "Lomnica" in the High Tatras, Czechoslovakia (2044 m altitude). Period of observations at both stations, 1939-1944. The dispositions of wind directions at Kasprowy Wierch with prevailing south and north winds indicate the presence of local orographic influences. Kasprowy Wierch is situated on the main flange of the Tatra on the sector where the largest depression occurs. The winds follow it. Southerly winds are mainly katabatic winds of the föhn type (called "halny" or "liptowski"), which are local. Northerly winds are also local in the warm season. In the process of diurnal change, the wind direction follows the position of the sun. At Kasprowy Wierch a meridional disposition of wind directions and greater speed due to the orographic dip are observed. At Lomnica there is a predominance of NW winds and the speeds are lower. Although second in altitude in the Tatras, Lomnica represents better weather conditions in the free atmosphere. Föhn winds of the Tatras are compared with föhns of the Alps. *Subject Headings: 1. Local winds 2. Föhn winds 3. Tatra Mountains 4. Poland 5. Czechoslovakia.*—A.M.P.

## WIND EFFECTS

7.5-184

551.556:532.594

Bryson, Reid A. and Kuhn, Peter M., *On the measurement of bottom stress in lakes*. *American Geophysical Union, Transactions*, 36(4):612-614, Aug. 1955. fig., 2 tables, 7 refs., 4 eqs. **DWB**—The rate of decrease of amplitude of the persistent small-scale wind-induced seiche in a lake is primarily a function of bottom stress. This idea is developed and a number of measurements presented. *Subject Headings: 1. Seiches 2. Wind effects on lakes.*—Authors' abstract.

7.5-185

551.556:551.465(261)

Bumpus, Dean F., *The circulation over the continental shelf south of Cape Hatteras*. *American Geophysical Union, Transactions*, 36(4):601-611, Aug. 1955. 18 figs., 2 tables, numerous refs. **DWB**—South of Cape Hatteras, a southerly-flowing coastal current, such as is common to the northward, is a transient affair. Such a current, when present, is restricted to a very narrow portion of the continental shelf. The dynamic pressure gradient resulting from the combined effect of the runoff and the cross-shelf thermal gradient together with the prevailing wind and the frictional drag of the Florida current provides for a northeasterly drift over a broad part of the Carolina continental shelf. *Subject Headings: 1. Ocean currents 2. Wind driven currents 3. Western North Atlantic.*—Author's abstract.

7.5-186

551.556:631.4:551.311

*Can prevent dustbowls.* *Science News Letter*, Wash., D. C., 67(13):204, March 26, 1955. **DLC**—The Great Plains (about 200,000 sq mi) in Colorado, Kansas, New Mexico, Oklahoma and Texas are highly susceptible to wind erosion in years with below normal rainfall. The high crop yield in wet seasons was responsible for the plowing of about 40,000 acres of sodland, of which 75% was normally unfit for cultivation. Soil conservation experts believe that technical assistance, education and research can successfully counteract and prevent dustbowls. *Subject Headings: 1. Soil conservation 2. Wind erosion 3. Great Plains.*—W.N.

7.5-187

551.556:532.593

Charnock, H., *Statistics and aerodynamics of the sea surface*. *Nature*, London, 177(4498):62-63, Jan. 14, 1956. 8 refs., eq. **DWB**—Review of meetings of Royal Meteorological Society and Challenger Society on June 15 and Royal Met. Soc. on July 22-23, 1955.

Papers dealt with wave-spectra statistics (agreement of observation and theory) and the mechanism by which momentum is transferred from the wind to the sea surface. Most of the papers have appeared in the Society's *Quarterly Journal* and been abstracted, but this digest is useful. A generalized expression for the wind profile over a water surface is derived. M. S. LONGUET-HIGGINS described a set-up at the National Institute of Oceanography for finding the form-drag of larger waves by precise recordings of the pressure at the sea surface. *Subject Headings: 1. Wind-wave relationships.—C.E.P.B.*

7.5-188

551.556:551.579

Kluźniak, Sylwia, **Hydrologiczne i meteorologiczne warunki występowania wysokich stanów wody na zalewi Wiślanym.** [Hydrological and meteorological conditions of occurrence of high water in the Vistula Bay.] *Przegląd Meteorologiczny i Hydrologiczny*, Warsaw, 6(3/4): 95-106, 1953. 5 figs., 6 refs. English summary p. 106. DWB—The causes and extent of water level variations in the Vistula Bay are analyzed and discussed on the basis of observational data for a 50-yr period (1901-1952). It is shown that these variations in the bay which are much (70%) greater than in the Baltic Sea because of the small size and depth of the bay occur mostly in autumn and winter and are caused by the dynamic action of strong N, NNW and NE winds, especially when they blow in the direction of the bay's longitudinal axis. A detailed study of 70 weather situations during the occurrence of high water shows the existence of 5 types of meteorological situations conducive to these winds. These 5 types of weather situations—especially the first—are carefully analyzed and shown on maps. *Subject Headings: 1. Wind effects on water level 2. Long period records 3. Vistula Bay.—A.M.P.*

7.5-189

551.556:551.46:622.323(263)

Leipper, Dale F. (*Dept. of Oceanog., Texas A. & M. College*), **Ocean waves and marine oil operations.** *Texas Agricultural and Mechanical College. Dept. of Oceanography, Collected Reprints in Oceanography and Meteorology*, No. 1/30, 1950/1954, p. 5-7. port., photo. DWB—Reprint from *Oil and Gas Journal*, Tulsa, Oklahoma, 49(7), June 1950.—Mention is made of a symposium on offshore drilling problems in *Oil and Gas Journal*, Feb. 23, 1950, and conclusions that vertical forces associated with ocean waves are the most damaging, that additional data on ocean waves are needed, that the Sverdrup-Munk wave theory is not applicable to short fetch winds such as hurricanes in shallow waters, and that standard forecasts for general public do not contain enough information for the offshore operator. Maximum heights of waves link between oceanography and engineering, and ocean wave studies at Jolla and Texas A & M are reviewed. *Subject Headings: 1. Ocean wave research 2. Wind waves 3. Off shore oil industry 4. Gulf of Mexico.—M.R.*

7.5-190

551.556.3:621.311.2

Sidorov, V. I., **Vetrodvigateli v Arktike.** [Windpower generators in the Arctic.] Moscow, Izdat. Glavsevmorputi, 1948. 2nd ed. 182 p. 105 figs., 35 tables, 27 diagrs. (3 fold). DLC—A technical "manual" describing and giving details of construction and operation of wind power generators in the Arctic. Actual examples of their use and difficulties encountered under severe gale or ice conditions, and efficiency at a place like Cape Zhelania are given. *Subject Headings: 1. Wind generators 2. Cape Zhelania 3. Soviet Arctic.—M.R.*

## UPPER AIR WINDS

*See also: Upper air wind measurem.* (Robertson et al), 7.5-65; *Radar wind comparisons* (Harrison), 7.5-66; *Stratospheric winds* (Dütsch), 7.5-105; *Jet stream profiles* (Harding), 7.5-121; *Jet stream variations* (Hoyle), 7.5-122; *Jet stream*, 7.5-123; *Jet stream properties* (Serebreny et al.), 7.5-124; *Jet stream structure* (Serebreny), 7.5-125; *Jet stream navigation* (Stiefellmaier), 7.5-126; *Atmos. winds & temps.* (Kennedy et al.), 7.5-261.

7.5-191

551.557:551.510.53

\*†Bannon, J. K. and Jones, R. A., **The mean wind at 60 mb.** *Great Britain. Meteorological Research Committee, M.R.P.* 925, Aug. 24, 1955. 22 p. 4 figs., 3 tables, 36 refs. Mimeo. DWB—Vector resultant winds at 60 mb (20 km) were constructed from the few wind ob-

ervations available and from contour charts of 100 mb level extrapolated to 60 mb, for Jan., April, July and Oct. Values of direction and speed are tabulated for 83 stations ranging from 61°N–52°S, plotted on Mercator charts and discussed. *Subject Heading: 1. Stratospheric winds.*—C.E.P.B.

7.5-192

551.557:551.547:019.941

Clodman, J. (*Met. Service, Toronto*), A misinterpretation in the Bulletin of some data presented by W. C. Godson on winds aloft. *American Meteorological Society, Bulletin*, 6(3):103, March 1955. DWB—Comments on Reed, J. W., Representativeness of winds aloft observations (see 6.11–100, Nov. 1955, *MAB*) and on Godson, W. L., Study of the deviations of wind speeds and directions from geostrophic values (see 3–90, March 1950, *MAB*). DWB—Godson (1950) used North American data, not English. Figure of 41 mph for daily change in wind velocity did not refer to local change in wind velocity ( $\partial V/\partial t$ ) but change with a moving parcel  $V$  ( $dV/dt$ ), GODSON calculated  $15.4 \pm 0.5$  mi/hr/day compared with REED's figure of 14 mi/hr/day. *Subject Headings: 1. Reviews 2. Upper air winds 3. Upper air pressure 4. Geostrophic winds. I. Godson, W. C. II. Reed, J. W.*—M.R.

### VERTICAL CURRENTS

See: Upper air wind measurem. (Morasca), 7.5–80; Turbulence in standing waves (Scorer), 7.5–174; Airflow over Mountains (Corby, Wallington), 7.5–178.

## AQUEOUS VAPOR, HYDROMETEORS AND HYDROMETEOROLOGY

### HUMIDITY

See also: Hydromet. data, 7.5–72; Shower conditions (Müller), 7.5–160; Melting of snow cover (Manohin), 7.5–214.

7.5-193

551.571:551.511

Budyko, M. I. and Drozdov, O. A., Zakonomernosti vlagoooborota v atmosfere. [Laws of moisture exchange in the atmosphere.] *Akademiia Nauk SSSR, Izvestiia, Ser. Geogr.*, No. 4:5–14, 1953. 2 tables, 16 refs., 4 eqs. DLC—A series of papers have been published recently by K. H. P. POGOSIAN, K. I. KASHIN and others (of the Hydrometeorological Service) opposing BRÜCKNER's theory and showing that laws of moisture exchange cannot be studied without taking into consideration the atmospheric circulation. Although subsequent written and oral discussions of their results approved the basic principles of their calculations, some doubts were expressed concerning the methods of calculation of the annual variations of the moisture exchange components; on the method of determining the horizontal water vapor transfer and the calculation of the influence of "active" and "passive" water vapor in the analysis of humidity circulation. In view of the fact that the latter doubt is based on erroneous concepts of the inquirers, the authors summarize the basic principles of the theory as developed by the Central Geophysical Observatory which comply fully with VOEIKOV's concepts of the nature of moisture exchange, on the importance of local evaporation for summer precipitation in European Russia, and on the dominant rule of vapor transfer from the Atlantic on precipitation in Europe and W. Siberia, and prove the correctness of their calculation methods of determining the annual variation and the horizontal transfer of water vapor in the atmosphere. *Subject Headings: 1. Moisture exchange 2. Water vapor transfer 3. Atmospheric circulation.*—A.M.P.

### EVAPORATION AND EVAPOTRANSPIRATION

7.5-194

551.573

†\*Blaney, Harry F. (*U. S. Soil Conservation Serv., Los Angeles*), Consumptive use of water. *American Society of Civil Engineers, Proceedings*, Vol. 77, Separate No. 91, Oct. 1951. 8 tables, 3 figs., 32 refs. DWB—The subject of consumptive use for evapotranspiration is discussed

with special reference to definitions, methods and results of research. Empirical formulas are analyzed relating the consumptive use to temperature, daytime hours and humidity. Total evapotranspiration data for the growing period or annual periods are given for irrigated crops and natural vegetation on the basis of field experiments, tank measurements and soil moisture studies. *Subject Headings: 1. Evapotranspiration 2. Irrigation 3. United States*—A.A.

7.5-195

551.573:551.578.1

Bolelli, Ed. (*Centre des Études Hydrogéologiques du Maroc*), *Coefficients d'infiltration et Coefficients d'évaporation: étude d'un cas précis dans des calcaires gréseux (pliocène et quaternaire de la côte du Maroc)*. [Coefficients of infiltration, coefficients of evaporation. Study of a given case on sandy limestone (pliocene and quaternary of the Morocco coast)] *I.U.G.G. International Association of Scientific Hydrology, Brussels, 1951, [Transactions]* 4:12-14, 1952. DWB—Study, made for the catchment area 40 km<sup>2</sup> of the oasis Ain Reboua near Rabat, shows that 83.5% of the annual precipitation (549 mm) is lost by evapotranspiration. The area has 20% forests (*Quercus Suber* L.), 45% pastures and 35% cultivated land, mainly under cereals. *Subject Headings: 1. Evapotranspiration 2. Hydrologic cycle Morocco*.—A.A.

7.5-196

551.573

Budyko, M. I., *Izmerenie estestvennogo isparenniia*. [Measurements of natural evaporation.] *U.S.S.R. Glavnoe Upravlenie Gidrometeorologicheskoi Sluzhby, Trudy Nauchno-issledovatel'skikh Uchrezhdenii, Ser. 1, Meteorologiya, No. 34:83-92, 1946. fig., 6 refs. DLC*—Two principal methods for determining the total evaporation from soil surface are mathematically analyzed. The first is the so-called gravimetric method (periodical weighing of monoliths (cores) of soil with plants.) The second method, presented by THORNTON and HOLZMAN, defines the total evaporation by measurement of the specific humidity on two levels above soil surface and by determination of the coefficient of turbulent exchange. The author prefers the second method but points out a mistake in the determination of the coefficient of turbulent exchange which exaggerates the value of evaporation from 200-300%. The author presents his own formula for determining the intensity of natural evaporation through the coefficient of turbulent exchange. *Subject Heading: 1. Evaporation measurement*—N. T. Zikeev.

7.5-197

551.573:551.578.41 551.579.2

Kaiteira, Pentti [*Finland*], *Snow melting in the spring and its effects on the opening of the waterways in Finland*. *International Association of Scientific Hydrology, Oslo 1948, [Transactions]*, 2:38, [1949]. DWB—Brief report on experiments made in 1934-37 to determine rate of melting of snow and evaporation from surface. It was found that on the average 45-50% melts in 5 days, 70% in 10 days, 85% in 15 days, and 95% in 30 days. At -2.9°C, .41 mm evaporated in one day, at +1.5°C, .29 mm, and at +4.3°C, .07 mm. On warmer days the dew point is often higher than the snow temperature resulting in condensation instead of evaporation. *Subject Headings: 1. Snow melt 2. Evaporation of snow 3. Finland*.—M.R.

7.5-198

551.573

Ståfält, M. G., *Om metoderna att bestämma avdunstningen i naturen*. [Methods for determining natural transpiration and evaporation.] (*K. Lantbruksakademien, Stockholm, Tidskrift*, 86(4):308-327, 1947. refs. p. 326-327. English summary p. 327. DLC—Some misinterpretations of the author's data by OLOF TRYSELIUS in his paper on *Evaporation in southern Sweden* are discussed. *Subject Headings: 9. Evaporation 2. Reviews*.—W.N.

## CONDENSATION

7.5-199

551.574.1:551.594.11

Dreisbach, K., *Die vertikale Verteilung der grossen Kerne in der unteren Troposphäre und ihr Zusammenhang mit dem elektrischen Potentialgefälle*. [The vertical distribution

large nuclei in the lower troposphere and its connection with the electric potential gradient.] *Archiv für Meteorologie, Geophysik und Bioklimatologie, Ser. A*, 9(1):36-53, 1956. 8 figs., tables, 18 refs. English and French summaries p. 36-37. DWB—Measurements of vertical distribution of large nuclei up to 2800 m were made in haze with a Zeiss conimeter in a glider. The values were only relative but comparable among themselves; they gave: diameter  $<1\mu$ , 4%;  $1-2\mu$ , 23%;  $>2\mu$ , 3%. Observations of potential gradient were made at the same time, and the curves showed remarkable similarity. The mean number of nuclei decreased from 10,000 at 430 m to 257 at 2600 m, gradient volt/m from 85 at 500 m to 19 at 2500-2800 m. In individual ascents nuclei and potential gradient gave peaks in the haze layers. *Subject Headings*: 1. Nuclei in free air 2. Potential gradient observations.—C.E.P.B.

7.5-200

551.574.1:551.510.42:551.590.25:551.577.3

Smith, E. J.; Kassander, A. R. and Twomey, S., **Measurements of natural freezing nuclei at high altitudes.** *Nature*, London, 177(4498):82-83, Jan. 14, 1956. fig., 3 refs. DWB—To test BOWEN's theory of stimulation of rainfall by meteor dust, measurements of temperature at which one ice crystal per liter formed at 3000 ft were made at Sydney (Australia) in Jan. 1954 and 1955, at Tucson (Ariz.) in Jan. 1955, and on a mountain peak in Hawaii. They showed maximum temperatures of about  $-20^{\circ}\text{C}$  on Jan. 12-14, 22-23 and 31, which roughly coincided with peaks in Sydney rainfall. *Subject Headings*: 1. Freezing nuclei 2. Meteoric dust 3. Rainfall singularities.—C.E.P.B.

7.5-201

536.7:551.574.41:551.508.74

†Hofmann, Gustav, **Die Thermodynamik der Taubildung.** [Thermodynamics of dew formation.] *Germany. Deutscher Wetterdienst, Berichte*, 3(18), 1955. 45 p. 13 figs. (inc. photos), 7 tables, 126 refs., 67 eqs. DWB—This comprehensive survey of the dew problem is based upon a critical survey of the literature and upon original experimental and theoretical research. Pt. 1 deals with the characteristics of dew and of related precipitation forms, its frequency and temporal distribution, the maximum night values of dew, its role in water balance, its biological value and methods of dew measurement. In Pt. 2, the thermodynamics of dew formations, dew is considered as a part of the nocturnal energy balance and a dew formula is derived from the equation of energy and mass transfer. It gives the temporal increase in amount of dew as a function of effective outgoing radiation and of the product of saturation deficit and ventilation. The methodology of dew measurement, the maximum of dew formation, the thermodynamics of rime formation, the analogy between dew formation and electrolytic deposition, etc. are considered. Pt. 3 contains a comparison of the theoretical work of the author with studies on the physics of dew formation of M. ROBITZSCH, F. ZUNKER, G. YAMAMOTO, etc. involving the energy measurement of dew by way of heat balance and turbulent exchange with T. HOMÉN's and E. WOLLNY's investigations on the energy of dew formation, etc. The influence of weather elements and of the microclimate on dew formation is analyzed. Pt. 4 contains a description of the construction, theory and use of a thermoelectric dew recorder. *Subject Headings*: 1. Thermodynamics of dew formation 2. Dew measurement techniques 3. Dew formation 4. Dew recorders.—I.L.D.

7.5-202

551.574.42:621.315

Diem, M., **Hochstlasten der Nebelfrostablagerungen an Hochspannungsleitungen im Gebirge.** [Maximum load of rime on high tension conductors in mountains.] *Archiv für Meteorologie, Geophysik und Bioklimatologie, Ser. B*, 7(1):84-95, 1955. 3 figs., 3 tables, 31 refs., 8 eqs. English and French summaries p. 84-85. DWB—The physics of ice deposition on wires from cloud elements is set out, with curves of deposited mass from droplets of  $2\mu$  diameter with different wind velocities. WAIBEL's measurements and others are then analyzed, and shown to fit in with the theoretical computations. The total load in  $t$  hours is given by  $c \cdot e^{at}$ , where  $c$  is a constant and  $a$  varies with location (especially height) between .003 and .03. *Subject Headings*: 1. Icing of transmission lines. I. Waibel, K.—C.E.B.P.

7.5-203

551.574.42:621.315

Waibel, K., **Die meteorologischen Bedingungen für die Nebelfrostablagerungen an Hochspannungsleitungen im Gebirge.** [The meteorological conditions for rime deposits on

1

... ..

先施 建築 設計 事務所

15

1. The first group of people who are interested in the study of the history of the world are the historians. They are the people who study the past and write about it. They are the people who tell us what happened in the past and why it happened. They are the people who help us to understand the world we live in today.

一、政治  
 二、經濟  
 三、社會  
 四、文化  
 五、教育  
 六、宗教  
 七、藝術  
 八、科學  
 九、法律  
 十、道德  
 十一、哲學  
 十二、歷史  
 十三、地理  
 十四、生物  
 十五、醫學  
 十六、農學  
 十七、工學  
 十八、商學  
 十九、法學  
 二十、政治學  
 二十一、經濟學  
 二十二、社會學  
 二十三、文化學  
 二十四、教育學  
 二十五、宗教學  
 二十六、藝術學  
 二十七、科學史  
 二十八、法律史  
 二十九、道德史  
 三十、哲學史  
 三十一、歷史學  
 三十二、地理學  
 三十三、生物學  
 三十四、醫學史  
 三十五、農學史  
 三十六、工學史  
 三十七、商學史  
 三十八、法學史  
 三十九、政治學史  
 四十、經濟學史  
 四十一、社會學史  
 四十二、文化學史  
 四十三、教育學史  
 四十四、宗教學史  
 四十五、藝術學史  
 四十六、科學史  
 四十七、法律史  
 四十八、道德史  
 四十九、哲學史  
 五十、歷史學  
 五十一、地理學  
 五十二、生物學  
 五十三、醫學史  
 五十四、農學史  
 五十五、工學史  
 五十六、商學史  
 五十七、法學史  
 五十八、政治學史  
 五十九、經濟學史  
 六十、社會學史  
 六十一、文化學史  
 六十二、教育學史  
 六十三、宗教學史  
 六十四、藝術學史  
 六十五、科學史  
 六十六、法律史  
 六十七、道德史  
 六十八、哲學史  
 六十九、歷史學  
 七十、地理學  
 七十一、生物學  
 七十二、醫學史  
 七十三、農學史  
 七十四、工學史  
 七十五、商學史  
 七十六、法學史  
 七十七、政治學史  
 七十八、經濟學史  
 七十九、社會學史  
 八十、文化學史  
 八十一、教育學史  
 八十二、宗教學史  
 八十三、藝術學史  
 八十四、科學史  
 八十五、法律史  
 八十六、道德史  
 八十七、哲學史  
 八十八、歷史學  
 八十九、地理學  
 九十、生物學  
 九十一、醫學史  
 九十二、農學史  
 九十三、工學史  
 九十四、商學史  
 九十五、法學史  
 九十六、政治學史  
 九十七、經濟學史  
 九十八、社會學史  
 九十九、文化學史  
 一百、教育學史  
 一百零一、宗教學史  
 一百零二、藝術學史  
 一百零三、科學史  
 一百零四、法律史  
 一百零五、道德史  
 一百零六、哲學史  
 一百零七、歷史學  
 一百零八、地理學  
 一百零九、生物學  
 一百一十、醫學史  
 一百一十一、農學史  
 一百一十二、工學史  
 一百一十三、商學史  
 一百一十四、法學史  
 一百一十五、政治學史  
 一百一十六、經濟學史  
 一百一十七、社會學史  
 一百一十八、文化學史  
 一百一十九、教育學史  
 一百二十、宗教學史  
 一百二十一、藝術學史  
 一百二十二、科學史  
 一百二十三、法律史  
 一百二十四、道德史  
 一百二十五、哲學史  
 一百二十六、歷史學  
 一百二十七、地理學  
 一百二十八、生物學  
 一百二十九、醫學史  
 一百三十、農學史  
 一百三十一、工學史  
 一百三十二、商學史  
 一百三十三、法學史  
 一百三十四、政治學史  
 一百三十五、經濟學史  
 一百三十六、社會學史  
 一百三十七、文化學史  
 一百三十八、教育學史  
 一百三十九、宗教學史  
 一百四十、藝術學史  
 一百四十一、科學史  
 一百四十二、法律史  
 一百四十三、道德史  
 一百四十四、哲學史  
 一百四十五、歷史學  
 一百四十六、地理學  
 一百四十七、生物學  
 一百四十八、醫學史  
 一百四十九、農學史  
 一百五十、工學史  
 一百五十一、商學史  
 一百五十二、法學史  
 一百五十三、政治學史  
 一百五十四、經濟學史  
 一百五十五、社會學史  
 一百五十六、文化學史  
 一百五十七、教育學史  
 一百五十八、宗教學史  
 一百五十九、藝術學史  
 一百六十、科學史  
 一百六十一、法律史  
 一百六十二、道德史  
 一百六十三、哲學史  
 一百六十四、歷史學  
 一百六十五、地理學  
 一百六十六、生物學  
 一百六十七、醫學史  
 一百六十八、農學史  
 一百六十九、工學史  
 一百七十、商學史  
 一百七十一、法學史  
 一百七十二、政治學史  
 一百七十三、經濟學史  
 一百七十四、社會學史  
 一百七十五、文化學史  
 一百七十六、教育學史  
 一百七十七、宗教學史  
 一百七十八、藝術學史  
 一百七十九、科學史  
 一百八十、法律史  
 一百八十一、道德史  
 一百八十二、哲學史  
 一百八十三、歷史學  
 一百八十四、地理學  
 一百八十五、生物學  
 一百八十六、醫學史  
 一百八十七、農學史  
 一百八十八、工學史  
 一百八十九、商學史  
 一百九十、法學史  
 一百九十一、政治學史  
 一百九十二、經濟學史  
 一百九十三、社會學史  
 一百九十四、文化學史  
 一百九十五、教育學史  
 一百九十六、宗教學史  
 一百九十七、藝術學史  
 一百九十八、科學史  
 一百九十九、法律史  
 二百、道德史  
 二百零一、哲學史  
 二百零二、歷史學  
 二百零三、地理學  
 二百零四、生物學  
 二百零五、醫學史  
 二百零六、農學史  
 二百零七、工學史  
 二百零八、商學史  
 二百零九、法學史  
 二百一十、政治學史  
 二百一十一、經濟學史  
 二百一十二、社會學史  
 二百一十三、文化學史  
 二百一十四、教育學史  
 二百一十五、宗教學史  
 二百一十六、藝術學史  
 二百一十七、科學史  
 二百一十八、法律史  
 二百一十九、道德史  
 二百二十、哲學史  
 二百二十一、歷史學  
 二百二十二、地理學  
 二百二十三、生物學  
 二百二十四、醫學史  
 二百二十五、農學史  
 二百二十六、工學史  
 二百二十七、商學史  
 二百二十八、法學史  
 二百二十九、政治學史  
 二百三十、經濟學史  
 二百三十一、社會學史  
 二百三十二、文化學史  
 二百三十三、教育學史  
 二百三十四、宗教學史  
 二百三十五、藝術學史  
 二百三十六、科學史  
 二百三十七、法律史  
 二百三十八、道德史  
 二百三十九、哲學史  
 二百四十、歷史學  
 二百四十一、地理學  
 二百四十二、生物學  
 二百四十三、醫學史  
 二百四十四、農學史  
 二百四十五、工學史</

[illegible]

...

...the ...

100

1. The first step in the process is to identify the problem or issue that needs to be addressed. This involves gathering information and understanding the context of the problem.

[illegible]



7.5-210

551.577.5:581.0

Glock, Waldo S., **Tree-growth and rainfall.** *American Geophysical Union, Transactions* 36(2):315-318, April 1955. table, 10 refs. **DLC**—Two methods of analysis of tree-rings to estimate rainfall are suggested: 1) study of rainfall types in relation to growth patterns and 2) direct correlation of tree growth and rainfall. For the study of growth patterns, 3 types are recognized: (1) California or Sierra type (rainy winter and dry summer, autumn and spring); (2) West Texas type (intermittent at any season) and (3) Arizona or varying type—sometimes with marked annual cycle and sometimes with fluctuating patterns. Since growth responds quite rapidly to moisture in dry soils, several rings may occur in a year under (2) and (3). For correlations, data from Santa Fe for March-July and Holman Pass tree ring data have been used for two independent periods 1850-97 and 1898-1941. Latter period showed better correlation. *Subject Headings:* 1. Tree growth patterns and rainfall types 2. Tree ring rainfall relationships 3. New Mexico.—*M.R.*

7.5-211

551.577.

Rakhmanov, V. V., **K voprosu o vlianii lesa na osadki.** [On the problem of the forest effect on precipitation.] *Meteorologiya i Gidrologiya*, No. 2:61-64, March/April, 1955. refs. **DLC**—In connection with the second edition of V. G. NESTEROV's book, "Obshchelesovodstvo" [General forestry], the author discusses the chapter dealing with the hydro-meteorological role of forests, in particular the section on the effect of forests upon precipitation. He criticizes the statements that forests increase precipitation by facilitating the condensation of moisture. *Subject Headings:* 1. Forest effects on precipitation 2. Forest hydrometeorology—*I.L.D.*

## RAIN AND SNOW

See also: **Snow conference proceed.** (Western Snow Conf.), 7.5-78; **Snow cover depth** (Abramova), 7.5-61; **Measurem. of precip. effect** (Robinson), 7.5-68; **Snow res. institutes** (de Quervain et al.), 7.5-71; **Infrared transmission through raindrops** (Johnson, Terrell), 7.5-144; **Soil temp. under snow** (Nagasawa, Makino), 7.5-162; **Snow melt and its effects on waterways** (Kaitera), 7.5-197; **Water supply forecasts** (Strauss), 7.5-217; **Hail growth** (Wolf), 7.5-249; **Electrical charges on raindrops** (Goyer, Handeer), 7.5-251.

7.5-212

551.578.4

Hallett, J., **Replica technique for the study of snow crystals.** *Weather*, 11(2):40-4 Feb. 1956. 4 figs. **DWB**—Describes the technique of making replicas with a solution of Formvar in ethylene dichloride with examples and notes on growth. *Subject Headings:* 1. Snow crystals.—*C.E.P.B.*

7.5-213

551.578.42(538)

\*Kosiba, Aleksander, **Opady śnieżne na Śląsky.** [Snowfall in Silesia.] *Wrocławskie Towarzystwo Naukowe, Prace, Ser. B*, No. 71, 1955. 40 p. 8 figs. (some fold.), 19 tables, 9 refs. On t-p: *Acta Meteorologica et Climatologica, Universitatis Wratislaviensis*. **DWE**. **DLC**. Also his: **Snowfalls in Silesia.** *Acta Geophysica Polonica*, Warsaw, 2(3):136-139, 1954. eqs. Polish summary p. 138-139. **MH-BH**—A detailed study of snowfall in Silesia based on observational data for 117 stations for the 1935-1940 period, published in various issues of the *Deutsches Meteorologisches Jahrbuch*, Pt. 3, of the Reichsamt für Wetterdienst and later the Deutscher Wetterdienst in der US-Zone. The data were found to be representative in spite of the brevity of the period. The results dealing with questions of the topographical distribution of annual and monthly frequencies (number of days with) snowfall in relation to altitude, and the causes of anomalies; the dates of first snowfall in autumn and of the last in spring; the potential periods of snowfall in various sections of the area; the variations of the annual and seasonal frequencies of snowfall and its correspondence with the thickness of the snow cover; hoar frost as a component part of snowfall (increasing with height, oceanity and latitude); the part played by snow in the total amount of precipitation and in the balance of ground and river waters—are presented in numerous tables, graphs and charts and discussed. The author stresses the difficulty of obtaining a complete picture of the phenomenon in the

hole area in view of the insufficiency or the lack of observation stations in high mountains and at remote points, as well as to the absence of uniform criteria for determining days with snowfall in case of mixed precipitation. *Subject Headings:* 1. Snowfall data 2. Snow cover 3. Snow melt 4. Silesia.—A.M.P.

7.5-214

551.578.46:551.571:551.43(497.1)

Manohin, V., *Topljenje snežnog pokrivača na planinama prema podacima sa Kredarice*. [Melting of the snow cover in mountains according to data for Kredarica Mountain.] *Yugoslavia. Hidrometeorološka Služba, Vesnik*, 3(3/4):105-106, July/Dec. 1954. DWB—Describes observations from which it appears that snow temperature (and consequently the snow line) is much more affected by dewpoint than by air temperature. *Subject Headings:* 1. Snow line and dew point 2. Kredarica Mt., Yugoslavia.—G.T.

7.5-215

551.578.46

Yosida, Zyungo, *A theoretical study on subsidence force of snow*. *Low Temperature Science, Sapporo, Japan, Ser. A, Physical Sciences*, v. 12:25-35, 1954. 3 figs., 6 refs., eqs. [In Japanese; English summary p. 35. DWB—The author derives a mathematical formula expressing the subsidence force of a snow cover, namely:  $F_s = 2bpD(t)$ ,  $D(t) = \frac{4}{B} \sqrt{\frac{nZ_0}{2pg}} \frac{\sqrt{A+Bt}}{t}$ , where  $F_s$ =subsidence force,  $b$ =thickness of the surface snow layer,  $p$ =snow density of this layer,  $g$ ,  $Z$ , and  $t$  are, respectively, the acceleration of gravity, the height of the horizontal base (upon which the snow layer is acting) above the ground surface and  $t$ , the time that has elapsed since the snow layer began to subside.  $A$  and  $B$  are two constants, representing the relation between initial thickness of any snow layer and the thickness after subsidence. *Subject Heading:* 1. Snow cover compaction.—Based on author's abstract.

## HYDROMETEOROLOGY

See also: Water economy (Lütschg-Loetscher et al.), 7.5-12; Soil moisture studies, 7.5-30; Hydrology bibliog. (I.U.G.G.), 7.5-33; Runoff evaluation from rainfall (Novotny), 7.5-63; Water level variations (Gur'ev), 7.5-89; Thunderstorms (Thomas), 7.5-131; Wind effects on water level (Kluzniak), 7.5-188; Hydrologic cycle (Boelli), 7.5-195; Snow melt & its effects on waterways (Kaitera), 7.5-197.

7.5-216

551.579:551.481.1

Sokolov, A. A., *Vliianie ozer na normu stoka rek*. [Influence of lakes on the norm of river flow.] *Meteorologiya i Gidrologiya*, Leningrad, No. 1:36-41, Jan./Feb. 1955. 2 figs., 2 tables, 3 refs. DWB—A water balance scheme for investigating the effect of the influence of lake basins upon the norm of river flow is described. For the European part of the U.S.S.R. it is shown (1) that in a forest zone the river flow diminishes with increasing areal surface occupied by lakes and (2) that in the southern forest zone the lake area of the catchment region sharply influences river flow. *Subject Headings:* 1. Lake influences 2. River flow 3. U.S.S.R.—I.L.D.

7.5-217

551.579.2:551.501:551.578.46:551.509.5

Strauss, Fred A., *Forecasting water supply through snow surveys*. *American Water Works Association, Journal*, 46(9):853-863, Sept. 1954. 6 figs. DLC—Techniques used in water supply forecasting for the season as employed in California by the Cooperative Snow Surveys and other agencies are described and illustrated. The first snow surveys for the purpose of runoff forecasting were made in 1918, using techniques and data initiated by J. E. CHURCH of the Univ. of Nevada in the early part of the century. Surveys are now paid for by the state and U. S. Government and are supervised by the State of California. They cover 3 watersheds from the Shasta River to Cottonwood Creek Basin. Accuracy of forecasts is shown on a scatter diagram. *Subject Headings:* 1. Water supply forecasts 2. Snow surveys 3. Sierra Nevada Range, Calif.—M.R.

7.5-218

551.579:628.1(4)

**The water problem in Great Britain.** *Nature*, London, 176(4494):1133-1134, Dec. 1955. **DWB**—Increasing population and increasing use of water per head, especially in industry, have raised consumption to 1750 million gallons a day. Rainfall averages 2600 million gallons but is unevenly distributed in space and time. Underground supplies are falling. A Central Advisory Water Committee has been appointed to consider the overall problem. *Subject Headings: 1. Water supply survey 2. Great Britain.—C.E.P.B.*

7.5-219

551.579.2:551.584

**CHigirinskiĭ, P. F., Elementy limannogo orosheniia na mezhpolosnykh poliakh.** [The elements of flooding irrigation on fields between forest strips.] *Meteorologiya i Gidrologiya*, No. 2:32-33, March/April, 1955. fig., ref. **DLC**—Contemporary concepts on the water regulating role of forest strips must consider the water regulating role of snow drifts that are formed in forest strips. It is shown that forest strips can be used to form snow drift dikes for flood irrigation especially in drought regions. *Subject Headings: 1. Water supply from snow 2. Forest snow pack.—I.L.D.*

7.5-220

551.579.4:551.4

**CHekalovskii, E. F., Ob odnom nelogichnom trebovanii "Nastavleniia."** [Illogical requirement in the "Instructions."] *Meteorologiya i Gidrologiya*, No. 2:47, March/April, 1955. **DWB**—Criticizes the requirement of calculating the velocity of flow in water discharge studies to three significant figures. *Subject Heading: 1. River discharge calculations.—I.L.D.*

## CLIMATOLOGY AND BIOCLIMATOLOGY

### CLIMATOLOGY

*See also: Annual climatological reports* (Davos. Switzerland. Schweizerisches Forschungsinstitut), 7.5-18.

7.5-221

551.58:001

**Dammann, W., Vor einer Neuordnung des Beobachtungs- und Arbeitssystems der praktischen Klimatologie?** [Improvement of the observation and working methods of practical climatology?] *Archiv für Meteorologie, Geophysik und Bioklimatologie*, Ser. 2, 7(1):1-10, 1955. English and French summaries p. 1. **DWB**—In most countries climatology cannot be further improved by increasing number of stations, except temporarily for special problems such as microclimatology. For technical problems daily means and the usual observation hours (7, 14, 21) are insufficient; night observations are often required. Author suggests a network of first order stations supplemented by mobile units. The possibility of combining climatological and synoptic networks with the same hours is considered. All observations should be punched on cards and frequencies as well as means computed. Investigations should be carried out regionally by teams at the main stations, with local knowledge. *Subject Heading: 1. Climatological research.—C.E.P.B.*

### CLIMATOLOGY OF PARTICULAR PLACES

*See also: Climate of Hungary* (Görög), 7.5-11; *Climate of St. Moritz* (Lütsch-Loetscher et al.), 7.5-12; *Sailing directions* (Gr. Brit. Hydrogr. Dept.), 7.5-45; *Climate of White Sea* (U. S. Hydrogr. Off.), 7.5-46; *Climate of El Salvador* (El Salvador. Centro Nac. de Agronomía), 7.5-74.

7.5-222

551.582.2(529)

\*†**Formosa Bank.** Economy Research Laboratory [T'ai wan yin hang ching chi chiu shih] **T'ai wan ch'i hou chih.** [Climate of Formosa.] Taipei, 1954. 220 p. 101 figs., 135 tables, refs. In Chinese. **DLC**—A good climatology of Formosa, which contains the following chapters: 1) geographical environment, 2) climatic provinces and climatic classification, 3) monthly climatic characteristics with tables, 4) air temperature, 5) rainfall, 6) wind

humidity, 8) evaporation, 9) thunderstorm, 10) adaptability of principal agricultural products, 11) distribution of forests, 12) mountain climate, 13) climatic cycle of rainfall, temperature and typhoon, 14) annual regime of climatic elements, 15) rainfall and run-off in principal river basins and 16) insects and their distribution. *Subject Headings:* 1. Climate of Formosa 2. Climatic data 3. Formosa.—*H. Arakawa.*

7.5-223

551.582.2(761)

\*U. S. Weather Bureau, *Climatological summary, Auburn, Alabama, 1855-1952*. Montgomery, Alabama, 1953. 30 p. mostly tables. Price: \$.20 from Weather Bureau Office, Montgomery, Ala. **DLC**—A good example of getting the most out of a little available data. Besides normal and comparative data for temperature, precipitation, and the usual elements, the publication contains data and analysis of frost, dew, hail, sleet, snow, tornado, evaporation, drought, wet periods, heating and cooling degree days, earthquakes, daylight, sunshine, twilight, etc. Frequencies of precipitation amounts of .01, .05, .10, .25, .50, 1.00 and 2.00 in. or more, and of maximum and minimum temperatures of 90°, 95°, 100° and 105°F and over 2°, 30°, 25°, 20°, 15°, 10°, 5° and 0° or below, monthly precipitation and temperature means and extremes, etc. for each year from 1855-7 and 1881-1952 are tabulated. A summary of the climate and a description of station and list of observers are also included. *Subject Headings:* 1. Climatic data summaries 2. Climate of Auburn, Alabama 3. Auburn, Alabama.—*M.R.*

7.5-224

551.582.2(761)

\*U. S. Weather Bureau, *Climatological summary, Troy, Alabama, 1872-1953*. Montgomery, Alabama, 1954. 26 p. numerous tables. **DWB**—Data and discussion of climate, precipitation (averages, extremes, frequency, maximum 24-hour), temperature (average, extreme, range, degree-days, frequency, diurnal fluctuations), sunshine, snow, sleet, dew, frost, humidity, tornadoes, wind and daylight. Monthly values for each year are given for major elements. Names of observers (and period served) are listed. *Subject Headings:* 1. Climate of Troy, Alabama 2. Troy, Alabama.—*M.R.*

## CLIMATIC CHANGES

See also: **Historical climates** (Arakawa), 7.5-77.

7.5-225

551.583.3

Bartha, Lajos, Jr., *Bacsák György kandidátusi értekezésének vitája*. [Debate on G. Bacsák's thesis for Ph.D.] *Időjárás*, Budapest, 58(5):321, Sept./Oct. 1954. **DWB**—G. BACSÁK presented as his thesis: **Astronomical interpretation of the pliocene and pleistocene periods**. In this work shortcomings of the ice age theory of MILANKOVIČ were corrected and another 100,000 years were added to the 600,000 years of paleoclimatic records hitherto available. *Subject Headings:* 1. Ice ages 2. Paleoclimates 3. Debates 4. Bacsák, G.—*G.T.*

7.5-226

551.583.3

Emiliani, Cesare; Flint, Richard Foster and Urey, Harold C., *Past climates of the earth: an NBC radio discussion*. *Chicago. Univ., Round Table*, No. 870, Dec. 12, 1954, p. 1-10. **DWB**—This round table discussion brings out recent advances in geochronology by C<sup>14</sup> and oxygen isotope measurements, fossils from deep sea samples or from glacier moraines, and deductions as to past climates and glaciation. PROF. UREY is of the mind that we may be in the middle of an ice age which has fluctuated widely but endured for about a million years. *Subject Headings:* 1. Climatic changes 2. Glacial periods.—*M.R.*

7.5-227

551.583.3:581.16

Straka, Herbert, *Die Auswertung pollenanalytischer Ergebnisse*. [The evaluation of pollen analysis results.] *Naturwissenschaftliche Rundschau*, 8(12):480-483, Dec. 1955. 2 figs., 3 refs. **DWB**—The principles of pollen analysis and construction of dated pollen diagrams are described. Specimen profiles of tree and hazel pollen and of herb pollen back to 8640 B.C. are shown and described, including climatic bearing. *Subject Heading:* 1. Pollen analysis.—*C.E.P.B.*

## MICROCLIMATOLOGY

See: Plant climate (Berger-Landfeldt, 7.5-78; Temp. recording (Berger-Landfeldt, 7.5-87).

## BIOCLIMATOLOGY

See also: Man in a cold environment (Burton, Edholm), 7.5-9.

7.5-228

551.586:612.6

Lotmar, R. and Häfelin, J., Über den Einfluss der Witterung auf den Schwefelstoffwechsel von Kaninchen. [On the influence of weather on sulfur metabolism in rabbits.] *Archiv für Meteorologie, Geophysik und Bioklimatologie, Ser. B*, 7(1):133-145, 1955. 4 figs., 3 tabs., 24 refs. English and French summaries p. 133. DWB—During four months the urine of certain number of rabbits, which had received radioactively marked sodium-sulfate ( $\text{Na}_2\text{SO}_4$ ) has been examined daily as to its activity. It resulted that on certain days the secretion of sulfur was distinctly above the normal value. This was the case on all cold front days, when a polar air mass before as well as after their passage. The five cold fronts followed by a tropical air mass on the other hand produced no biotrophic effect on the sulfur metabolism. Subject Headings: 1. Bioclimatology 2. Physiological effects 3. Rabbits.—Authors' abstract

7.5-229

551.586:612.6

Undt, W. (Vienna), Erholung und Klima. [Convalescence and climate.] *Wetter und Leben*, Vienna, 7(34):61-67, 1955. 10 refs. DLC—A general discussion of the relations between constitutional type, type of cure, disease and climatic effects is presented. The climatic characteristics of various types of health resorts, the choice of convalescence periods and the duration of vacations are considered. Subject Headings: 1. Health resorts 2. Medical climatology 3. Climatotherapy.—I.L.D.

7.5-230

551.586:632.9:633

Vámos, Rensó, Az időjárás és a rizs barnulósos betegségének kapcsolata. [Relation between weather and the browning disease of rice plants.] *Időjárás*, Budapest, 58(5):273-274, Sept., Oct., 1954. table, 2 eqs. DWB—The browning disease which causes considerable damage among rice plants in Hungary is found to be connected with sudden drops in summer temperature. The author gives his interpretation of the harmful biochemical processes taking place in the paddy field under the influence of temperature fluctuations. Subject Headings: 1. Plant diseases 2. Temperature drop 3. Bioclimatology 4. Rice 5. Hungary.—G.T.

## ENVIRONMENTAL INFLUENCES

See also: Lake heat balance (Eckel), 7.5-168; Ocean currents (van Dijk), 7.5-180; Forest snow pack (Chigirinskii), 7.5-219.

7.5-231

551.58

Asci, Girolamo (Univ. of Perugia), Continentalità e insularità. [Continentality and insularity.] *Giornale di Meteorologia*, Genoa, 21(34):62-64, May-Aug., 1954. 2 figs., 2 tables, 6 eqs. MH-BH—Indices of continentality and insularity are developed taking into account both horizontal and vertical extension. Subject Headings: 1. Continentality 2. Insularity.—I.L.D.

## SYNOPTIC CLIMATOLOGY

See also: Synoptic climatology (Jayamaha), 7.5-135.

7.5-232

551.589

\*Vowinkel, E., Beitrag zur Witterungsklimatologie Südafrikas. [Contribution to weather-type climatology of South Africa.] *Archiv für Meteorologie, Geophysik und Bioklimatologie, Ser. B*, 7(1):31-51, 1955. 9 figs., 11 tables. English and French summaries p. 10. DWB—The frequencies of main weather types for the Pretoria region: fine weather, weakened fine weather, warm air, cold air, monsoon, shower, equatorial, bad weather,

ated and typical isobars, winds, fronts and weather of each shown in charts. The monthly frequencies of interdiurnal temperature rises and falls, their duration, droughts and rainy days are tabulated. Hourly rainfall frequencies and a conventional climatic table for Pretoria are given. The annual variation of temperature, rainfall and raindays (3 day means), are plotted and the singularities discussed. *Subject Headings:* 1. Synoptic climatology 2. Weather types 3. Pretoria, S. Africa.—*C.E.P.B.*

## MISCELLANEOUS

### COSMIC INFLUENCES

See also: Meteor trail drift Robertson et al.), 7.5-65; Sunspot effects on temp. Nantahasis), 7.5-153; Freezing nuclei measurem. (Smith et al.), 7.5-200.

7.5-233

551.590.21

Boute, Carmen. Wirkungen elektrischer Felder und Strahlungen atmosphärischen und kosmischen Ursprungs auf das Wasser. [Effect of electric fields and radiations of atmospheric and cosmic origin on water.] *Archiv für Meteorologie, Geophysik und Bioklimatologie, Ser. B*, 146-155, 1955. 6 figs., table, 7 refs. DWB—Passing water between iron electrodes which a weak alternating potential was applied, and subsequent warming, accelerated the saturation of dissolved  $\text{CaCO}_3$  on colloidal iron hydrates obtained by corrosion of the electrodes. Daily observations in Brussels and Florence in 1952-54 in a chamber shielded with different materials showed (10-day means) correlations up to 0.57. *Subject Heading:* 1. Cosmic influences. —*E.P.B.*

7.5-234

551.5:541.18: 551.590.21

Neuwirth, R.. Atmosphärische Einflüsse auf die Alterung eines anorganischen Sols. Atmospheric influences on the alteration of an inorganic sol. *Meteorologische Rundschau*, Linz, 8, 7, 81:108-113, July/Aug. 1955. 8 figs., 13 refs. DLC—The coagulation of colloid preparations of arsenic trisulphide was measured daily by a photometric method, controlled electron microscope, for 2 years. Change of coagulation was found to depend on the passage of cold fronts influencing the troposphere to at least 500 mb, and on the horizontal shear (as a measure of vorticity). The speed of change also increased following increased height of the 1000 mb surface. The effect is related to changes of charge on the colloid but the explanation not clear. It may be due to the effect of extraterrestrial 2-5 cm waves on the structure of water. *Subject Headings:* 1. Meteorological effects on colloids 2. Colloid coagulation. —*E.P.B.*

7.5-235

551.590.21:541.18

Piccardi, Giorgio (*Dir. Chem. Phys. Inst. Florence Univ.*) and Doat, Henri Yves (*Dir. Unter-Tullnerbach Wasserleitung, Vienna, Unter-Tullnerbach*), Sulla variazione annuale registrata a Vienna in base al test inorganico. [Annual variation registered at Vienna on the basis of an inorganic test.] *Geofisica e Meteorologia*, Genoa, 311 2:30, Jan./April 1955. fig. DWB—Comparative graph shows a sharp Feb. minimum of  $T$  (%) values for both  $D$  and  $F$  ( $D$ =shielded,  $F$  not based on 1953 results of tests of precipitation of  $\text{BiOCl}$  at Vienna Unter-Tullnerbach near Wiental Wasserleitung. Text states there is a sharp minimum in Feb. in cases, from data at Florence, Brussels and Vienna. Experiments are made in morning and evening, in shielded and unshielded enclosures. See 6.5-171, May 1955, *MAB*. *Subject Headings:* 1. Annual physico-chemical variations 2. Bismuth oxychloride precipitation 3. Solar influences 4. Unter-Tullnerbach, Austria.—*M.R.*

7.5-236

551.590.21:523.7:550.38

Roberts, Walter Orr. *Dir. High Altitude Obs., Boulder, Colo.* Can we blame the sun for our weather? *Popular Mechanics Magazine*, Chicago, 10316:165-69; 234-240, June 1955. photos, illus. DWB—A semipopular and well illustrated article on the sun's structure and temperature, the high altitude astrophysical observatory at Boulder and Climax, Colo., the synchrography or artificial eclipse simulating telescope at Climax, the work of the observatory.

and the usefulness of results in helping to study or predict magnetic storms which affect radio communication, or even rainfall at Kansas City or cold fronts in the Midwest. *Subject Headings: 1. Solar physics 2. High altitude observatories 3. Solar-terrestrial relationships 4. Climax, Colo.—M.R.*

## OPTICAL PHENOMENA

See also: *Twilight phenomena* (Bigg), 7.5-103; *Geomagnetic disturbances* (Wiese), 7.5-106.

7.5-237

551.593.62

Richardson, W. E., *Bouguer's [Bouguer's] halo?* *Weather*, 10(10):355, Oct. 1954. 2 figs., ref. DWB—Alston, Nov. 7, 1954, fog bow and glory seen from high ground. *Subject Headings: 1. Bouguer's halo 2. Ulloa's ring 3. Glories.—C.E.P.B.*

7.5-238

551.593.62(0)

Khan, Mohd A. R., *Early theories of rainbows.* *Weather*, 10(10):358-359, Oct. 1954. DWB—Correct explanation was first given by MUHAMMAD IBN MAS'UD IBN MUSLIP QUTUB AL-DIN (born 1236). *Subject Headings: 1. Rainbow theory 2. History of rainbows.—C.E.P.B.*

7.5-239

551.593.62

Ashmore, S. E., *Unusual halo phenomena.* *Meteorological Magazine*, London, 84(99):287-288, Sept. 1955. DWB—Feb. 5, 1955, at Wrexham, persistent brilliant upper arc in contact to 22° halo and a sun-pillar. *Subject Heading: 1. Halo observations.—C.E.P.B.*

7.5-240

551.593.62

Crabbe, J. A., *Rare solar haloes.* *Weather*, 10(10):359, Oct. 1955. fig. Also: Ashmore, S. E., *Minor halo complex at Wrexham, Feb. 5, 1955.* *Ibid.*, 359-360. And: Scorer, R. C., *The Parry arc.* *Ibid.*, 360, fig. DWB—CRABBE describes complex at Sistiana, N. Italy, June 13, 1954, with 11° halo and other curious features. ASHMORE observed upper arc in contact to 22° halo persisting from sunrise to sunset, also sun pillar and parheliion, at Wrexham, Feb. 5, 1955. SCORER gives sketch of halo complex in London, March 2, 1954. The Parry arc was faint but distinctly colored. *Subject Headings: 1. Halos 2. Parry arc.—C.E.P.B.*

7.5-241

551.593.62

Halo [in] Atlantic Ocean; South Pacific Ocean; Western Mediterranean Sea; Pacific Ocean. *Marine Observer*, 25(170):213-214, Oct. 1955. fig. MH-BH—Solar halo of radius  $14\frac{1}{2}^\circ$  in 7°N 14°W. Lunar halos of 20°10' (inner edge) in 26½°S 170°W and of 19° in 37°S 1°E. Lunar halo complex in 22°S 134°W showed 22° halo, concentric arcs of 75° radius (through sun) and 60° and an antisolar arc (sketch). *Subject Heading: 1. Halo observations.—C.E.P.B.*

7.5-242

551.593.65

Ludlam, F. H., *Luminous night clouds.* *Weather*, 10(12):421-423, Dec. 1955. photo. DWB—Noctilucent clouds were frequently reported in 1885-1886, rarely in later years. From simultaneous photographs heights were calculated as 74-92 km, moving from NE at 50-300 m/s. They may be meteor dust or ice crystals on meteor dust. *Subject Heading: 1. Noctilucent clouds.—C.E.P.B.*

## ELECTRICAL PHENOMENA

See also: *Scatter propagation* (Norton, Wiesner), 7.5-1; *Solar radio noises* (Kawakami et al.), 7.5-147; *Nuclei distrib. in lower troposphere* (Dreisbach), 7.5-199; special bibliography on *Atmospheric Radioactivity*, p. 616.

7.5-243

551.594.1/2:537.792.

Martinoli, C. A. M., *Nuevo soporte y conexión para la determinación del potencial eléctrico atmosférico, con sonda iónica y electrómetro, utilizando método de cero.* [A new

and and attachment for determination of electric atmospheric potential, with an ionic collector and electrometer, utilizing method of Cero.] *Meteoros*, Buenos Aires, 4(4):324-326, Oct./Dec. 1954. fig. English summary p. 324. **DWB**—A description, illustrated with a diagram, of a new stand and attachment for obtaining absolute values of the atmospheric electric field by means of an ionic collector and electrometer. Although made of metal and of vertical design, the stand does not cause disturbances in the uniform electrical field existing previously so that the apparatus can be built fairly high in comparison to the measuring round. *Subject Headings*: 1. Electrometers 2. Atmospheric electricity measurement.—*Based on author's abstract.*

7.5-244

551.594.1:551.43

Reiter, Reinhold (*Munich*), **Ergebnisse luftelektrischer Messungen auf dem Zugspitzplatt a 2500 m Seeöhe.** [Results of atmospheric electricity measurements at the Zugspitze, 5000 m above sea level.] *Geofisica Pura e Applicata*, Milan, 30(1):155-169, Jan./April 1955. 3 figs., 2 tables, 4 refs. German and English summaries p. 155-156. **MH-BH**—Besides our continuous synoptic records of the air-electric elements in the region of the Zugspitze (Wetterstein Mountains, Bavarian Alps), a measuring excursion has been undertaken to the "Zugspitzplatt" in order to clarify some special questions (Aug. 1954). On this plateau, 2500 m above sea level, readings of the potential gradient have been recorded with a transportable instrument and the polar conductivities of the air have been measured. Comparing exactly the readings recorded on the Zugspitze-Peak (Z, 2963 m above sea level) with those recorded on the Zugspitzplatt (P) we could show that the values measured on the peak—in spite of the exposed situation of this station—have to be considered as representative and free from disturbing secondary phenomena. Our former observation that the accessory potential gradient during snowfall has a positive sign, and during rain shows a negative one, has been confirmed. On days when convection prevails, the deviation of the diurnal variation of the potential gradient on P from the diurnal variation on Z indicates distinctly the elevation up to 2500 m, caused by the exchange of nuclei and large ions. During fog lifted up from lower cloud levels (stratus, stratocumulus) potential gradient and polar conductivities on station P show the same behavior as in low altitudes. If station P is reached by descending currents, the negative conductivity sometimes is clearly observed to rise separately. It has been noticed that on the base of a standing lenticular crest cloud there are free electric charges of negative sign, and on the upper surface, probably, positive ones. On the surface or fore part of these clouds a separate increase of the negative conductivity could be measured distinctly. *Subject Headings*: 1. Atmospheric electricity 2. Mountain effects 3. Zugspitze, Germany.—*Author's abstract.*

7.5-245

551.594.11

\*Czyszek, Wacław (*Polish Academy of Sciences*), **Der mittlere tägliche Gang des luftelektrischen Potentialgradienten an ungestörten Tagen in Swider.** [Average course of daily potential gradient of atmospheric electricity during calm days in Swider.] *Acta Geophysica Polonica*, Warsaw, 2(3):149-155, 1954. 3 figs., 4 tables, 6 refs. Polish summary p. 155. **MH-BH**—Presents results of the study of electric potential gradient daily variation obtained from recordings of 2 Benndorf quadrant electrometers installed at the Swider (near Warsaw) Geophysical Observatory only on 58 perfectly calm days (evenly distributed throughout 1953). The mean daily course shows two maxima—between 6-8 a.m. and 6-8 p.m. through the whole year, except Oct. when there is only one maximum between 4-6 p.m. The main minimum occurs about 4 a.m. and a secondary minimum about 8-10 a.m. in fall and winter and about noon during the rest of the year. The mean yearly value of the potential gradient in 1953 was 82 V/m. *Subject Headings*: 1. Diurnal potential gradient 2. Potential gradient meters 3. Swider, Poland.—*A.M.P.*

7.5-246

551.594.11

\*Hatakeyama, H. and Kawano, M., **On the diurnal variation of atmospheric potential gradient in the Japan Archipelago.** *Papers in Meteorology and Geophysics*, 4(2):55-60, Sept. 1953. 2 figs., 4 tables, 5 refs. **MH-BH**—Data on average diurnal variation of atmospheric potential gradient at eight Japanese stations (representing both rural and city locations) in

winter and summer are presented in tabular and graphical form and briefly commented.  
**Subject Headings:** 1. Potential gradient variations 2. Japan.—G.T.

7.5-247

551.594.11:551.594.221:551.508

Kitagawa, N.; Tizuka, T.; Murai, K. and Kobayashi, M., On some aspects of lightning discharge observed by electrostatic fluxmeter. *Geophysical Magazine*, Tokyo, 25(3/4):242, March 1954. 7 figs., 9 refs., 3 eqs. MH-BH—Field variations due to lightning charges were investigated by means of an electrostatic flux meter the output of which is fed parallel to a magnetic-tape recorder and to an oscilloscope. The great majority of observed field variations are slow field changes with duration ranging from 0.1 to 0.5 sec, the rest consisting of rapid field changes with a duration of 0.001 sec. Such a slow field variation indicates that the effective velocity of electric charges neutralized at the inter-cloud discharge is of order lower than that of the stepped leader, and that further investigation is necessary to understand physically the mechanism of such a discharge. The records of rapid field-changes confirm the existence of a pocket of positive charge in the cloud base. **Subject Headings:** 1. Lightning discharges 2. Potential gradient variations.—Authors' abstract.

7.5-248

551.594.13:551.52

Kamiyama, Hiroshi (*Tôhoku Univ.*), Ion production rate in an atmosphere of exponential rising temperature with height. *Tôhoku University, Science Reports, 5th Ser., Geophysics* 6(1):11-18, Aug. 1954. 6 figs., 22 refs., 10 eqs. MH-BH—Assuming that the temperature increases exponentially with height above the mesopause, the expression for the distribution of the ion production rate is derived. The effect of the temperature variation is also examined. The maximum rate of ion production and the height at which it occurs show the anomalous variation in the course of a day, the former being minimum and the latter being maximum at noon, in the high region, whereas in the low region their variations follow almost completely CHAPMAN's law which is derived from the assumption of an isothermal atmosphere. It seems that the results partially give an account of the anomalous behavior of the F2 layer. **Subject Headings:** 1. Ion production rate with height 2. Isothermal atmosphere.—Author's abstract.

7.5-249

551.594.21:551.57

Wolf, Franz, Hagelwachstum eine Quelle der Gewitterelektrizität. [Hail growth the source of atmospheric electricity.] *Naturwissenschaften*, 42(24):641-642, Dec. 1955. 2 refs. DWB—The growth of hailstones must be accompanied by a steady development of electricity through the FARADAY-SOHNCKE effect, positive on the hailstone, negative on the water spray carried away. The latter gives the negative region at middle levels, while the break up of falling hailstones explains the lower positive region. **Subject Headings:** 1. Thunderstorm electricity 2. Hail.—C.E.P.B.

7.5-250

551.594.221:551.508

Pierce, E. T., The influence of individual variations in the field changes due to lightning discharges upon the design and performance of lightning flash counters. *Archiv für Meteorologie, Geophysik und Bioklimatologie, Ser. A*, 9(1):78-86, 1956. 5 figs., table, 4 refs. German and French summaries p. 78. DWB—The types of electrostatic field change > 1 km from cloud—cloud or cloud—earth flashes at Cambridge, England, are examined. Lightning flash counters responding only to the electrostatic component are least in error. The performance of a counter operating on a threshold field of 0.9 v/m is tabulated. Only 1% of flashes last > 1 sec, and none were recorded at a rate > 10/min. A simple low frequency circuit with an insensitive period of about 1 sec for counting discharges to earth is described. **Subject Headings:** 1. Lightning counters 2. Cambridge, England.—C.E.P.B.

7.5-251

551.594.25:551.578

Goyer, Guy G. and Handler, George S., Water-vapor condensation as a cloud-droplet charging mechanism. *Journal of Meteorology*, 12(6):569-570, Dec. 1955. fig., 13 refs. DWB—An experimental study of charges produced by condensation was made on droplets given by condensation of ion-free water vapor on nuclei of ammonium chloride. No charge was observed on any droplets. **Subject Heading:** 1. Electrical charges on raindrops.—C.E.P.B.

## AURORAS

7.5-252

551.594.5

Meinel, A. B. (*Verkes Obs.*), **Systematic auroral motions.** *Astrophysical Journal*, Chicago, 12(12):206-208, July 1955. fig., 6 refs. DWB, DLC—A reply to criticism of McLAUGHLIN (see 6.7-342, July 1955, *MAB*), MEEK (see 7.4-298, April 1956, *MAB*), and BLESS, GARTLEIN and KIMBALL (1955) who deny the conclusions of MEINEL and SCHULTE (1953) that there is a distinct time relationship in direction of motion of auroral rays, etc. MEINEL claims that there may not be an exact or detailed local time relationship, but merely a systematic relation which may be hard to detect by the naked eye. The idea that the excitation pattern may reverse itself at noon and midnight is generally accepted but the idea of mass motion is harder for some to accept. The author maintains that evidence exists for such mass motions (electrojet stream) and illustrates a theoretical current system and two actual current systems schematically. *Subject Headings: 1. Auroral drift 2. East-west auroral motion 3. Ionospheric winds 4. Electrojet stream theory.—M.R.*

7.5-253

551.594.51:523.75:550.385

Beiser, Arthur (*N. Y. Univ.*), **On an interplanetary magnetic field.** *Journal of Geophysical Research*, Wash., D. C., 60(2):155-159, June 1955. 7 refs., 14 eqs. Also his: **Solar-terrestrial time delays.** *Ibid.*, 60(2):161-164, June 1955. 6 refs., 11 eqs. DWB—1) Considerations suggesting the existence of an interplanetary magnetic field are presented. Such a field would not exceed about  $5 \times 10^{-8}$  gauss, and its presence can explain the observed cutoff in the primary cosmic-ray momentum spectrum. A field existing within the earth's orbit can account for all or part of the observed solar-terrestrial time delays in aurorae and magnetic storms. The time required for the formation of a magnetic field pervading the solar system is less than  $10^3$  yrs, and its lifetime against decay is probably more than  $10^{10}$  yrs. 2) The observed delay of about 24 hrs between the meridian passage of a sunspot or flare and the onset of an associated magnetic storm or aurora is shown to originate in the magnetic deflection of the ion streams involved. If a solar magnetic dipole is exclusively responsible, its moment must be between  $6 \times 10^{27}$  and  $10^{29}$  gauss. Should both fields act, which is likely, then the above figures represent maxima. *Subject Headings: 1. Interplanetary magnetic field 2. Solar-terrestrial time delays 3. Auroral physics.—Author's abstract.*

7.5-254

551.594.51

Turner, R. G. and Nicholls, R. W., **Intensity measurements of molecular spectra, Pt. 2, An experimental study of band intensities in the first positive system of  $N_2$ .** London, Ontario, University of Western Ontario. Dept. of Physics, Contract AF 19(122)-470, Scientific Report, No. 14, April 10, 1954. 26 p. 3 figs., 7 tables, 13 refs., 4 eqs. MH-BH—Integrated intensities of 52 bands of the  $N_2$  first positive system have been measured using a recording infrared spectrometer. These data have been interpreted as vibrational transition probabilities which were compared with theoretical values calculated under the assumption that the electronic transition moment is independent of internuclear separation. The comparison shows that the assumption is not valid for this electronic transition. The experimental band intensities have been used together with the theoretical transition probabilities to determine the dependence of the electronic transition moment upon internuclear separation. Over the range  $1.17 < r < 1.59 \text{ \AA}$  of internuclear separation this dependence may be represented by

$$R_e(r) = \text{const. exp. } (-3.02 \text{ } r).$$

(For Pt. 1, see 4.7-225, July 1953, *MAB*.) *Subject Headings: 1. Auroral physics 2. Infrared spectroscopy 3.  $N_2$  spectra.—Authors' abstract.*

## RADIO METEOROLOGY

7.5-255

551.594.6:523.45

**Jupiter emits static (and) Short waves from stars.** *Science News Letter*, Wash., D. C., 67(16):243, April 16, 1955. DLC—BURKE and FRANKLIN detected radio noise from Jupiter that sounded like "thunderstorm interference on a broadcast receiver." The series are

heard at 22 Mc about one day out of three during the 6 min when the planet crosses the narrow path of their radio telescope in Seneca, Maryland. *Subject Headings: 1. Radio noise 2. Jupiter 3. Sferics from planets.—W.N.*

7.5-256

551.594.7:621.396 538.3

Furutsu, Koichi, **Propagation of electro-magnetic waves over a flat earth across a boundary separating different media and coastal refraction.** *Japan. Radio Research Laboratories, Tokyo, Journal*, 2(7):1-49, Jan. 1955. 5 foot-refs., numerous eqs. DWB—The theory of propagation of radio wave over a flat homogeneous earth, transmitted across a boundary of discontinuity, such as a coast-line, is theoretically treated in three dimensional space. The derived formula for wave strength is exclusively expressed in the terms of the functions of the form:  $U(z,n) = \int_z^\infty dx e^{-x^2} \int_{nz}^\infty e^{-y^2} dy$ , which has a close connection with the function  $G(u)$  introduced by CLEMMOW. The coastal refraction, the refraction of wave path at a coast line is also treated, and the refraction angle is theoretically derived in a simple form for practical use. Further, the wave propagation across two or more boundaries of discontinuities is also discussed. *Subject Headings: 1. Electromagnetic wave propagation 2. Radio wave propagation 3. Refraction of electromagnetic waves.—Author's abstract.*

7.5-257

551.594

Gordon, William E., **Radio scattering in the troposphere.** *Institute of Radio Engineers, N. Y., Proceedings*, 43(1):23-28, Jan. 1955. 8 figs., 11 refs., 19 eqs. DWB—The theory of radio scattering in the troposphere is modified in the light of recent observations of the fluctuations in refractive index. The theory is applied to the communication problem and yields some characteristics which are peculiar to the scattering mechanism. One characteristic imposes a limit on the maximum size of an antenna which yields its full theoretical gain. The characteristic is deduced from the prediction of diversity distance. Height gain is also deduced from diversity distance. Other characteristics are derived pertinent to the communication problem, including fading rates and frequency bandwidth of the scattering mechanism. *Subject Headings: 1. Radio wave scattering 2. Troposphere.—Author's abstract.*

7.5-258

551.594.7:551.508.4

Hirao, Kunio and Maruyama, Hiroyuki, **Special instruments for observations and analyses of VHF fading.** *Japan. Radio Research Laboratories, Tokyo, Journal*, 2(8):207-216, April 1955. 12 figs., 2 refs., 5 eqs. DWB—The autocorrelation analysis has been carried out for the examination of fading of VHF wave. For the sake of this analysis, the recording system which is linear in voltage in its recorded fluctuation and the relay computer for  $\Sigma xy$  are both designed and constructed. A few examples of the results are introduced in the present paper. The necessary duration of observation and intervals of reading are also discussed in the present report in order to avoid misunderstanding about the statistical quantities of fading. *Subject Headings: 1. Radio fading 2. Radio fading instruments.—Authors' abstract.*

7.5-259

551.594.7:621.396

Kono, Tetsuo; Nishikori, Kiyoshi; Fukushima, Madoka; Ikeda, Masao and Yoshida, Noriaki, **Experimental studies on diffracted waves from a mountain at 3000 Mc/s.** *Japan. Radio Research Laboratories, Tokyo, Journal*, 2(8):163-180, April 1955. 21 figs., 4 tables, 8 refs. DWB—Radio transmission experiments were made at the frequency of 3000 Mc/s over the 243 km path between Kawaguchi and Ryozen in Sept. and over the 166 km path between Kawaguchi and Izumi in Dec. 1954. Mt. Yamizo lies in the midway of these paths. Transmission loss and fading characteristics obtained in this experiment are much different from that of a VHF radio wave experiment over a mountain. In the first experiment, the median value of the field intensity agreed approximately with that calculated by FRESNEL's knife-edge diffraction theory, but in the second experiment it was about 10 db below the calculated value. *Subject Headings: 1. Radio transmission ducts 2. Radio fading 3. Radio wave diffraction 4. Japan.—Authors' abstract.*

7.5-260

550.384:551.594.7:551.510.52

Tao, Kazuhiko, **On the relationship between the hourly variation of field strength and the structure of the lower atmosphere.** *Japan. Radio Research Laboratories, Tokyo, Journal*, 18(8):181-191, April 1955. 13 figs., table, 10 refs. **DWB**—It is clear that the relationship between the hourly variation of field strength and the distribution of the refractive index in the lower atmosphere is ascertained by the actual data from captive balloon observations, i.e., the high level of field strength corresponds to the abnormal distribution of the refractive index. Moreover, it is clear that the abnormal distribution of the refractive index can be explained from the view-point of synoptic meteorology. *Subject Headings: 1. Geomagnetic variations 2. Tropospheric refraction.*—*Author's abstract.*

### ACOUSTICAL PHENOMENA

7.5-261

551.596.1:551.557(789)

Kennedy, William B.; Brogan, Lee and Sible, Norman J., **Further acoustical studies of atmospheric winds and temperatures at elevations of 30 to 60 kilometers.** *Journal of Meteorology*, 12(6):519-532, Dec. 1955. 10 figs., 4 tables, 9 refs., 16 eqs. **DWB**—Results of firing 200 lb charges of TNT and recording elevation and azimuth of sound wave by an array of microphones are described. Operations in Colorado, Oct. 31, 1951–Aug. 28, 1952, confirmed the broad conclusions of the earlier Colorado series. Those in New Mexico bihourly Oct. 20–24, 1952 (T-Day) are fully treated. The winds and temperatures between 25 and 55 km are tabulated and plotted. The average wind was 23–39 m/s from 242–276°, but there were marked fluctuations over very short periods. Temperature increased as wind decreased with advancing time of day. *Subject Headings: 1. Acoustical upper wind measurement 2. New Mexico.*—*C.E.P.B.*

# PART II. ANNOTATED BIBLIOGRAPHY ON NATURAL AND ARTIFICIAL RADIOACTIVITY IN THE ATMOSPHERE

By: Geza Thuronyi

## INTRODUCTION

The primary subject of this bibliography is the artificial radioactivity in the atmosphere originating from atomic or thermonuclear explosions. In addition to this principal subject, several peripheral fields such as the nonradioactive effects of nuclear weapons, natural radioactivity in the atmosphere and the use of radioactivity in other disciplines (tracer techniques, radioactive dating methods, instruments using radioactive elements) have been included.

Several other pertinent subjects such as atmospheric pollution in general, atmospheric diffusion studies and basic climatological studies for atomic energy installations or tests, have not been covered in this bibliography. The reader interested in such subjects should consult other issues of *Meteorological Abstracts and Bibliography*, like Vol. 1, No. 1, Jan. 1950, for a bibliography on **atmospheric pollution** by smoke and gases (240 references), Vol. 1, No. 6, June 1950, for a bibliography on **volcanic dust** (66 references), Vol. 4, Nos. 1 and 2, Jan. and Feb. 1953, for bibliographies on **turbulence**, **turbulent diffusion and exchange** (547 references), and individual items like 3.5-111, 4.3-25, 4.4-152, 4.4-274, 5.4-80, 6.1-346 and 6.11-6 for **radioactivity in rocks**, 2.2-160, 2.2-161 and 5.5-23 for **atmospheric ionization** due to radioactivity, 3.3-207 and 3.8-55 for radioactive snow gages.

An annotated bibliography has been prepared on **The transport and deposition of atomic debris** by R. J. LIST of the U. S. Weather Bureau (see 7E-190) and published recently (Jan. 20, 1956) by the U. S. Atomic Energy Commission. We have made extensive use of that bibliography.

The problem of possible cumulative effects of atomic debris has been discussed by scientists in several countries (especially the U. S., Japan, France, Germany, Britain) who have come to conclusions varying in detail if not in principle. Several popular works touch on this aspect.

The bulk of the material has naturally been taken from the literature of the last decade. Only a very few representative papers have been chosen from the earlier literature.

Many of the most informative sources in the field covered are still restricted in most countries. This bibliography, therefore, cannot be considered to be exhaustive, but rather only a guide to the available literature on a subject of great concern to the public as well as to scientists.

The following subject outline gives an idea of the more detailed scope of the subject matter and a geographical outline shows the extent of the areas concerned.

## OUTLINE OF CONTENTS

### SUBJECT OUTLINE

#### COMPREHENSIVE WORKS

- Effects of atomic weapons, 7E-25, -178
- Congressional hearings on civil defense, 7E-208
- Atomic weapons reference data, 7E-118
- Meteorology and atomic energy, 7E-183
- Radioactive fallout analysis in Japan, 7E-98
- Computation of fallout plots, 7E-117
- Bibliography on atomic debris, 7E-190
- Impact of nuclear weapons on humanity, 7E-103, -153
- Natural radioactivity in atmosphere (Compendium article), 7E-35

- Instruments for measuring radioactivity in air and under snow, 7E-6
- Instrument manual, Brookhaven Nat. Lab., 7E-57
- Climatology of stack diffusion, 7E-49
- RADIOACTIVE SUBSTANCES IN THE ATMOSPHERE
  - Natural, 7E-21, -41, -42, -71, -90, -149, -173, -174
  - Precipitation, 7E-24, -56, -78, -86
  - Radioactive emanations, 7E-2, -188
  - Distribution, 7E-3, -9, -50, -55
  - Adsorption on nuclei, 7E-5, -7, -73
  - Radon, 7E-6, -83, -107, -176

Radium decay products, 7E-4

Tritium, 7E-109

Beryllium-7, 7E-126

Radiocarbon, 7E-75

#### Artificial

Radioactivity from nuclear explosions,  
7E-16, -17, -149, -151, -173, -174,  
-187, -214

$\beta$ -activity, 7E-32, -38, -39, -56, -59, -65,  
-84, -121, -129, -132, -200

$\gamma$ -activity, 7E-11, -85

Radioactive complex "A," 7E-29, -30

Radioactive gases, 7E-10

Radioactive particles, 7E-28, -31, -36,  
-64, -65

Radioactive dust, 7E-54, -56, -88

Radioactivity in precipitation, 6E-62,  
-77, -82, -85, -129

In hailstones, 7E-93

In hoarfrost, 7E-138

Radioactive fallout

Size and composition, 7E-95, -96, -98,  
-102, -115

Radiochemical properties, 7E-60, -92,  
-98, -145, -146, -156

Distribution, 7E-117, -154, -157, -178,  
-180, -182, -193, -204, -205, -210

Radioactive debris trajectories, 7E-69,  
-88, -99, -155, -159, -164

Nuclear reactor effluents, 7E-14, -15, -22,  
-142

Radioargon concentration, 7E-112

#### EFFECTS OF NUCLEAR EXPLOSIONS

**General**, 7E-25, -81, -118, -160, -181, -208,  
-213

**Cumulative effects**, 7E-100, -110, -114, -122,  
-131, -153, -172, -177, -179, -185, -207

**Effects on weather**, 7E-33, -46, -72, -76,  
-105, -113, -128, -135, -147, -152, -201

On condensation nuclei, 7E-30, -32

On condensation, 7E-130

On cloud formation, 7E-194

On pH content of rain, 7E-189

On atmospheric circulation, 7E-116, -119

On jet stream, 7E-125

On tornadoes, 7E-72, -91

On atmospheric conductivity, 7E-140

**Biological effects of radiation**, 7E-8, -98, -124,  
-137, -150, -175, -179, -196, -197, -199

Genetic, 7E-158

Wildlife, 7E-139

**Radioactive contamination of:**

Atmosphere, 7E-63, -67, -133, -134, -171

Sea water, 7E-154, -157

Surface water, 7E-79, -191

Reservoirs, 7E-97

Water supply, 7E-104

Fishing boats, 7E-92, -95, -96, -98, -106,  
-111, -115, -145

Consumers goods, 7E-106, -175

Film packs, 7E-18, -202

**Thermal effects**, 7E-26

**Pressure waves**, 7E-98, -120, -169

**Base surge**, 7E-33, -34

#### RADIOACTIVITY AS RELATED TO METEOROLOGICAL FACTORS

**Meteorological effects on atmospheric radioactivity**, 7E-52, -155, -165, -198, -209

Air mass effects, 7E-60

Jet stream effects, 7E-192

Removal of radioactivity by precipitation,  
7E-31, -41, -44, -192

**Cosmic ray effects on atmospheric radioactivity**, 7E-75, -109, -126

**Effect of natural radioactivity on atmospheric ionization**, 7E-4, -19, -20, -70, -71

#### MEASUREMENT AND CALCULATION OF ATMOSPHERIC RADIOACTIVITY

**Instruments for measuring radioactivity**,  
7E-6, -57, -99

Dose rate meters, 7E-148

Counters, 7E-161

Geiger-Müller counters, 7E-38, -54,  
-77, -144

Scintillation counters, 7E-62

Ionization chambers, 7E-12, -78, -83

Nuclear emulsions, 7E-74

Photographic emulsions, 7E-23

Radiosonde, 7E-144

#### Sampling devices

Sampling from airplane, 7E-16, -17, -89

Air filters, 7E-53, -66, -83, -121, -211

Precipitation filters, 7E-24

Gummed surfaces, 7E-53, -136, -210

Electrostatic precipitators, 7E-58

#### Fallout monitoring networks

United States, 7E-53, -61, -81, -99, -136,  
-151, -210

Western Europe, 7E-56

Japan, 7E-102, -203

**Fallout analysis (radiochemical)**, 7E-60, -92,  
-98, -145, -146, -156

#### Theoretical studies and computations

Calculation of radioactive fallout area,  
7E-178, -180, -182, -212

Radioactive diffusion studies, 7E-14, -15,  
-22, -48, -49, -87, -112

Calculation of radioactive emanation distribution, 7E-3

#### APPLICATIONS

##### Radioactive tracing

Air currents, 7E-46, -68, -69, -86, -142,  
-167, -168

Ocean currents, 7E-157, -206

Ground water, 7E-143

**Dating of nuclear explosions**, 7E-47, -110,  
-132, -186

**Dating of rainwater**, 7E-109

**Determination of turbulent exchange coefficient**, 7E-37

**Forecasting for nuclear tests**, 7E-81, -170,  
-195

**Civil defense**, 7E-166, -180, -181, -204, -205,  
-208

**Radiation safety measures**, 7E-53, -141, -162,  
-166

**Radioactive snow gages**, 7E-43, -108

**Soil moisture and density meters**, 7E-40

## GEOGRAPHIC OUTLINE

## NORTH AMERICA

## Canada

Kingston, 7E-163

Ottawa, 7E-54

## United States, 7E-99, -136, -210

## Arkansas

Fayetteville, 7E-60

Idaho, 7E-48, -49

## Indiana

Vincennes, 7E-18

Massachusetts, 7E-79

## Michigan

Ann Arbor, 7E-36

## Nevada

Ely, 7E-151

Yucca Flat, 7E-139, -170

## New Mexico

Socorro, 7E-58

## New York, 7E-97

Brookhaven, 7E-14, -15, -22, -112

Hannibal, 7E-82

New York, 7E-20, -21, -62

Schenectady, 7E-28

Troy, 7E-85

## Ohio

Cincinnati, 7E-104, -191

## Oklahoma

Tulsa, 7E-10

## Texas

Houston, 7E-11

Washington, D. C., 7E-93, -187, -214

## EUROPE

## Austria

Salzburg Province, 7E-107

## Great Britain, 7E-133

England, 7E-42, -134

France, 7E-16, -17, -29 to -31, -64, -65, -66

Paris, 7E-38, -39, -59, -121

Pic du Midi, 7E-6

Puy-de-Dôme, 7E-32, -42, -63, -89, -100

-138, -188

Val Joyeux, 7E-174

## Germany, 7E-169

Freiburg, 7E-69

Königsstuhl, 7E-67, -110

Zugspitze, 7E-165

## Italy, 7E-77

## Netherlands, 7E-184

## Sweden

Stockholm, 7E-23

## ASIA

## India

Calcutta, 7E-84, -129, -132

Japan, 7E-102, -125, -146, -155, -160, -170

-192, -201, -203

Arima, 7E-94

Shionomisaki, 7E-120

Tokyo, 7E-186

## AUSTRALASIA

## Australia

Woomera, 7E-88

## New Zealand

Wellington, 7E-88, -200

## PACIFIC OCEAN, 7E-92, -95, -96, -98, -100

-111, -115, -145, -154, -156, -157, -206

Bikini, 7E-34

1901

7E-1

Rutherford, E., *Emanations from radio-active substances.* *Nature*, London, 64(1650):157-158, June 13, 1901. **DLC**—Reports experiments which lead to the conclusion that emanation from radium is a radioactive gas or vapor with a molecular weight between 40 and 100. *Subject Heading: 1. Radioactive emanations.*—G.T.

7E-2

Elster, J. and Geitel, H., *Über eine fernere Analogie in dem elektrischen Verhalten der natürlichen und der durch Becquerelstrahlung abnorm leitend gemachten Luft.* [A further analogy between natural air and air rendered abnormally conductive by means of Becquerel rays.] *Physikalische Zeitschrift*, 2(40):590-593, July 6, 1901. refs. **DLC**—RUTHERFORD experimentally demonstrated the existence of gaseous radioactive emanations from radioactive substances. Analogies between properties of natural air and air brought into contact with radioactive objects appear to indicate that radioactive emanations are present in the atmosphere. *Subject Heading: 1. Radioactivity in the atmosphere.*—G.T.

1926

7E-3

Schmidt, Wilhelm, *Zur Verteilung radioaktiver Stoffe in der freien Luft.* [Distribution of radioactive substances in the free atmosphere.] *Physikalische Zeitschrift*, 27(11):371-378, June 1, 1926. fig., 4 tables, refs., 10 eqs. **DLC**—Height distribution of radioactive substances in the atmosphere is calculated on the basis of new concepts of random motion in free air. Values of the different radioactive substances are tabulated for various heights as fractions of their ground-level concentration. *Subject Headings: 1. Radioactive emanation distribution 2. Diffusion equations.*—G.T.

1934

7E-4

551.594.14

Wait, G. R. and McNish, A. G., **Atmospheric ionization near the ground during thunderstorms.** *Monthly Weather Review*, 62(1):1-4, Jan. 1934. 5 figs., refs. **DLC**—Data on ionization values measured during a number of thunderstorms are presented. Ionization is found to increase in proportion with rainfall intensity. This is attributed to the presence of radium decay products (especially RaB and RaC) in rainwater. Radium emanation from the soil is carried up into the air and presumably dissolved into existing cloud droplets where it disintegrates, producing RaA, RaB and RaC. *Subject Headings: 1. Radioactivity in the atmosphere 2. Ionization.*—G.T.

1935

7E-5

551.574.1:551.594.14

Aliverti, Giuseppina and Rosa, G., **Zur Frage der Adsorption van RaEm an Kernen.** [On the adsorption of radium emanation on nuclei.] *Beiträge zur Geophysik*, 44(2):107-111, 1935. figs., tables. Italian and German summaries p. 107. **DLC**—ALIVERTI's method of measurement of atmospheric radioactivity is discussed. Considering the presence of active thorium-precipitation in the atmosphere and the results of experiments, it is concluded that the adsorption of radium emanation on nuclei is very improbable. (Same item as 6H-97, Aug. 1955, MAB.) *Subject Headings: 1. Nuclei theories 2. Radioactivity in the atmosphere 3. Nuclei and radioactivity.*—N. A. Likeev

1936

7E-6

551.594.14

Garrigue, Hubert, **Radioactivité de l'air en montagne.** [Radioactivity of the air on mountains.] Thesis (Ph.D. in Physical Sciences)—Univ. of Paris, May 1936. 83 p. 36 figs., 6 photos, 13 tables, 26 refs. **DLC**—Various instruments and methods for measuring radioactivity in the air and under snow are described in detail, including portable equipment designed by the author. From measurements made at Pic du Midi Observatory it is deduced that snow shields off part of the radon normally emanating from fissures in the soil. Radon accumulated under the snow decays in calm weather; it is liberated on slopes exposed to wind. *Subject Headings: 1. Radioactivity in the atmosphere 2. Pic du Midi, France.*—G.T.

1941

7E-7

551.594.14:551.574.1

Freed, Simon and Schultz, Melvin L., **Deposition of atmospheric radioactivity on objects exposed to air streams.** *Franklin Institute, Philadelphia, Journal*, 231(4):345-355, April 1941. 2 figs., tables. **DLC**—When air was blown against various objects, radioactive material was deposited which was identified as the decay products of radon and thoron. The deposition took place on glass, mica, and on the metals copper, brass, steel, aluminum, but not lead. It was immaterial whether the metals were grounded or insulated. No appreciable electrical potential was produced on the objects by the streaming gas. It is inferred that smoke, dust, etc. blown about in the atmosphere gathers radioactive and hence ionizing substances. A computation is included on the proportion of radioactive nuclei in the atmosphere which might be expected to be uncharged under equilibrium conditions. *Subject Headings: 1. Radioactivity in the atmosphere 2. Nuclei and radioactivity.*—From authors' abstract.

7E-8

551.594.14:575.7

Krebs, Adolf, **Radioaktive Beimengungen der Luft als bioklimatische Faktoren.** [Radioactive atmospheric admixtures as bioclimatic factors.] *Meteorologische Zeitschrift, Bioklimatische Beiblätter*, 8(3/4):81-82, 1941. refs. **DWB**—Average radioactive emanation content of free air is  $10^{-16}$  c/cm<sup>3</sup>; in narrow valleys values up to  $10^{-14}$  c/cm<sup>3</sup> may be reached; in closed rooms and cellars  $10^{-11}$  c/cm<sup>3</sup> and more has been measured. Values of this order may be considered significant from a biological point of view. According to new regulations in Germany, 15 Mäße units ( $5.46 \times 10^{-9}$  c/l) are maximum permissible emanation content in mines. *Subject Headings: 1. Biological effects of radioactivity 2. Radioactivity in the atmosphere.*—G.T.

7E-9

551.594.14:532.72:551.511

Lettau, H., **Anwendung neuerer Ergebnisse der Austauschlehre auf zwei luftelektrische Fragen.** [Application of recent results of Austausch research to two problems in atmospheric electricity.] *Gerlands Beiträge zur Geophysik*, 57(3/4, Benndorf-Heft):365-383, 1941. 3 figs., 4 tables, 10 refs., eqs. **DLC**—The distribution of radioactive substances in the atmosphere is determined theoretically by assuming linear height dependence of Austausch. According to the calculations, total radium

emanation content in a vertical column of air is about  $27 \times 10^{-12}$  c/cm<sup>2</sup>. This indicates a sup- of  $57 \times 10^{-18}$  c/cm<sup>2</sup> sec, which is in agreement with observed values. Earlier theories are also viewed. *Subject Headings: 1. Radioactive emanation distribution 2. Diffusion equations.—G.T.*

## 1946

7E-10

551.594.1

Fearson, R. E.; Engle, A. Wendell; Thayer, Jean et al., *Results of atmosphere analyses done at Tulsa, Oklahoma, during the period neighboring the time of the second Bikini atomic bomb test*. *Physical Review*, 70(7/8):564, Oct. 1/15, 1946. fig. DLC—Radioactive concentrates were prepared from the atmosphere on July 26, July 28, and August 30, 1946. Data on July 26 and Aug. 30 were explained as natural radioactivity. Data on July 28 assumed to be from new rare radioactive gas of atomic number 86, having an effective half-life of 82 min. *Subject Headings: 1. Radioactivity in the atmosphere 2. Radioactive fallout 3. Tulsa, Okla. I. Swift, Gilbert II. Johnson, Irving—R. J. List.*

7E-11

551.594.2

Herzog, G., *Gamma-ray anomaly following the atomic bomb test of July 1, 1946*. *Physical Review*, 7(3/4):227-228, Aug. 1/15, 1946. DLC—A sensitive gamma-ray meter in Houston, Texas, indicated an increase, reaching a maximum of 77% over background, from 8 p.m. July 4, to 7 p.m. July 5, 1946. The maximum occurred 108 hrs after the explosion, corresponding to a speed of over 60 mi/hr from Bikini. *Subject Headings: 1. Gamma ray anomalies 2. Bikini atom bomb test 3. Houston, Texas.—R. J. List.*

## 1948

7E-12

551.594.14:551.508.1

Aliverti, G., *Su la camera di ionizzazione e il suo uso in misure quantitative di radioattività atmosferica*. [The ionization chamber and its use in quantitative measurement of atmospheric radioactivity.] *Annali di Geofisica*, Rome, 1(3):478-487, July 1948. 3 figs., tables. DWB—A technique for indirect measurement of atmospheric radon content is described in detail and a complete record is given of such a measurement made with the author's method. *Subject Headings: 1. Radioactivity measurement techniques 2. Ionization chambers.—Transl. of author's abstract.*

7E-13

551.510.42:551.594.1

Carmichael, H. and Tunnicliffe, P. R., *Measurement of alpha-active dust in the atmosphere*. *Journal of Industrial Hygiene and Toxicology*, 30:211-227, July 1948. 17 figs., 6 refs. DSG—Discussion of radioactivity of atmospheric dust and effect when absorbed into body; decay curves; apparatus; filter, precipitator, airflow measurements, methane proportional counter; effect of voltage on collection, etc.; determination of various radioactive elements. (Same item as A-206, Jan. 1951 MAB.) *Subject Headings: 1. Atmospheric pollution 2. Radioactivity in the atmosphere 3. Public health.*

7E-14

551.510.42:628.53:551.594.1

U. S. Brookhaven National Laboratory, *Scientific progress report, Jan./July 1948*. Edited and issued by the Information and Publications Div., Brookhaven National Laboratory, Associated Universities, Inc. [1948?] 48 p. 13 figs. (incl. photos.) DWB—Among the various activities of Departments reported (Physics, Chemistry, Biology, Medicine, Engineering, Reactor Dept.), the work in meteorology is reported on p. 25-26. Staff includes 4 professional meteorologists and weather technicians, 3 computers and 2 secretaries. The main work is in study of relation between weather and behavior of stack effluents for radiation protection purposes. Instruments which have been procured and installed are described. Routine and special operations, forecasts and plans for future investigations are mentioned. *Subject Headings: 1. Radioactive effluents 2. Atmospheric pollution studies 3. Stack meteorology 4. Brookhaven, N. Y.—M.R.*

## 1949

7E-15

551.510.42:628.53:551.594.1

Beers, Norman R., *Stack meteorology and atmospheric disposal of radioactive waste*. *Nuclear Electronics*, New York, 4(4):28-38, April 1949. fig. 7 photos, 7 refs., eq. DLC—Survey of problem of atomic pollution disposal and investigations carried out at Brookhaven, N. Y., with 420 ft tower micrometeorological installations and artificial smoke ejector. Many photographs show equipment in operation under varying diurnal turbulence conditions. (Same item as 4.11-47, Nov. 1951 MAB.) *Subject Headings: 1. Atmospheric pollution 2. Radioactive effluents 3. Stack meteorology 4. Brookhaven, N. Y.—M.R.*

7E-16

551.594.14

Garrigue, Hubert, **La recherche du nuage radioactif**. [Investigation of the radioactive cloud.] *France. Ministère de l'Air, Publications Scientifiques et Techniques*, No. 228, Paris, 1949. 23 p. 2 figs., plates. Preface by Jean Cabannes. **DLC**—In three out of 23 flights at 6000 m over France in July 1946, an unknown radioactive material with half-life of  $25 \pm 5$  hours was detected. Average concentration  $0.013 \times 10^{-16}$  c/cm<sup>3</sup> radon equivalent. The first detection was on July 20, 1946 20 days after the first explosion at Bikini. Similar material was detected in 6 out of 15 flights in July 1949, the first on July 2, 27 days after the Eniwetok test. Average concentration  $0.0001 \times 10^{-16}$  c/cm<sup>3</sup>. *Subject Headings*: 1. Radioactive fallout data 2. Airplane sampling of radioactivity 3. France. I. Cabannes, Jean.—*R. J. List*.

7E-17

551.594.14

Garrigue, Hubert, **Sur la radioactivité de l'atmosphère**. [On the radioactivity of the atmosphere.] *Académie des Sciences, Paris, Comptes Rendus*, 228 (20):1583-1584, May 16, 1949. **DLC**—A radioactive substance with a half-life of 25 hrs was detected in aircraft flights at about 6000 m in the summer of 1946 and again, in much weaker concentration, in the summer of 1948. Highest value reported, Aug. 1, 1946, at 6000 m,  $2.0 \times 10^{-18}$  c/cm<sup>3</sup>. Observations at Puy-de-Dôme, 1500 m, gave no definite positive results. Speculation that material is from Bikini tests or possibly of meteoric or cosmic ray origin. *Subject Headings*: 1. Radioactivity in the atmosphere 2. Airplane sampling of radioactivity 3. France.—*R. J. List*.

7E-18

551.594.14

Webb, J. H., **The fogging of photographic film by radioactive contaminants in cardboard packaging materials**. *Physical Review*, 76(3):375-380, Aug. 1, 1949. 3 figs., 6 tables. **DLC**—Film packed in strawboard produced in Vincennes, Ind. on August 6, 1945, exhibited many small exposed areas after a three-week contact. About 600 small circles of the board coinciding with the spots were punched out and counted. Beta-activity appreciably above background was observed,  $\alpha$ -activity was negligible. The half-life of the  $\beta$ -activity during Oct. and Nov., 1945, averaged about 30 days. A similar phenomenon occurred in strawboard manufactured in Tama, Iowa, during Sept., 1945. It was concluded that the activity came from fission products in the water supply, and was a result of the atom-bomb detonation in New Mexico on July 16, 1945. *Subject Headings*: 1. Radioactivity in packaging materials 2. Atomic explosion effects 3. Vincennes, Indiana.—*R. J. List*.

1950

7E-19

551.594.12:551.521.64

Aliverti, Giuseppina, **Radioattività atmosferica**. [Atmospheric radioactivity.] *Rivista di Meteorologia Aeronautica*, 10(2):3-9, April-June 1950. 1 fig., 1 table. Italian, French, English and German summaries p. 3. **MH-BH**—Three causes of ionization of air are considered: cosmic radiation, radioactivity from the soil and radioactivity in the air. The relative importance of the three is discussed and quantitative estimates, together with measurements made for the ionization based on soil emanations and other factors, are given. Results obtained by several investigators tabulated. Effect of weather conditions, turbulence, altitude, etc. also discussed. (*Same item as* 2.6-148, June 1951, *MAB*.) *Subject Headings*: 1. Ionization 2. Radioactivity in the atmosphere.—*M.R.*

7E-20

551.594.1

Hess, Victor F. and Vancour, Roger P., **The ionization balance of the atmosphere**. *Journal of Atmospheric and Terrestrial Physics*, 1(1):13-25, 1950. 4 figs., 5 tables, 12 refs., 6 eqs. **MH-BH**—Authors examined, by new methods at Fordham, ionization I (pairs of ions produced in 1 cc. air per sec.) due to hard (filtered through 10 cm iron) and soft cosmic radiation and to radioactive material in air and ground. At 1 m results gave:

|             |        |        |
|-------------|--------|--------|
| Cosmic rays | hard   | 1.51 I |
|             | soft   | 0.27 I |
| Alpha rays  |        | 1.76 I |
| Beta rays   |        | 0.40 I |
| Gamma rays  | air    | 0.15 I |
|             | ground | 3.0 I  |

From the total, 7.2 I, law of recombination and average life of small ions (observed, same site, 10.6 sec.) the number of small ions in equilibrium is 70 80 per cc. Site is near a large city, average nuclei 40,000 per cc. (*Same item as* 3.1-181, Jan. 1952, *MAB*.) *Subject Headings*: 1. Ionization 2. Radioactivity in the atmosphere 3. New York, N. Y.—*C.E.P.B.*

7E-21

551.594.14

Hess, V. F., **New studies on the radioactivity of the atmosphere.** *Archiv für Meteorologie Geophysik und Bioklimatologie, Ser. A*, 3(1/2):56-63, 1950. 3 tables, 6 refs., 6 eqs. English, German and French summaries p. 56-57. **DWB**—The effect of the gamma rays from radioactive substances in the atmosphere near New York was measured in an ionization chamber; it averaged 0.15 I (ion pairs/cm<sup>3</sup>/sec) with considerable day-to-day variations. Alpha rays from radon and its decay products gave 0.93 I and from thoron and its decay products 0.83 I. The radon content averaged  $46 \times 10^{-18}$  c/cm<sup>3</sup>. (Same item as 2.2-163, Feb. 1951, MAB.) **Subject Headings:** 1. Radioactivity in the atmosphere 2. New York.—C.E.P.B.

7E-22

551.510.42:628.53:551.594.14

Lowry, Philip H., **The theoretical ground-level dose-rate from the radioargon emitted by the Brookhaven Reactor stack.** Upton, N. Y., Brookhaven National Laboratory, July 1950. 33 p. 24 figs., 9 tables, 15 refs., 28 eqs. **DWB**—By means of theoretical and empirical data on weather (wind, turbulence, etc.) and oil fog concentration measurements, tables and templates were compiled and are presented for calculating the mean hourly ground-level concentration of A<sup>41</sup> during various meteorological conditions for distances up to 15 km from the stack. The factors considered are rate of emission, exit velocity from stack, height and diameter of stack, mean wind speed and direction, type of gustiness and mean hourly direction distribution. The instantaneous maximum concentration as a function of distance is also mentioned. Results applicable to any similar installation in flat terrain regardless of height of stack. (Same item as 3.7-83, July 1952, MAB.) **Subject Headings:** 1. Turbulent diffusion 2. Atmospheric pollution 3. Radioargon concentration 4. Radioactive effluents 5. Brookhaven, New York.—M.R.

7E-23

551.594.14:551.508.99

Siksna, Reinhardt, **Photographic emulsion method applied to the investigation of radioactive deposits from atmospheric air.** *Tellus*, 2(2):89-92, May 1950. 5 figs., 7 refs. Also his: **Radioactivity induced from the atmospheric air, investigated with the photographic emulsion method.** *Arkiv för Geofysik*, Stockholm, 1(2/4):123-147, 1951. 18 figs., 8 tables, refs. English summary p. 146-147. **MH-BH**—The method which is described in detail proves very sensitive to weak radioactive deposits on objects suspended in air which is contaminated. Experimental data are discussed and illustrated. (For fuller abstracts, see 11-49 and 4.6-241, Nov. 1950 and June 1953, MAB.) **Subject Headings:** 1. Radioactivity measurement techniques 2. Stockholm, Sweden.—M.R., W.N.

7E-24

551.577.1:551.594.14

Stefanizzi, A., **On the radioactivity of atmospheric precipitates.** *Journal of Geophysical Research*, 55(4):373-378, Dec. 1950. 2 figs., 2 tables, 9 refs., eq. **MH-BH**—The method of filtration was used for separating the radioactive products of precipitates. Thirty-three cases of atmospheric precipitation were analyzed for radioactivity. The curve of the logarithm of saturation intensity of the precipitate plotted against time indicates that only the decay products of radon were present in the precipitates. The author concludes that some radioactivity was acquired by precipitates during their fall from the clouds to ground level; that snow is more active than rain; and that rain in thundershowers is more active than ordinary rain. Also presence of thoron decay products in precipitates was detected. (Same item as 2.8-111, Aug. 1951, MAB.) **Subject Heading:** 1. Radioactivity in the atmosphere.—I.L.D.

7E-25

662.2:539.1(02)

U. S. Scientific Laboratory, Los Alamos, New Mexico, **Effects of atomic weapons.** Prepared for and in cooperation with the U. S. Dept. of Defense and the U. S. Atomic Energy Commission. Wash., D. C., U. S. Govt. Printing Office, June 1950. 456 p. figs., tables, refs., eqs. Price: \$1.50. Another edition, identical with Official edition, published Wash., D. C., by Combat Forces Press, Aug. 1950. **DLC**—This is the most authoritative and comprehensive book on atomic bombs now available to the general public. It deals with: explosions, shocks from air and underwater bursts, physical damage from air, ground and underwater shock, thermal radiation from the fire ball, incendiary effects, nuclear radiation, contamination and its measurement, decontamination, effects on human beings, protection of personnel, etc. In Appendix 7 is given the latest method for computing meteorological trajectories from the radioactive cloud. Fallout is treated thoroughly and quantitatively in respect to air currents, rain, etc. in Ch. 8 (p. 267-276), and underwater or underground explosions, including base surge, dust contamination, etc., on p. 277-287. **Subject Headings:** 1. Atomic explosion effects 2. Radioactivity in the atmosphere 3. Textbooks. I. U. S. Dept. of Defense II. U. S. Atomic Energy Commission III. Hirschfelder, J. O. (ed.) IV. Effects of atomic weapons.—M.R.

1951

7E-26

551.521.9:536.33:551.586:612

Buettner, Konrad J. K., KKK robe, light skin help foil A-bomb heat. *Science News Letter*, 15(2):231, Oct. 13, 1951. photo. DWB—Brief report on experiments made by the author for U. S. Air Force School of Aviation Medicine in San Antonio, Texas. The experiments carried on heat created with a sun reflector are said to have shown that only 10% of the heat rays to which a person might be exposed by A-bomb are reflected by black skin and 40% by white skin. Hooded suit and aluminum foil are suggested as best available shield against intense heat. (Same as 4.4-141, April 1953, M.A.B.) *Subject Headings*: 1. Aviation medicine 2. Atomic heat effects. U. S. School of Aviation Medicine.—G.T.

7E-27

551.524:620.92:539.1

Chernick, J., Dependence of reactor kinetics on temperature. *U. S. Brookhaven National Laboratory, BNL 173 (T-30)*, Dec. 20, 1951. 38 p. table, 5 figs., 8 refs., 58 eqs. DWB—Non-linear temperature effects, which are important in thermal stability of reactors and experiments with reactors, are treated mathematically. It has been found that when the temperature is too low and is brought up to standard by the nuclear reactions, it tends to rise too fast and "overshoot," leading to oscillations which are gradually damped. Attempts at solving this sort of a reaction are set forth in detail and examples given. *Subject Heading*: 1. Temperature effects on nuclear reactors.—M.R.

7E-28

551.594.14:551.506.9

\*Cherubin, L. J. et al., Evaluation of the effects of atomic bomb detonations in the state of Nevada on air-borne contamination at Knolls Atomic Power Laboratory, Knolls site and environs. *U. S. Atomic Energy Commission, Report*, No. KAPL-559, May 7, 1951. 15 p. 3 tables. DLC—Contamination of the atmosphere with radioactive elements above the normally expected levels occurred at KAPL—Knolls, Sacandaga, and West Milton sites—soon after the first atomic bomb was exploded at the Nevada testing station on Jan. 27, 1951. Significant increases in air-borne radioactivity were established by radioactive particle determinations. Air and precipitation samples disclosed significant fission product content for the first time. Nuclear film studies of alpha tracks from snow and rain sample residues and from an air filter revealed the presence of U-235 and plutonium. Radioactive decay studies of precipitation residues indicate an apparent half-life of 2.6 to 4 days (~90%) and longer (approx. 19 days and 100 days, 10%). Beta activity with predominant energy of 0.3 mev is indicated. Abnormal findings at the Knolls and West Milton sites were indicated as late as March 16, 1951. Findings after Feb. 18, 1951 may be attributed to resumption of dissolving and subsequent separations operations in the Separation Plant at KAPL. No significant health hazard to this locality is attributed to the air-borne contamination produced by the Nevada tests. *Subject Headings*: 1. Radioactive fallout data 2. Schenectady, N. Y.—Authors' abstract.

7E-29

551.594.14

Garrigue, Hubert, Recrudescences d'anomalies dans la radioactivité de l'air à moyenne altitude. [Renewal of anomalies in atmospheric radioactivity at middle altitude.] *Académie des Sciences, Paris, Comptes Rendus*, 232(9):827-829, Feb. 26, 1951. ref. DLC—Samples taken in flight at 3000-3500 m on Jan. 13 and 14, 1951 show A activity of  $0.03 \times 10^{-18}$  c radon equivalent, which is three times the maximum found since Jan. 1950. *Subject Heading*: 1. Radioactivity in the atmosphere.—G.T.

7E-30

551.594.14:551.574.1

Garrigue, Hubert, L'invasion d'air radioactif d'origine atomique et son influence sur les précipitations atmosphériques. [The invasion of radioactive air of atomic origin and its effect on precipitation.] *Académie des Sciences, Paris, Comptes Rendus*, 232(10):1003-1004, March 5, 1951. DLC—On Jan. 13, 1951 and Feb. 3, 1951 a radioactive complex "A," observed first after the Bikini atomic explosion, was detected anew in France. The radioactive cloud observed may be of direct atomic origin or from products of the explosion. After the explosion a large part of the radioactive cloud extends into the stratosphere, a part forms condensation nuclei. It is concluded that although the principal area of contamination from an atomic explosion is rather restricted, radioactive condensation nuclei will cover a large portion of the globe. (Same item as 3.1-182, Jan. 1952, M.A.B.) *Subject Headings*: 1. Radioactivity in the atmosphere 2. Radioactive condensation nuclei 3. Atomic explosions 4. Bikini atom bomb tests 5. France.—I.L.D.; G. C. Bristow.

7E-31

551.594.14:551.574.1:551.509.67

Garrigue, Hubert, Recherches sur la radioactivité de l'air libre. [Research on the radioactivity of free air.] *Académie des Sciences, Paris, Comptes Rendus*, 233(16):860-862, Oct. 15, 1951. refs.

**DWB**—Data obtained through measurements from the ground and in flight for the period May through May 1951 are presented and claimed to confirm the existence of a complex radioactive particle with a half-life of several hours, which had been anticipated as early as 1946. For the time this particle could be observed from the ground. Other data chosen from the period May through 1951 are arranged with a view to proving that the abundant precipitation lately noticed over France (and definitely claimed by the author to be the result of condensation nuclei emitted from atomic explosions) washed out radioactive particles from the lower atmosphere. Artificial precipitation is suggested as a possible means of defense against air pollution from radioactive. (Same item as 4.6-240, June 1953, *MAB.*) *Subject Headings:* 1. Radioactivity in the atmosphere 2. Air sampling and analysis 3. Condensation nuclei 4. Artificial precipitation 5. France.—

7E-32

551.594.14:551.57

Garrigue, Hubert, **Recherches de radioactivité au sommet du Puy-de-Dôme.** [Researches on radioactivity at the top of Puy-de-Dôme.] *Académie des Sciences, Paris, Comptes Rendus*, 233 (1951): 1447-1448, Dec. 3, 1951. **DLC**—Snow collected at Puy-de-Dôme which fell on Nov. 19-20, 1951, showed  $\beta$ -activity about 43% above background with an apparent half-life of 10 days. Speculation on role of particles as condensation nuclei. *Subject Headings:* 1. Radioactivity in snow 2. Puy-de-Dôme, France.—*R. J. List.*

7E-33

551.5:539.1:61

Holzman, Benjamin G., **The effect of atomic bomb explosions on weather.** *Weather*, 4(1):3-4, 9, Feb. 1951. **fig. MH-BH**—The physical reasons as to why an atomic explosion can produce directly thunderstorms, rain or hurricanes are presented. It can affect weather indirectly by causing fires which may sustain convection for a long time or when exploded in shallow water by giving rise to base surge which may become a stratocumulus cloud from which rain falls. (Same item as 2.11-6, Nov. 1951, *MAB.*) *Subject Heading:* 1. Atomic explosion, effects on weather.—*I. D.*

7E-34

551.509.6:623.45:551.5

Holzman, Benjamin G., **Meteorological aspects of the atomic "Base Surge."** *American Meteorological Society, Bulletin*, 32(7):251-258, Sept. 1951. 8 **figs.** **DWB**—The effects of the underwater detonation of an atomic bomb at Bikini are described and the "base surge" wave (which resembles the outflow of cold air from an intense summer thunderstorm) beautifully illustrated by several photographs taken from different points and at different stages. In addition to the "cold front" effects, the cloud formations, precipitation and other condensation processes are revealed with remarkable vividness in this series of pictures. (Same item as 3.5-91, May 1952, *MAB.*) *Subject Headings:* 1. Bikini atom bomb tests 2. Base surge 3. Cloud formations 4. Bikini, Marshall Islands.—*M.R.*

7E-35

551.594

†Israel, Hans, **Radioactivity of the atmosphere.** (In: *Compendium of meteorology.* Boston: American Meteorological Society, 1951. p. 155-161. **fig.**, 6 tables, 63 refs.) **DLC**—Emanation ( $\alpha$ ,  $\beta$  and  $\gamma$ ) from radioactive substances in the earth or air provide the principle source of ions which increase the conductivity of the lower layers of the atmosphere. Fifteen of these radioactive elements, together with their half-life and disintegration constant, and the type of rays emitted, each are described in a table. Two classic methods of measuring radioactivity in the atmosphere are discussed: the direct or emanometry method, and the indirect or induction method. The latter is simpler but less reliable except when dealing with certain elements whose life is too short for emanometer techniques. Corrections for time, saturation deficit, pressure and temperature are discussed. Actual measurements of radon content of the atmosphere in various parts of the earth (1907-1942) according to different authorities, are tabulated. Relation to meteorological conditions (pressure, wind, air mass, precipitation, Austausch, etc.) vertical and geographical distribution is then treated. Finally, unsolved problems such as the development of automatic recording devices to substitute for isolated measurements, surveys by networks to determine simultaneous geographical (horizontal and cross section) distribution, development of an air mass classification based on radioactive elements in air, determination of radioactivity of precipitation and relation to thunderstorm activity and survey classification and analysis of records of radioactivity in atmosphere and precipitation. (Same item as 4.2 11, Feb. 1953, *MAB.*) *Subject Headings:* 1. Radioactivity in atmosphere 2. Ionization 3. Austausch 4. Emanometry 5. Compendium articles.—*M.R.*

7E-36

551.594.14:551.578.46:539

Meinke, W. Wayne (Dept. of Chemistry, Michigan Univ., Ann Arbor), **Observations on radioactive snows at Ann Arbor, Michigan.** *Science*, 113(2941):545-546, May 11, 1951. 4 refs. **DLC**—Careful chemical determinations of radioactive elements found in snow which fell before Jan. 1, 1951, and from Jan. 31-Feb. 1, 1954, respectively (tests were made as of Feb. 4) show that ratio of r

th atoms to Ba-Sr atoms found in the snow-pack correspond to what would be expected from fission such as occurred during Las Vegas, Nev., test explosions of Jan. 27-Feb. 6, 1954. and that most of the radioactivity was concentrated in top half (portion fallen Jan. 31 and Feb. 1) and the activity must have originated in explosions of Jan. 27 and or 28. Later snowfalls (Feb. 6 and 6) show little activity. The greatest amount detected does not approach levels dangerous to health; but does offer possibility of contamination of film packs or of low-background radioactivity experiments. *Same item as 6.5-344, May 1955, MAB.* *Subject Headings:* 1. Radioactivity in snow 2. Snow radioactivity analysis 3. Atomic explosions 4. Ann Arbor, Mich.—M.R.

7E-37

551.551:551.594.14

Millin, V. B., *K voprosu opredeleniia koefitsienta turbulentnogo obmena v prizemnom sloye atmosfery*. [Determination of the coefficient of turbulent exchange in the layer of air near the ground.] *U.S.S.R. Glavnoe Upravlenie Gidrometeorologicheskoi Sluzhby, Informatsionnyi Sbornik*, 1952:28-36, 1951. figs., 2 tables, 5 refs. **DLC**—The use of radioactivity measurements to determine the coefficient of turbulent exchange is suggested. The basic differential equation is:

$$\frac{\partial S}{\partial t} = A \frac{\partial^2 S}{\partial h^2} + \frac{\partial A}{\partial h} \frac{\partial S}{\partial h} - \lambda S,$$

where  $S$  = concentration of emanation in the air;  $t$  = time;  $h$  = height above the ground;  $\lambda$  = decay constant of the emanation;  $A = \frac{1}{h}$  = coefficient of turbulent exchange. The author developed a method for the determination of  $A$  knowing  $S$  for the air in the soil and in the atmosphere and knowing the diffusion coefficient of the emanation in the soil. Results of measurements and calculations show a sharply expressed diurnal course of the exchange coefficient. *Same item as 4B-273, Feb. 1953, MAB.* *Subject Headings:* 1. Radioactive diffusion 2. Exchange coefficient 3. Diurnal turbulent exchange variations.—A.A.

1952

7E-38

551.594.14:551.578.11

Abribat, Marcel; Pinoir, Robert; Pouradier, Jacques and Venet, Anne-Marie, *Sur l'existence de produits radioactifs artificiels dans les eaux de pluie de la région parisienne*. [The presence of artificial radioactive matter in rain water in the region of Paris.] *Académie des Sciences, Paris, Comptes Rendus*, 254 (11):1161-1163, March 10, 1952. fig. **DWB**—Measurements made with a Geiger-Müller counter at the research laboratory of Kodak-Pathé are reported.  $\beta$ -rays emitted by dry residue of rainwater were measured and showed abnormally high activity 8-15 days after nuclear explosions in Nevada on Oct. 22 and Nov. 19, 1951. The lack of emission of  $\alpha$  particles proved that the residue investigated was of artificial origin which leads to the conclusion that they came from the Nevada explosions, an assumption which is supported by the agreement of dates. The radioactivity measured during the critical months is graphically illustrated. *Same item as 4B-272, Aug. 1953, MAB.* *Subject Headings:* 1. Radioactivity in rainwater 2. Rainwater analysis 3. Radioactive rainout 4. Paris, France.—G.T.

7E-39

551.594.14

Abribat, Marcel; Pouradier, Jacques and Venet, Anne-Marie, *Sur les produits radioactifs artificiels existant dans l'atmosphère de la région parisienne*. [On the artificial radioactive products present in the atmosphere in the region of Paris.] *Académie des Sciences, Paris, Comptes Rendus*, 235 (2):157-159, July 16, 1952. 3 figs., refs. **DLC**—Daily air filtering from Nov., 1951 to June, 1952 showed  $\beta$ -activity in Nov. and Dec., and a much stronger peak in the spring of 1952. Also measured activity in precipitation residue. A plot of activity vs. time for the three most active air samples (May 15, April 17, 1952) and the most active rain samples (Nov. 6, 1951) showed the exponent in the decay law to be  $-1.2 \pm 0.1$ . *Subject Headings:* 1. Radioactivity in rainwater 2. Paris, France.—R. J. List.

7E-40

551.508.79:551.579.5:551.594.14

Belcher, D. J.; Cuykendall, T. R. and Sack, H. S. (all, *Cornell University*), *Nuclear meters for measuring soil density and moisture in thin surface layers*. *U. S. Civil Aeronautics Administration, Technical Development and Evaluation Center, Technical Development Report*, No. 161, Feb. 1952. 8 p. 6 figs., table. **DWB**—The measurement of soil density and moisture at varying depths by means of nuclear instruments was described previously in its *Technical Development Report*, No. 127. The present report describes the development of new meters that measure density and moisture of the surface layer of soil. Using the same radioactive sources and same counter tubes as used in the depth probes, but with a different geometric design, these preliminary models prove to be promising under both laboratory and field conditions. Further studies are being made to improve their operational characteristics, particularly that of sensitivity. When perfected, they can be

used advantageously for compaction control and related purposes in all types of earth construction. They are efficient, convenient and economical. It takes about fifteen minutes to take measurements and obtain the results on a complete set of density and moisture readings. *Subject Headings:* 1. Radioactive soil moisture instruments 2. Soil density instruments.—*Authors' abstract.*

7E-41

551.594

Blifford, Irving H.; Lockhart, Luther B., Jr. and Rosenstock, Herbert B. (U. S. Naval Lab., Wash., D. C.), On the natural radioactivity in the air. *Journal of Geophysical Research* 57 (4):499-509, Dec. 1952. 2 figs., 11 refs., 16 eqs. DLC—The concentrations of the various radioactive decay products of radium in the air have been determined by observing the beta activity (1) of pieces of filter paper through which air has been passed, and (2) of chemically separated isotopes obtained from such filter papers. The relative amounts of long-lived and short-lived products found indicate that, besides the radioactive decay of the substances, some other process which removes radioactive particles from the air is active. The mean life of the particles with respect to this removing process is found to be about 10 days. The hypothesis that this process is the capture of the radioactive particles by rain droplets (clouds) is consistent with measurements made of the radioactive content of rainwater. On the other hand, the removal of the ionized radioactive particles by the electric field of the earth leads to a much smaller effect. (*Same item as* 4.8-273, Aug. 1953, MAB.) *Subject Headings:* 1. Radioactivity in the atmosphere.—*Authors' abstract.*

7E-42

551.594

Dawson, K. B., Radioactive material in the atmosphere. *British Journal of Cancer*, 6:22-23, 1952. 6 tables, 10 refs. DSG—Summary of observations at 3 sites in London (open air and cell or raid shelter), Rothamsted and Manchester, in c/m<sup>2</sup>. No consistent differences from towns or country in the open, but rapid variations from day to day. Underground amounts were more than 100 times greater than open but did not reach harmful level. (*Same item as* 5.3-318, March 1953, MAB.) *Subject Headings:* 1. Radioactivity in the atmosphere 2. England.—C.E.P.B.

7E-43

551.508.77:551.578.4:551.594

Doremus, John A. (Motorola, Inc., Chic.), Radioactive snow gage with telemetering system. *Eastern Snow Conference, 9th, Springfield, Mass., 1952, Proceedings*, p. 13-23, [1952?] 8 figs. (incl. photos) DWB—The technical (engineering) aspects of the radioactive snow gage are described and illustrated. The telemetering system, calibration (counts per minute vs. inches of water in snow column), elimination of background count, magnitude of error, proposed use of scintillation counter to reduce dead time and increase accuracy of count, wiring of a typical transmitting station (automatic) and automatic repeater station, etc., are covered. The engineering group headed by the author put GERDEL's idea of a radioactive snow gage into operational form so that data from a network of remote gaging stations could be collected at one central point for use by the forecasters. One main problem has been to have the data recorded in units which are directly applicable (water equivalent) rather than in counts per minute. *Subject Headings:* 1. Radioactive snow gages 2. Telemetering systems.—M.R.

7E-44

551.577:551.594

Garrigue, Hubert, Recherches sur les précipitations atmosphériques a l'échelle du globe. [Research on atmospheric precipitation on a global scale.] *Académie des Sciences, Paris, Comptes Rendus*, 234 (15):1571-1573, April 7, 1952. DWB—In connection with observations on the reduction of radioactive pollution in the atmosphere between 1946 and 1951, the author investigated variations in precipitation over the entire earth during this period. The world is divided into regions, viz.: 1) North America, 2) South America, 3) Europe, 4) India, 5) Japan, 6) Australasia, 7) South Africa and 8) Philippines, and mean monthly precipitation for 1949 is compared with the normals. An increase in mean annual precipitation is noted for 1949 and 1950. (*Same item as* 4.10-200, Oct. 1953, MAB.) *Subject Headings:* 1. Global precipitation variations 2. Precipitation effects on radioactivity.—I.L.D.

7E-45

551.594

\*Garrigue, Hubert, Sur la radioactivité anormale de l'atmosphère. [On abnormal radioactivity of the atmosphere.] *Académie des Sciences, Paris, Comptes Rendus*, 235 (23):1498-1499, Dec. 1952. table. DWB—The tabulated recordings on the radioactivity of the atmosphere were based on ground observation at 1500 m (Puy de Dôme) and flights up to 5000 m on selected days from April 11 through July 1, 1952. This span of time permits no satisfactory conclusion to be drawn to speed of propagation and dissemination of radioactive "atomic" clouds. (*Same item as* 6.5-3, May 1955, MAB.) *Subject Headings:* 1. Radioactivity in the atmosphere 2. Radioactive fall propagation 3. Puy de Dôme, France.—W.N.



on a gammameter varies as a function of (1) the radioactivity of the soil, (2) the intensity of cosmic radiation and (3) charge of the radioactive elements contained in the air surrounding the instrument. By eliminating factors (1) and (2) the radioactivity of atmospheric air can be measured. Experimental evidence presented is found to justify this method. Probable error involved is evaluated. *Subject Headings: 1. Radioactivity in the atmosphere 2. Gammameters.—G.T.*

7E-52

Lossnitzer, H., *Über meteorologisch bedingte Schwankungen der radioaktiven Umgebungstrahlung*. [Meteorologically conditioned variations in local radioactive radiation.] *Baden Landeswetterdienst, Jahresbericht mit Abhandlungen, 1951/1952*. p. 154. fig. DWB—A short note showing that the diurnal means of radioactivity observed over 2½ months show variations which can be attributed to meteorological factors (snow cover, precipitation, etc.). (Same item as 6.5-343, May 1955, MAB.) *Subject Headings: 1. Meteorological effects on radioactivity 2. Radioactivity in the atmosphere.—A.A.*

7E-53

Luntz, Jerome D., *Radiation safety for a weapons test*. *Nucleonics*, N. Y., 10(5):10-11, May 1952. 11 figs. DLC—Describes monitoring in areas within 200 mi of test site, in ring from 200-500 mi, and nationwide monitoring with gummed paper and air filters during the Nevada test in the Spring of 1952. States that for an air burst of one nominal bomb, 0.02 per cent of the fission products were left on the ground within a radius of 2000 ft of ground zero. *Subject Headings: 1. Radiation safety measures 2. Radioactive fallout networks.—R. J. List.*

7E-54

Rose, D. C. and Katzman, J., *Radioactive deposits at Ottawa after the atomic explosions of January and February 1951*. *Canadian Journal of Physics*, 30(2):111-116, March 1952. 4 figs., 5 refs. DWB—At about 1000 G.M.T. on Jan. 29 and about 0800 G.M.T. on Feb. 7, 1951 the fall of a considerable amount of radioactive matter was recorded by various arrangements of Geiger-Müller counters which were in continuous operation on the roof of the cosmic ray observatory of the National Research Council of Canada at Ottawa. Light snow was falling on both occasions (changing into rain on Feb. 7), but it is uncertain whether this had any bearing on the deposit of radioactive material. The material was found to be dust distributed over the snow cover. The quantity was roughly estimated to be of the order of one microgram radium equivalent per square meter. Measurement of decay rate was made on samples of melted snow and indicated that the radioactivity recorded on the above dates was probably due to products of fission originating in atomic explosions in Nevada on Jan. 27, and between Feb. 2 and Feb. 4, respectively. Decay curves are presented and the arrangement of the counter trays shown in a diagram. (Same item as 5.2-303, Feb. 1954, MAB.) *Subject Headings: 1. Radioactive fallout data 2. Ottawa, Canada.—G.T.*

7E-55

Schellenberger, Günther, *Zur Verteilung radioaktiver Substanzen in einem turbulenten Windfeld*. [On the distribution of radioactive substances in a turbulent wind field.] *Zeitschrift für Meteorologie*, 6(8):225-231, Aug. 1952. 2 figs., 8 refs., eqs. DWB—The diffusion of an emanation of gas in the turbulent atmosphere from a linear or point source is studied, using ERTL's differential equation of exchange and considering the decay constant and concentration of the emanation. The solution can be used in unsteady cases starting with 100 m from the source. As a steady case the vertical distribution of emanation is derived theoretically as a function of the exchange coefficient  $\eta$ . Assuming  $\eta = 50$  [g cm<sup>-1</sup> sec<sup>-1</sup>] the height of half value ( $h$ ) is found for Ra (A, B, C)  $h \times 1100$  m, Ra (D, E, F) practically no vertical decrease in the troposphere, emanations of Th and Ac  $h \approx 1$  and 4 m, Th (B, C . . .)  $h \approx 300$  m, Ac (B, C . . .)  $h \approx 80$  m. (Same item as 4B-321, Feb. 1953, MAB.) *Subject Headings: 1. Radioactive diffusion 2. Turbulence theory.—A.A.*

7E-56

U. S. Office of Naval Research, London, *Atmospheric radioactivity following nuclear explosions*. Its *Technical Report ONRL-66-52*, July 3, 1952. [5 p.] 3 figs. DWB—Brief note on measurement of  $\beta$ -activity of rain water, made by employees of Kodak-Pathé at Paris, from Nov. 1951 through Feb. 1952, following nuclear explosions in Nevada on Oct. 22, Nov. 5 and Nov. 19, and on activity of atmospheric dust observed during the same period. Radioactivity curves of rainwater and dust are presented for the four months and show peak values about ten days after nuclear explosions and amounts reaching 20 times normal during Nov. and Dec. A map indicating the paths of air masses at 700 and 500 mb levels, as traced back from Paris to Nevada by M. GENÈVE of the Météorologie Nationale, is reproduced. The French Meteorological Office is setting up a network in Norway, France, Morocco and French West Africa for further observations of radioactivity. (Same item as 551.594.14:551.515.)

4242, June 1953, *MAB.*) *Subject Headings:* 1. Radioactivity in the atmosphere 2. Radioactive fallout networks 3. Air mass movements. I. Hyde, W. Lewis.—*G.T.*

7E-57 551.594.14:551.501.9  
Weiss, Max M., The area survey manual of Brookhaven National Laboratory: area radiation detection instrumentation, maintenance and results. *U. S. Brookhaven National Laboratory, Upton, N. Y., BNL 167, Jan. 1, 1952.* 147 p. figs., tables, refs., eqs. **DLC**—Instrumentation for the area radiation monitoring system of Brookhaven National Lab. is described in detail; its operation and maintenance is discussed. The units are: (1) photographic assembly, (2) Geiger-Müller counter assembly, (3) battery-operated ratemeter assembly, (4) dynamic condenser electrometer—ionization chamber, (5) continuous dust monitor for airborne radioactive dust, (6) integrating ionization chambers, and other installations. The report includes an analysis of measurements of background radiation and its variations due to (a) natural causes, (b) reactor operations (c) atomic explosions. *Subject Headings:* 1. Radioactive fallout networks 2. Radioactivity measurement techniques 3. Radioactive effluents 4. Instrument manuals 5. Brookhaven National Lab., Upton, N. Y. I. U. S. Atomic Energy Commission.—*G.T.*

7E-58 551.508.91:546.432  
Wilkening, M. H., A monitor for natural atmospheric radioactivity. *Nucleonics*, New York, (6):36-39, June 1952. 4 figs., table, refs. **DLC.** Also issued as New Mexico Institute of Mining and Technology, Contract N7ONR-405, Task 1, Project NR-082-013, Technical Report, No. 6-NR, 1952. 4 figs., table, 5 refs. **DWB**—The apparatus described in this paper is used at the New Mexico Institute of Mining and Technology. It records time variations of radon and thoron products deposited by an electrostatic precipitator on a moving tape. The instrument is used, in particular, for studies of the effect of meteorological phenomena on the natural radioactivity in the atmosphere. Alpha activities from 12 to over 400 cpm have been observed and variations up to a factor of 10 occurred in the course of a day. Two sample records (one showing effect of long wind on  $\alpha$ -activity) and graphs showing average diurnal variations of  $\alpha$  and  $\beta$  counts for 14 days are presented. *Subject Headings:* 1. Electrostatic precipitators 2. Radon content of atmosphere 3. Aerosols 4. Radioactivity in the atmosphere 5. Socorro, New Mexico.—*G.T.*

1953

7E-59 551.594.14  
Aribrit, Marcel and Pouradier, Jacques, Évolution de la teneur en radioéléments artificiels de l'atmosphère de la région parisienne. [Evolution of the artificial radioelement content of the atmosphere in the Paris region.] *Académie des Sciences, Paris, Comptes Rendus*, 237 (20):1233-1235, Nov. 16, 1953. 2 figs., 2 refs. **DLC**—Daily air filter measurements in Paris from Jan. through Oct., 1953 clearly show increases in  $\beta$ -activity during the spring and fall, corresponding to the Nevada and Russian tests, respectively. Spring peak about three times peak from Russian tests, activity in rainfall also shows marked increase in spring, lack of precipitation in Sept. resulted in evidence of the Russian tests in rainfall. *Subject Headings:* 1. Radioactive fallout data 2. Paris, France.—*R. J. List.*

7E-60 551.594.14:551.578.11(767)  
Damon, P. E. and Kuroda, P. K., On the artificial radioactivity of rainfall. *Nucleonics*, (12):59, Dec. 1953. **DLC**—On June 5, 1953, rain which fell in Fayetteville, Arkansas was found to contain fission product activity. Radiochemical analyses of several elements. Analysis of rainwater from June 5 to June 23 showed an apparent correlation between artificial radioactivity and air mass. High activity associated with polar continental air, low with tropical maritime. The total fission activity falling in the two-month period in the vicinity of Fayetteville was in excess of  $10^{-3}$  curie per sq m. *Subject Headings:* 1. Radioactive fallout data 2. Fayetteville, Arkansas.—*R. J. List.*

7E-61 551.594.14:551.501.9  
Eisenbud, Merrill and Harley, John H. (*U. S. Atomic Energy Comm., N. Y.*), Radioactive dust from nuclear detonations. *Science*, 117(3033):141-147, Feb. 13, 1953. 3 tables, fig., 8 refs. **DWB**—Results obtained in measuring radioactivity in dust particles dispersed by nuclear explosions are reported. The measurements are being made by a monitoring system set up by the Atomic Energy Commission and comprising 121 monitoring stations located at Weather Bureau stations throughout the U. S., as well as mobile teams operating in the area 200-500 mi from the atomic test site. After discussing the data obtained so far, the authors conclude that "the long-lived components of the radioactivity are of a low order compared with the natural radioactivity of the earth's surface and atmosphere." (Same item as 4.10-90, Oct. 1953, *MAB.*) *Subject Heading:* 1. Radioactive fallout networks.—*G.T.*

7E-62

551.594.14

Fafarman, A. and Shamos, M. H., *Effect of fall-out from atomic blast on background count rate.* *Nucleonics*, N. Y., 11(6):80-81, June 1953. 2 figs. DLC—Background measurements with a sodium-iodide scintillation detector at New York Univ. show normal variation of  $\pm 5\%$ . 1030, March 19, 1953, the rate increased to 3850 cpm, 600% above background. A heavy fallout preceded the measurement and presumably contained debris from the March 17 Nevada test. Removal of rain water dropped rate to 1470 cpm. Curves of energy versus count before and after fallout are given. *Subject Headings: 1. Radioactive rainout 2. New York, N. Y.—R. J. List.*

7E-63

551.510.42:551.578.41 551.594.14:551.578.41

Garrigue, Hubert, *Observations sur les impuretés contenues dans l'air libre.* [Observations of impurities in the free air.] *Académie des Sciences, Paris, Comptes Rendus*, 236(24):2309-2310, June 15, 1953. refs. DWB—Measurements of atmospheric impurities are reported from the Puy de Dôme peak (1450 m) and various points within 500 m below the peak (Jan.-Feb. 1953). The measurements were made by analyzing residual matter obtained from evaporated snow samples.  $10^4$ - $10^6$  radioactive atoms (probably fission products) and 0.01-0.1 g of dust and soot were identified per liter of precipitation. The synoptic situations prevailing during the sampling are specified. The dust and soot are attributed to local factors, while the radioactive matter is thought to be of very remote origin (in respect to both space and time), which would mean that it affects large areas. (Same item as 5.7-72, July 1954, MAB.) *Subject Headings: 1. Radioactivity in snow 2. Snow radioactivity analysis 3. Puy de Dôme, France.—G.T.*

7E-64

551.594.14

Garrigue, Hubert, *Prospection de la radioactivité de l'air.* [Observation of the radioactivity of the air.] *Académie des Sciences, Paris, Comptes Rendus*, 237(15):802-803, Oct. 12, 1953. DLC—Aircraft sampling at about 3000 m from May to Sept., 1953, indicated no evidence of atomic debris or only traces on most occasions. During flights on Aug. 15 and Aug. 28, material with an apparent half-life of 25 hrs was found. The concentration on the 15th was  $0.1 \times 10^{-18}$  c/cm<sup>3</sup> radon equivalent. *Subject Headings: 1. Radioactivity in the atmosphere 2. Airplane sampling of radioactivity—R. J. List.*

7E-65

551.594.14:551.578.41

Garrigue, Hubert, *Sur la radioactivité de l'atmosphère d'origine atomique.* [On atmospheric radioactivity of atomic origin.] *Académie des Sciences, Paris, Comptes Rendus*, 237(20):1232-1233, Nov. 16, 1953. refs. Also: Same title, *Ibid.*, 240(2):178-180, Jan. 10, 1955. 5 refs. DLC—(1) Aircraft measurements in Oct. 1953 show at most traces of radioactivity. Snow sample (7 kg) on Nov. 3, 1953 yielded  $0.1 \times 10^{-18}$  c/cm<sup>3</sup> (radon equivalent) in the residue, about 20% above background. Only  $\beta$ -activity was found.—(2) Aircraft sampling over France in the summer of 1954 showed no positive results. A flight on Oct. 13, 1954 at 3000 m showed a trace of long-lived particles. Analysis of solid residue from 7 kg of precipitation which fell on Dec. 5 and 6, 1954, showed  $\beta$ -activity 14% above background from long-lived particles. *Subject Headings: 1. Radioactivity in the atmosphere 2. Radioactivity in snow 3. Airplane sampling of radioactivity 4. France.—R. J. List.*

7E-66

551.501:551.594.14:546.2

Haxel, Otto, *Eine einfache Methode zur Messung des Gehaltes der Luft an radioaktiven Substanzen.* [A simple method of measuring the content of radioactive substances in the air.] *Zeitschrift für angewandte Physik*, 5(7):241-242, July 1953. fig., 3 refs. DLC—Filter paper containing asbestos or amber have the property of retaining radioactive emanations. If a measured volume of air is passed through such a filter and the radioactivity of the paper measured, the radioactivity of the air is given. Its nature can be determined from the decay curve. (Same item as 5.2-24, Feb. 1954, MAB.) *Subject Heading: 1. Radioactivity measurement techniques.—C.E.P.B.*

7E-67

551.594.14:551.578.41

Haxel, Otto and Schumann, G., *Über die radioaktive Verseuchung der Atmosphäre.* [On the radioactive contamination of the atmosphere.] *Naturwissenschaften*, 40(17):458-459, Sept. 1953. 2 figs., refs. DWB—Continuous records of radioactivity at Königsstuhl near Heidelberg since March 1953 show long-lived activity which is attributed to end products of atomic bomb explosions. The Las Vegas explosion of May 8 appeared as a sudden increase of activity on May 10 to  $2.5 \times 10^{-12}$  c/m<sup>3</sup>. (Same item as 5.2-302, Feb. 1954, MAB.) *Subject Headings: 1. Radioactivity in the atmosphere 2. Atomic explosions 3. Königsstuhl, Germany.—C.E.P.B.*

7E-68

551.594.14:551.513.2:551.557.4

†Herbst, W.; Neuwirth, R. and Philipp, K., *Betrachtungen über die Eignung radioaktiver atomtechnischer Aerosole als Markierungsmittel bei Arbeiten auf dem Gebiete der meteorologischen*

**Strömungsforschung.** [Remarks on the suitability of artificial atomic radioactive aerosols as markers for work in atmospheric current investigations.] *Naturwissenschaften*, 41(7):156-160, April 1, 1954. 3 figs., 17 refs. **DLC**—Radioactive aerosols from the atom bomb explosion in Nevada on June 5, 1952, were brought down by rain at Helena, 800 km distant, on June 6-15. At Wittental, Germany (47°59'N, 7°57'E), twice normal radiation was recorded on June 18-19. During intervening days there was a steady jet stream. Beginning June 6 at Helena, tracks on 500 mb charts ran 18,000 km across Atlantic and round N. Scandinavia, reaching Germany from the east on June 18. Tracks leaving Helena on June 8-13 did not reach S.W. Germany but a direct track from Helena on June 14 gave a second radiation peak at Wittental on 21st. The occurrences at Wittental are attributed to descent of air at a divergence line on the margin of the jet stream. Technique of measuring residual atomic products is discussed. (Same item as 5.8-276, Aug. 1954, MAB.) *Subject Headings:* 1. Radioactivity in the atmosphere 2. Jet stream 3. Atomic explosions. —C.E.P.B.

7E-69

551.594.14:551.557

Herbst, Walter and Philipp, K., **Wanderweg eines atomtechnischen Aerosols.** [Track of an atomic aerosol.] *Naturwissenschaften*, 40(2):54, Jan. 2, 1953. 3 refs. **DWB**—Measurements with Geiger-Müller counter at Wittental near Freiburg showed a strong increase of "null" effect to 2-3 times its normal level on Oct. 18-20, 1951. This was traced back by weather charts to the radioactive cloud from an atom bomb, which passed Helena, Mont. on Oct. 6. (Same item as 4.8-275, Aug. 1953, MAB.) *Subject Headings:* 1. Atomic explosions 2. Radioactivity in the atmosphere 3. Upper air winds 4. Freiburg, Germany.—C.E.P.B.

7E-70

551.594.14

Hess, Victor F. (Fordham Univ., N. Y.), **On the ionization produced by gamma radiation from the ground and from the atmosphere.** *Journal of Geophysical Research*, 58(1):67-72, March 1953. table, 5 refs., 4 eqs. **DWB**—Two new methods for quick determination of the ionization produced by the gamma rays from the radioactive substances in the ground are discussed. The first ("absorption method") utilizes partial screening of a portable ionization meter with a lead shield of one centimeter from the bottom and from the sides, and empirical determination of its absorbing power. This method was tried out in field experiments and its results agree very well with the results obtained with the conventional method (alternative measurements over soil and over water). The second method ("well method") consists in placing a cylindrical ionization chamber inside an iron housing with a wall 10 cm thick, but open at the top and on the bottom. The chamber is used in two positions inside this "iron well" and from the difference of ionization observed at these two positions the total value of the terrestrial gamma radiation can be derived. Both methods can also be used for determining the gamma radiation coming from the atmosphere ("air radiation"); however, the smallness of this effect makes it difficult to get reliable results. Discrepancies arising in this case are discussed. (Same item as 5.1-309, Jan. 1954, MAB.) *Subject Heading:* 1. Radioactive emanations.—Author's abstract.

7E-71

551.594.14

Hess, Victor F., **Radon, thoron, and their decay products in the atmosphere.** *Journal of Atmospheric and Terrestrial Physics*, 3(3):172-177, April 1953. 2 tables, 16 refs. **DWB**—Ionization due to alpha rays measured at Fordham University, New York, by HESS and VANCOUR (1950) is recalculated to eliminate errors. Radon+decay products gave  $53.8 \times 10^{-18}$  c/cm<sup>3</sup> or 0.70 I (ions produced per cc per sec), thorium products  $41.0 \times 10^{-18}$  curie or 0.53 I. (Same item as 4.8-276, Aug. 1953, MAB.) *Subject Headings:* 1. Radioactivity in the atmosphere 2. Ionization.—C.E.P.B.

7E-72

551.506:539

Holzman, Benjamin G. (Kirtland Air Force Base, New Mexico), **Have atom bomb tests fouled up the weather?** *Look*, Des Moines, Iowa, 17(16):32-33, Aug. 11, 1953. diagr. Biographical note p. 32. **DWB**—The author, who has studied the meteorological effects and attending conditions for a number of atom bomb tests, shows that the atomic debris from the June 4, 1953 test in Nevada was far out to sea in the Atlantic when the Michigan and Worcester, Mass. tornadoes occurred, and states unequivocally that the explosion of an A-bomb does not affect the weather except locally through convective currents attending large scale fires started by the bomb (as at Hiroshima) or by affecting local winds temporarily. The energy and the debris from such an explosion are insignificant compared to the energy of a thunderstorm or hurricane, or condensation nuclei from sea salt or dust which are always present. (Same item as 5.6 42, June 1954, MAB.) *Subject Headings:* 1. Atomic explosion effects on weather 2. Tornadoes (June 1953).—M.R.

7E-73

551.594.14

Moraschinelli, E. (Pavia Univ.), **Autoradiografia dell'aerosol atmosferico.** [Autoradiography of atmospheric aerosols.] *Il Nuovo Cimento*, Bologna, 10(9):1341-1342, Sept. 1, 1953. refs.

**DLC**—Radioactive matter, produced by disintegration of radium and thorium emanation, can become "anchored" to aerosols. In this paper an apparatus for determining radioactive transitions in a film of deposited atmospheric solid particles is described. The principal problem investigated with the apparatus was whether successive elements of the two series of radium-uranium and thorium are fully present on the aerosols. After discussing the radioactive transitions identified, the author concludes that there is no radioactive equilibrium on the aerosols. The process of "anchorage" necessitates a certain time; short-lived elements are, therefore, liable to undergo a transformation before being anchored to an aerosol. (Same item as 5.9-313, Sept. 1954, MAB.) *Subject Heading: 1. Radioactive aerosols.—G.T.*

7E-74

551.594.14

Moraschinelli, E., *Misura della radioattività atmosferica con emulsioni nucleari*. [Measurement of the radioactivity of the atmosphere by means of nuclear emulsions.] *Annali di Geofisica*, 6(4):561-567, Oct. 1953. 11 refs. Italian and English summaries p. 567. **DLC**—A method of measuring atmospheric radioactivity by the employment of nuclear emulsions is described. The radioactive components are separated from the air by electrostatic separation into an electrode plate, following which, the plate is placed on the sensitive emulsion in order to obtain a registration of the emitted alpha particles. From a microscopic examination of the emulsion one determines the relative amount of atmospheric radioactivity and it is also possible to discriminate between the elements of the thorium family and those of the uranium-radium family. (Same item as 6.1-345, Jan. 1955, MAB.) *Subject Headings: 1. Radioactivity measurement techniques 2. Nuclear emulsions.—Author's abstract.*

7E-75

551.594.14:551.521.64

Pfotzer, G., *Zur Berechnung der Gleichgewichtsmenge  $\beta$ -aktiven Kohlenstoffes in der Atmosphäre aus Daten über Ultrastrahlungsneutronen*. [On the calculation of the equilibrium amount of  $\beta$ -active carbon from data on cosmic-ray neutrons.] *Zeitschrift für Naturforschung*, 7a(2):147-149, Feb. 1952. 9 eqs., refs. **DLC**—Calculations can be made using measurements of (a) the counting rate of unscreened counters; (b) (less accurately) the change in counting rate on inserting a Cd absorber (Cd-difference). The production rate of  $C^{14}$  is  $1.9-2.5$  atoms  $\text{sec}^{-1} \text{cm}^{-2}$  of air, giving an equilibrium amount of  $1.1-1.5 \times 10^{-11} \text{ g cm}^{-2}$  earth's surface. The corresponding  $C^{14}$  activity in organic biological substances is  $13.5-18 \beta$ -disintegrations  $\text{min}^{-1} \text{g}^{-1} \text{C}$ , in agreement with the measurements of Anderson and Libby. *Subject Headings: 1. Cosmic ray effects 2. Radio-carbon in the atmosphere.—Physics Abstracts, No. 5998, 1952.*

7E-76

551.5:662.2:539.1

Reichelderfer, Francis W., *What's wrong with the weather?* *U. S. News and World Report*, Wash., D. C., 34(26):50-54, 59-66, June 26, 1953. port., diags. **DLC**—An extensive interview between REICHELDERFER, chief of the U. S. Weather Bureau and the editors of the U. S. News and World Report wherein the author gives the latest official information or opinions on the possibility of atomic explosions influencing the weather, on radiation effects of atomic explosions, etc. It is concluded that the energy of an atom bomb is too small to influence the large-scale weather processes or even hurricanes. (Same item as 5.1-13, Jan. 1954, MAB.) *Subject Heading: 1. Atomic explosion effects on weather.—M.R.*

7E-77

551.594.14:551.577:539

Santomauro, L. and Cigna, A., *Prime misure sulla radioattività delle precipitazioni atmosferiche*. [First measurement of radioactivity of precipitation.] *Annali di Geofisica*, Rome, 6(3):381-387, July 1953. 2 figs., 16 refs. English summary p. 387. **MH-BH**—During Feb. 1951 to Nov. 1952, the radioactivity of atmospheric precipitation was tested with a G-M counter. This activity was not constant: indeed it became greater after atomic experiments at Las Vegas, Eniwetok and Montebello Island. Therefore these facts are probably related. The activity increased about 8 days after Las Vegas experiments, two weeks after Eniwetok experiments and about three weeks after Montebello Island explosions. Gamma and beta rays of the precipitation have been measured with G-M counter and the background of cosmic radiation was considered in drawing the diagrams. (Same item as 5.8-277, Aug. 1954, MAB.) *Subject Headings: 1. Radioactivity in precipitation 2. Atomic explosions 3. Italy.—Authors' abstract.*

7E-78

551.594.14

Sittkus, A.; Ganz, D. and Remy, E., *Untersuchungen über die radioaktive Umgebungsstrahlung und ihre Wirkung*. [Investigations into radioactive radiation from surroundings and its effect.] *Zeitschrift für Naturforschung*, 8a(5):317-322, May 1953. 4 figs., table, 11 refs. **DLC**—An investigation of influence of effect of nearby radioactive radiation on measurements with ionization chambers and simple counters showed that variations of ground and air radiation could change zero of unprotected apparatus by 100%, and behind  $50 \text{ g/cm}^2$  shield by 10%. Effect was due mainly

to new snow and rain water. (Same item as 4.10-260, Oct. 1953, MAB.) *Subject Heading: 1. Radioactivity in the atmosphere.—C.E.P.B.*

7E-79

551.594.14:551.579

Thomas, Harold A., Jr.; Kleinschmidt, R. Stevens; Parker, Frank L. et al., **Radioactive fallout in Massachusetts surface waters.** *American Water Works Association, Journal*, 45(6):562-568, June 1953. 2 figs., 6 tables, 3 refs., 4 eqs. **DLC**—Beginning on April 26, 1952, a series of weekly samples of water from various streams and reservoirs in Massachusetts and rain samples were tested for gross beta-gamma activity. Highest rain water activity, at Cambridge, Mass., on June 5, 1952, was 6899 cpm/liter, with a counter efficiency of 10-15%. A settling test on a rain water sample indicated 53.6% of the activity was in the lowest 25% of a glass cylinder in which the water had been allowed to settle for 48 hrs. Decay curves of several samples are given. *Subject Headings: 1. Radioactivity in surface waters 2. Massachusetts. I. Bell, Carlos G., Jr.—R. J. List.*

7E-80

551.594.14

\*Tsivoglou, E. C.; Ayer, H. E. and Holaday, D. A., **Occurrence of non-equilibrium atmospheric mixtures of radon and its daughters.** *Nucleonics*, New York, 11(9):40-45, Sept. 1953. 3 figs., 7 tables, 4 refs., 12 eqs. **DLC**—Describes method for laboratory field analysis of emission and decay properties of radon and its daughter products (RaA, RaB and RaC). Results obtained in a closed radon box and in two uranium mines under different conditions of ventilation are presented. The data were collected for the purpose of arriving at a more accurate evaluation of the effectiveness of ventilation in protecting workers in uranium mines. *Subject Headings: 1. Radioactivity measurement techniques 2. Uranium mines.—G.T.*

7E-81

551.594.14:551.501.9

U. S. Atomic Energy Commission, **Thirteenth Semiannual Report.** Washington, D. C., Government Printing Office, Jan. 1953. 210 p. figs., photos. **DLC**—Pt. 3 of this report (p. 77-125) deals with "Public safety in continental weapons tests." Effects of atomic explosions, the influence of various meteorological factors upon such effects, and pretest weather forecasts are discussed. The air sampling and radiation monitoring system consisting of fixed, mobile and airborne units around the test site and a national network of stations located at U. S. Weather Bureau Stations is described; instruments used and general results are indicated. It is found "that the highest levels of radioactivity released by fall-out of particles are well below the very conservative standards fixing the amounts of radiation that can be received externally or internally by the human body without harming the present or later generations." *Subject Headings: 1. Radioactive fallout networks 2. Atomic explosion effects.—G.T.*

7E-82

551.594.14:551.577

U. S. Atomic Energy Commission, **Fourteenth Semiannual Report.** Wash., D. C., Govt. Print. Off., July 1953. 98 p. figs., tables. **DLC**—Radioactivity was reported in snow in the northeastern United States during the Nevada tests of Jan. and Feb., 1951. Snow and rain samples were collected on Feb. 2 and 3 and again on Feb. 6-9. Activity in the filtrate and residue was measured, the highest total activity found was 25,300 d/m/l, corrected to Feb. 2, 1951, at Hannibal, New York, in a sample collected on Feb. 3. *Subject Headings: 1. Radioactivity in precipitation 2. Hannibal, N. Y.—R. J. List.*

1954

7E-83

551.510.41:551.594.14

Anderson, W.; Mayneord, W. V. and Turner, R. C., **The radon content of the atmosphere.** *Nature*, London, 174(4427):424-426, Sept. 4, 1954. fig., 13 refs. **DWB**—Comparative measures of radon by filter paper and ion chamber showed that the latter gave values 10-100 times the former. Large values in London smog ( $8 \times 10^{-13}$  c/l by filter paper) suggest radon is derived from coal and prevented by solid matter from dilution. Measurements of coal and coal ash show  $0.05-0.3 \times 10^{-12}$  gm radium per gm coal, 70-80% of which is liberated by burning. Coal gas contains  $0.5 \times 10^{-12}$  c/l. Fraction of atmospheric radon originating from coal cannot yet be assessed. (Same item as 6.1-113, Jan. 1955, MAB.) *Subject Heading: 1. Radon content of atmosphere.—C.E.P.B.*

7E-84

551.594.14:551.510.42:551.578.11

\*Chatterjee, Santimay; Patro, A. P.; Basu, Binayak; Bhattacharyya, R. L. and Hosain, Fazie, (Inst. of Nuclear Physics, Calcutta), **Presence of radioactive dusts over Calcutta.** *Science and Culture*, Calcutta, 19(11):570-571, May 1954. table, 2 refs. Also their: **Measurements on radioactive dusts over Calcutta.** *Ibid.*, 20(8):399-401, Feb. 1955. table, 5 refs. **DWB**—Following the nuclear explosions in the Pacific on April 4, 1954, tests were made at Calcutta to detect possible  $\alpha$ ,  $\beta$  or  $\gamma$  radioactive particles settling from the atmosphere. No rain occurred until April 29.

Samples of rainwater and dust (1000 cc) gave definite indication of  $\beta$  activity ( $120 \pm 10$  counts/min/gram). Dust collected from greasy parts of airplanes arriving daily at Dum Dum Airport from Ganhathi and on Sunday from Singapore from April 14-22 showed no  $\alpha$  or  $\gamma$  activity, but consistent  $\beta$  activity ranging from 5.8 to 121 counts/min/gram. The highest value was on April 11 on a plane flying to Djakarta and back at 12,000 ft. None of these rates are dangerous but they do indicate transport and detection of activity 5000 mi from source. In the second article the authors report that radioactivity was detected in rainwater collected at Calcutta between April 29, 1954 and June 5, 1954, although no thermonuclear explosions were announced in the press. The alpha and gamma activity was not found to be significant, but  $\beta$  activity as shown in following table, shows a definite increase after May 15, indicating an explosion around May 11, though location could not be determined.

| Rainwater collected on                                                      | Radioactivity of the Rainwater |                     |                               |
|-----------------------------------------------------------------------------|--------------------------------|---------------------|-------------------------------|
|                                                                             | Radio-activity tested on       | Ratio to background | Counts/litre/min              |
| 29-4-54                                                                     | 29-4-54                        | 2.5                 | 240 $\pm$ 21                  |
| 15-5-54                                                                     | 18-5-54                        | 9                   | 320 $\pm$ 52                  |
| 20-5-54                                                                     | 25-5-54                        | 7                   | 1562 $\pm$ 35                 |
| 22-5-54                                                                     | 28-5-54                        | 7                   | 1452 $\pm$ 46                 |
| 1-6-54                                                                      | 7-6-54                         | 2.5                 | 200 $\pm$ 13                  |
| 4-6-54                                                                      | 7-6-54                         | 2.8                 | 1043 $\pm$ 60                 |
| 5-7-54                                                                      | 12-6-54                        | 1.2                 | very small                    |
| S7 <sup>1</sup> Dust collected from a plane coming from Djakarta on 11-4-54 |                                | 4                   | 121 $\pm$ 5<br>per gm per min |

Amounts in rainwater are too small to harm plant or animal life in India. Analysis of indicated half-lives gives clue to possible  $\text{Ce}^{141}$  content. (Same item as 6.5-339, May 1955, MAB.) *Subject Headings:* 1. Radioactive fallout 2. Radioactivity in rainwater 3. Atomic explosions 4. Calcutta India.—M.R.

## 7E-85

551.594.1

Clark, Herbert M., The occurrence of an unusually high-level radioactive rainout in the area of Troy, N. Y., *Science*, 119(3097):619-622, May 7, 1954. 4 figs., 5 tables, 7 refs. **DLC**—Thirty six hours after the Nevada test of April 25, 1953, an unusually heavy and violent thunderstorm brought relatively large amounts of debris to the ground in the Troy, New York area. Monitor readings of several mr/hr (1 in. above ground) one day after arrival were found at some locations and a hot spot of 120 mr/hr 2.1 days after arrival was found near a drain spout. Accumulated 10-week gamma dose, 55 mr. A sample of rain from a puddle gave  $270 \mu\text{m}$  c/ml at time of sampling 0.7 days after arrival. A sample of a leaf  $3.14 \text{ cm}^2$  in area gave  $3.9 \times 10^6$  d/m, corrected to arrival time, a similar paper sample,  $13.5 \times 10^6$  d/m. Values of the exponent in the decay law varied from 1.26 to 1.52. *Subject Headings:* 1. Radioactive rainout 2. Troy, N. Y.—R. J. List.

## 7E-86

551.594.14:551.578.1

\*Damon, Paul E. and Kuroda, P. K. (both, Dept. of Physics, Univ. of Arkansas, Fayetteville) On the natural radioactivity of rainfall. *American Geophysical Union, Transactions*, 35(2):208-216 April 1954. 4 figs., 4 tables, refs. **DLC**—Measurements by the authors of the natural radioactivity of rainwater are reported. The radioactivity varied from one to 60 millimicrocuries per liter of rainwater and was due primarily to RaB+C. The activities due to ThB were less than  $10^{-10}$  and  $10^{-11}$  c/l each, respectively. RaA is present in rainwater at the time it reaches the earth's surface. The mechanism for the accumulation of decay products in rainwater is discussed. The total activity (per unit area and time) increases toward the limiting value determined by the supply of RaA from Rn. An average atmospheric Rn concentration within the cloud system of approximately  $0.2 \times 10^{-13}$  c/l is sufficient to supply the rainwater with the observed radioactivity. The natural radioactivity of the atmosphere can be used as a tracer to study meteorological phenomena. (Same item as 5.9-312, Sept. 1954, MAB.) *Subject Headings:* 1. Radioactivity in rainwater 2. Rainwater analysis.—Authors' abstract.

## 7E-87

551.594.1

Fitzgerald, J. J.; Hurwitz, H., Jr. and Tonks, L., Methods for evaluating radiation hazard from a nuclear incident. U. S. Atomic Energy Commission, Report No. KAPL-1045, March 26 1954. 52 p. diagrs., eqs. **DLC**—Mathematical formulas are developed for evaluating hazards resulting from the dispersion of radioactivity in air, water and soil. The values expressed are

(1) dispersion of fission products in the cloud, (2) radius of cloud at origin of incident and (3) at various distances from the origin, (4) height to which the cloud will rise, (5) external and (6) internal beta and gamma dose received at various distances from origin, (7) dose from fall-out and rain-out from the fission-products cloud and (8) hazards from the contamination of water systems. *Subject Headings: 1. Radioactive diffusion 2. Radiation hazards. I. General Electric Company. Knolls Atomic Power Laboratory.—G.T.*

7E-88

551.594.14:551.510.42:662:539.1

Gabites, J. F. (*Met. Off., Wellington, N. Z.*). **Drift of radioactive dust from the British nuclear bomb tests in October 1953.** *New Zealand. Meteorological Office, Meteorological Office Note*, No. 10, 1954. [6 p.] 4 figs., 7 refs. **DWB.** Also in: *New Zealand Journal of Science and Technology*, Sec. B, 36(2):160-165, Sept. 1954. **DLC**—Radioactive dust detected at Wellington, N. Z., just 10 hrs and again 38 to 54 hrs after the Woomera, S. Australia, (Oct. 1953) atomic test explosion, should not have been carried by direct air trajectories but must have followed isentropic surfaces starting at >20,000 ft, and have fallen out over New Zealand at a rate much faster than theoretically possible. The calculations and charts showing trajectories are included. Vertical cross section shows possible diffusion pattern from 3200 isentropic surface over Woomera to the surface at Wellington. How the dust got to the 320° isotherm when the cloud top was observed at 10,000 ft over Woomera, and how the first wave of dust got to N. Z. in 30 hrs is still a mystery. (*Same item as 6.8-339, Aug. 1955, M.A.B.*) *Subject Headings: 1. Radioactive fallout 2. Isentropic dust trajectories 3. Woomera, Australia 4. Wellington, New Zealand.—M.R.*

7E-89

551.594.14:551.578.41

Garrigue, Hubert, **Recherches sur la radioactivité de l'atmosphère.** [Investigation of the radioactivity in the atmosphere.] *Académie des Sciences, Paris, Comptes Rendus*, 238(21):2074-2075, May 24, 1954. ref. **DWB**—Systematic sampling of air at medium flying levels by a new apparatus installed on the S.A.L.S. flying laboratory, was begun on April 11, 1954. On April 24 at 2800 m (9500 ft) over France traces of radioactive dust were obtained over a long period. The synoptic condition (Greenland anticyclone following an Atlantic cyclone and abundant snowfall in mountains) led to the expectation of radioactivity in the snow obtained at Puy de Dôme (1465 m) but the radioactivity over 10 days was only 1/10 the maximum thus far observed in this manner. Unanalyzed samples obtained from lighter snowfall may give different results. (*Same item as 6.5-341, May 1955, M.A.B.*) *Subject Headings: 1. Airplane sampling of radioactivity 2. Radioactivity in snow 3. Air sampling and analysis 4. Puy de Dôme, France.—M.R.*

7E-90

551.594.14:546.296

Garrigue, Hubert, **Anomalies dans la radioactivité naturelle de l'air libre.** [Anomalies of natural radioactivity in the free atmosphere.] *Académie des Sciences, Paris, Comptes Rendus*, 239(13):776-777, Sept. 27, 1954. **DWB**—Large anomalies of atmospheric radon content observed in 1948 and 1950 in two different regions [East Pyrenees and Puy de Dôme, France] are tentatively attributed to large-scale shifts of the subsoil. *Subject Headings: 1. Radioactivity in the atmosphere 2. Radon anomalies 3. France.—Trans. of author's abstract.*

7E-91

551.594.14:551.515.3

Harris, D. Lee (*U. S. W. B., Wash., D. C.*). **Effects of atomic explosions on the frequency of tornadoes in the United States.** *Monthly Weather Review*, Wash., D. C., 82(12):360-369, Dec. 1954. 12 figs., 3 tables, 5 refs. **DWB**—The increase in tornadoes reported in the United States during the past few years is ascribed to better reporting procedures rather than the presence of atomic debris. Maps showing the distribution of fallout in the United States during the first and second halves of May, 1953, are given. *Subject Headings: 1. Atomic explosion effects on weather 2. Tornado frequencies.—R. J. List.*

7E-92

551.594.14

Ishibashi, M.; Shigematsu, T.; Ishida, T. et al., **Radiochemical analysis of the Bikini ashes.** *Kyoto. Univ. Institute for Chemical Research, Bulletin, (Supplementary issue)*, Nov. 1954. p. 39-59. 33 figs., 10 refs. **DLC**—Two samples of particles from the "Fukuryu Maru" gave the following decay curves for a period of 81 days following May 4, the 64th day after the burst:  $A_t = A_0 e^{-1.17 \pm 0.02}$  for white ashes;  $A_t = A_0 e^{-1.24 \pm 0.06}$  for dark grey ashes. Radiochemical analysis yielded  $\text{Ca}^{45}$ ,  $\text{Sr}^{89}$ ,  $\text{Y}^{91}$ ,  $\text{Zr}^{95}$ ,  $\text{Nb}^{95}$ ,  $\text{Ru}^{103}$ ,  $\text{Rh}^{103m}$ ,  $\text{Ru}^{106}$ ,  $\text{Te}^{129}$ ,  $\text{I}^{131}$ ,  $\text{Ba}^{140}$ ,  $\text{La}^{140}$ ,  $\text{Ce}^{144}$ ,  $\text{Pr}^{144}$ , and  $\text{U}^{237}$  in Bikini ashes. Rain which fell on Kyoto on May 16, 1954, showed activity of about  $\mu\text{c/l}$ . Analysis of the rain showed  $\text{Sr}^{89}$ ,  $\text{Zr}^{95}$ ,  $\text{Nb}^{95}$ ,  $\text{Ba}^{140}$ , and rare earth. *Subject Headings: 1. Radioactive fallout composition. I. Okada, S. II. Nishi, T. III. Takahashi, H. IV. Matsumoto, C. V. Shimizu, S. VII. Hirayama, F. VIII. Okamoto, S.—R. J. List.*

7E-93

551.578.7:551.594.14

Jaffe, Gilbert; Wittmann, Walter and Bates, Charles C. (all, U. S. Navy. *Hydrographic Office, Wash., D. C.*), **Radioactive hailstones in the District of Columbia area, May 26, 1953.** *American Meteorological Society, Bulletin*, 35(6):245-249, June 1954. 5 figs., ref. **MH-BH**—At about 2000 on May 26, 1953 the District of Columbia area experienced a hailstorm in which individual hailstones ranged up to the size of tennis balls. Determinations of the radioactive count of the water content of these hailstones and of roof gravels, indicate that considerable material was brought to earth by the hailstorm from the explosion of the atomic cannon shell 29 hrs earlier some 2000 airline miles away in Nevada. The air-flow pattern at upper levels proves to have been around a high-pressure ridge located between the two sites. Such a pattern permitted the arrival of such radioactive material over the District of Columbia area within the time noted. (Same item as 6.2-276, Feb. 1955, MAB.) **Subject Headings:** 1. Radioactivity in hailstones 2. Atomic explosions 3. Upper air flow patterns 4. Washington, D. C.—Authors' abstract.

7E-94

551.594.14:551.4

Kikkawa, Kyōzō, **Study on radioactive spring.** *Japanese Journal of Geophysics*, Tokyo, 1(1):1-25, May 1954. 8 figs., tables, 14 refs., 14 eqs. **DWB**—A thorough theoretical and empirical study of diurnal and seasonal effects on meteorological variables on radon content of spring water, based on data obtained nearly every day from Dec. 23, 1949 to Jan. 2, 1951 at Zuihozi spring in Arima, Hyogo Prefecture, Japan. Tabulated data include amount of discharge, temperature of spring, air temperature, Rn content and Cl content. Relationships between these elements are shown by scatter diagrams or curves. Rainfall produces several kinds of variation in Rn content; heavy rains in some cases increase the discharge thus reducing the Rn content which later comes back to normal, at other times rain increases the content which then decreases to normal and sometimes little change occurs. Unusual variations may be accredited to temperature, pressure, freezing ground or snow cover. Conclusion is that radon exhalation from soil air and dilution by excessive rainwater are the controlling factors. **Subject Headings:** 1. Radon content of soil air 2. Radon content of springs 3. Meteorological effects on radioactive springs 4. Arima, Japan.—M.R.

7E-95

551.594.14

Kikuchi, Takehiko; Akagi, Hiroaki; Goto, Hiroshi et al., **Radioautographic studies of the radioactive ashes obtained from the No. 5 Fukuryu Maru.** *Kyoto. Univ. Institute for Chemical Research, Bulletin*, (Supplementary issue):12-17, Nov. 1954. 4 figs., table, ref. **DLC**—Made radioautographic studies of particles collected on "Fukuryu Maru," using X-ray film, radioautographic stripping plates and plates for alpha emitters. Found no correlation between radioactivity and size of particles. As a rule, there was parallelism between beta and alpha particles. Some particles showed more alpha than beta particles and in some alpha tracks seemed to be emitted from one corner of the particle. Distribution of radioactivity in each particle not uniform. Microphotographs. **Subject Headings:** 1. Radioactive fallout analysis. I. Wakisaka, Gyoichi.—R. J. List.

7E-96

551.594.14

Kikuchi, Takehiko; Wakisaka, Gyoichi; Akagi, Hiroaki et al., **Studies on the properties and size of the radioactive ashes obtained from the No. 5 Fukuryu Maru.** *Kyoto. Univ. Institute for Chemical Research, Bulletin*, (Supplementary issue):4-11, Nov. 1954. 5 figs., 5 tables, ref. **DLC**—Examined dimensions and radioactivity of 200 particles collected by crew member of "Fukuryu Maru" and preserved by wrapping in paper. Under microscope there was some surface unevenness but as a rule particles looked like semi-transparent glass. Two to four black, spot-like grains about  $2-3\mu$  seen on particles. Diameter of particles  $100-400\mu$ , mean 257. Ratio of minimum of maximum diameter 0.3 to 1.0, mean 0.74. No direct correlation of particle size and radioactivity. Particles with black spots appeared to show strong radioactivity. On May 16, 1954, 1.0 mg showed 4218 c/m ( $0.4\mu\text{C}$  of  $\text{Co}^{60}$  showed 7475 c/m under same counting conditions). Microphotographs. **Subject Headings:** 1. Radioactive fallout analysis. I. Goto, Hiroshi.—R. J. List.

7E-97

551.594.14:627.1

Kilcawley, E. J.; Clark, H. M.; Ehrlich, H. L. et al., **Measurement of radioactive fallout in reservoirs.** *American Water Works Association, Journal*, 46(11):1101-1111, Nov. 1954. 5 figs., table, 3 refs. **DLC**—An extensive survey of radioactivity in the Troy, Albany, Schenectady water supply system was made in an investigation following the heavy rainout which occurred in that area on April 26, 1953. Samples of water, soil, algae, plants, etc. were measured for radioactivity. Decay rates, effectiveness of filtration, rate of disappearance, etc. were studied. The general contamination of the ground at arrival time was  $1\mu\text{C}/\text{ft}^2$ . Surface water on RPI campus had  $2.7 \times 10^2 \mu\text{C}/\text{ml}$ . Measurements were also made for subsequent bursts. Corrected to time of rainout, highest rainwater activity was  $25.0 \mu\text{C}/\text{ml}$  on June 9, 1953. Highest stream samples  $0.10-1.3 \mu\text{C}/\text{ml}$ . Alpha activity of same samples was also investigated. **Subject Headings:** 1. Radio-

activity in reservoirs 2. Radioactive rainout 3. New York. I. Kelleher, W. S. II. Schultz, H. E. Krascella, N. L.—R. J. List.

7E-98 551.594.14

\*Kyoto. University. Institute for Chemical Research, **Radioactive dust from the nuclear fission. Its Bulletin, Supplementary Issue**, Nov. 1954. 133 p. figs., tables, refs. DLC—This extensive factual account contains 14 detailed reports on measurements made in connection with radioactive contamination of the Japanese fishing boat "Fukuryu Maru." Data on size and properties of fallout particles and on radioactivity of ashes, various objects on the ship, fish, etc., are presented and discussed. Five papers are studies on the metabolism and various biological effects of fission products on the basis of experiments undertaken on animals with radioactive ashes. Microbarographic oscillations produced by H-bomb explosions are also reported. All papers are in English. Six of the reports (those considered to be of particular interest from a meteorological point of view) have been abstracted separately (see items 7E-92, -95, -96, -111, -115 and -120). **Subject Headings:** 1. Radioactive fallout analysis 2. Biological effects of radioactivity. I. Kyoto. Univ. Radioisotope Research Committee.—G.T.

7E-99 551.594.14:551.510.42

List, R. J., On the transport of atomic debris in the atmosphere. *American Meteorological Society, Bulletin*, 35(7):315-325, Sept. 1954. 13 figs., table, 3 refs. DWB. Also in: *Air Pollution Control Association, Pittsburgh, Journal*, 5:153-156, 183, 1955. MH-BH—Collections of radioactive debris were made daily at 120 Weather Bureau stations throughout the U. S. during the atomic test series in Nevada in the Spring of 1952. The measuring techniques employed and the meteorological factors involved in the transport and deposition of debris are discussed. Several examples of the relation of computed meteorological trajectories to actual observations of debris are given. (Same item as 6.5-342, May 1955, MAB.) **Subject Headings:** 1. Radioactivity measurement techniques 2. Radioactive fallout propagation 3. United States.—Author's abstract.

7E-100 551.594.14:662:539.1

Martin, Charles-Noël, **Sur les effets cumulatifs provoqués par les explosions thermonucléaires à la surface du globe.** [On the cumulative effects of thermonuclear explosions on the surface of the globe.] *Académie des Sciences, Paris, Comptes Rendus*, 239(20):1287-1289, Nov. 15, 1954. refs. WB. Review in: *Time*, 64(25):66-67, 1954. port. DLC—Possible chemical, climatic, radioactive and genetic effects of thermonuclear explosions are discussed. The following effects are suggested as being measurable: 1) variations in pH content of rain water (limited in space and time), 2) a marked increase of atmospheric C 14, 3) a (probably weak) increase of secondary cosmic radiation at sea level, 4) decrease of solar radiation intensity, 5) world-wide rainfall anomalies, 6) changes in the absorption band of nitric acid in the airglow spectrum and 7) presence of a large quantity of radioactive elements in the atmosphere. Some of these phenomena are irreversible and will become harmful after a certain threshold is reached, possibly with less than a hundred explosions. (Same item as 6.8-343, Aug. 1955, MAB.) **Subject Headings:** 1. Thermonuclear explosion effects 2. Radioactive fallout.—G.T.

7E-101 551.594.14:662.2:539.16

Meteorological Society of Japan, **Statement concerning hydrogen bomb of the Met. Soc. Jap.** *Journal*, 32(5/6):181, May/June 1954. MH-BH—According to this statement issued by the Meteorological Society of Japan on the occasion of injuries done to Japanese fishermen by H-bomb tests in the Bikini Atoll, meteorological factors may combine to extend harmful effects of thermonuclear explosions through the following mechanisms: (1) dispersion of radioactive ashes all over the world, (2) persistent large-scale contamination of the atmosphere affecting the amount of insolation and leading to weather disasters and (3) contamination of rain and sea water, disastrous for agriculture and fishing. In view of these possibilities, the Society demands discontinuation of experiments involving nuclear weapons, international control of the peaceful use of atomic energy and publication of data on the harmful effects which may follow H-bomb explosions. **Subject Headings:** 1. Atomic explosion effects 2. Radioactive fallout.—G.T.

7E-102 551.578.8:551.594.14

Miyake, Y., **The artificial radioactivity in rain water observed in Japan from May to August, 1954.** *Papers in Meteorology and Geophysics*, Tokyo, 5(2):173-177, Sept. 1954. 11 figs., 2 refs. H-BH—Observations on radioactivity of rainwater are being conducted at 10 university laboratories in Japan (Kagoshima, Hiroshima, Osaka, Kyoto, Nagoya, Shizuoka, Tokyo, Kanazawa, Niigata and Hiroaki, and the C.M.O. in Tokyo, etc.). Lat. and long. and names of research workers at each are tabulated. Results obtained at these places during April, May and June 1954 and trajectories of air over Pacific in May 1954 are shown on graphs and charts. High values of  $0.5 \times 10^{-6}$

curled were reported by T. Shupat at Kyoto Univ. on May 19, and 0.188  $\mu\text{m}^{-2}$  at Tokyo on 17, 1954. Several laboratories reported such fission products as  $\text{Ba}^{140}$ ,  $\text{La}^{140}$ ,  $\text{Sr}^{90}$ ,  $\text{Zr}^{90}$ ,  $\text{Nb}^{93}$ ,  $\text{I}^{131}$ ,  $\text{I}^{134}$ ,  $\text{I}^{135}$ ,  $\text{I}^{136}$ ,  $\text{I}^{137}$ ,  $\text{I}^{138}$ ,  $\text{I}^{139}$ ,  $\text{I}^{140}$ , and  $\text{Np}^{239}$  and some rare earth elements. Energy of  $\beta$  rays and  $\gamma$  rays were also measured in some instances. Bikini explosion of May 5 seems to be responsible for most of the high values reported. *Subject Headings*: 1. Radioactive fallout composition. 2. Bikini H-bomb tests, 1954. 3. Japan.—M. R.

7E-103

551.564.14:62.2

Meek, Jules Salvador. La folie des hommes. [Human folly.] Paris, Robert Laffont, 1955. 285 p., 41 figs., 11 tables. Translation into English by Edward Hyams as Human folly: to die or perish? With an intro. by Albert Einstein. London, Warner Books, 1955. 222 p., 41 figs., 11 tables. DLC—This book is an appeal for peaceful settlement of world problems in view of horrors of atomic warfare. In Ch. 5 the effects of thermonuclear explosions are discussed: chemical, thermal and immediate and residual radiation effects. Estimates of direct and indirect A and H-bomb effects are derived from facts known about atomic explosions of the past. *Subject Headings*: 1. Thermonuclear explosion effects. I. Hyams, Edward. II. Einstein, Albert. —C. T.

7E-104

551.594.14:551.5

\*Nader, J. S., Goldin, A. S. and Sever, L. R. Radioactive fallout in Cincinnati area. *American Water Works Association Journal*, 48:11-1196-1198, Nov. 1954, fig. 2, tables 3 and 4. DLC—Precipitation in the Cincinnati area was measured for suspended and soluble radioactivity on March 1955 to March 1954. Background level in precipitation was 0.03 to 0.08  $\mu\text{Ci}/\text{ml}$ . Maximum concentration on April 28, 1955, 304  $\mu\text{Ci}/\text{ml}$ , 500  $\mu\text{Ci}/\text{ml}$  corrected for decay. Maximum fallout from a single run on May 22, 1955, 1.55 in. containing 85  $\mu\text{Ci}/\text{ml}$  giving 8.75 curies  $\text{sq. mi.}$  Soluble activity averaged 60-80% of total before and after tests, fell to 50% during tests. Samples from creeks and tap water show most of activity removed by natural purification. Accumulated and decayed radioactivity on June 10 and Dec. 10, 1955, was 2.4 and 0.35 curies  $\text{sq. mi.}$ , respectively. *Subject Headings*: 1. Radioactive fallout data. 2. Radioactivity in precipitation. 3. Cincinnati, Ohio.—R. J. List.

7E-105

551.583:662.2:3

Nardone, Antonio. Le esplosioni atomiche possono influire sulle variazioni atmosferiche? [Atomic blasts affect weather conditions?] *Ciampino Interairport*, Rome, 6:10:16-17, Oct. 1954, 2 plates. MH-BE—The author categorically rejects the suggestion that A-bomb blasts may be related to the unusual weather conditions lately observed. Energies released by such explosions are negligible compared to those involved in dynamic processes of the atmosphere. Unusual wind frequently occurred in past decades and centuries. Possible extraneous causes are: solar activity, magnetic storms, melting of polar ice. *Subject Headings*: 1. Atomic explosion effects on weather. 2. Climatic variations.—C. T.

7E-106

551.546

Nishimaki, Yasushi. Bikini ash. *Atomic Science Journal*, London, 4:2:91-109, Nov. 1954, 1 table, plate. DLC—Results of measurements of radioactivity from thermonuclear explosions at Bikini testing ground, especially the one on March 1, 1954, are reported. The measurements showed considerable radioactive contamination of the Faguroi Maru, and other fishing boats, sea water, rain, vegetables, fish and drinking water. Contaminated items from the Faguroi Maru are described. *Subject Headings*: 1. Radioactive fallout. 2. Bikini H-bomb tests, 1954.—C. T.

7E-107

551.594

\*Pohl, Eugen and Föld-Rösch, Johannes. Radioaktive Luftmessungen im Raum von Badgassau und Bockstein. [Measurement of radioactivity in the vicinity of Badgassau and Bockstein.] *Abhandlungen der Wissenschaften, Klasse Naturwissenschaften, Abt. 2*, 195:5-7, 4 pls., 1954. 4 figs., 11 tables, 10 text-figs. DLC—In Badgassau and Bockstein a series of samples were tested for radon content during the period 1949-1952. The samples were taken outside in various rooms in health establishments and in a mine shaft. Particularly remarkable among the results is the high average radon content of the air in Bockstein (21  $\mu\text{Ci}/\text{m}^3$ ), the highest value of 11  $\mu\text{Ci}/\text{m}^3$  after was found in the Pochkar shaft. *Subject Headings*: 1. Radon content of atmosphere. 2. Salzburg Province, Austria.—Trans. of German geologists.

7E-108

551.504

Radioactive gages show snow water. *Electrical World*, San Francisco, 112:3:48-50, Mar. 1954, illus. DLC—Thermometering system that uses radioactive snow gages to bring daily report water content of remote snow peaks into system operator's office in use in California by the

Engineers; gage consists of heavy lead tube planted in vertical position flush with ground; in lower end of tube two units of cobalt 60 have sufficient strength to penetrate and measure snow depth equivalent to 55 in. of water. *Subject Headings:* 1. Telemetering systems 2. Radioactive snow gages 3. Water content of snow pack.—*Engineering Index Service, No. 54—13580.*

7E-109

551.578.1:551.594.14

Rain three weeks old. *Science News Letter*, 66(13):197, Sept. 25, 1954. DLC—The measurement of tritium radioactivity (half-life 12.5 years) provides a possibility of measuring the age of the water due to its contact with higher atmospheric layers, where tritium is formed by the action of cosmic rays. Rain on the average has three-week "old" water, deep water wells produce 50-year old water. Rain water mixes with ocean water down to 150 ft. (Same item as 7.4-236, April 1956, MAB.) *Subject Headings:* 1. Tritium measurement 2. Radioactivity in rainwater. I. Libby, W. F.—A.A.

7E-110

551.510.42:539.16

Schumann, G., Wie gross ist die künstliche Radioaktivität der Luft? [How great is the artificial radioactivity of the air?] *Umschau*, 54(9):267-268, May 1, 1954. 2 figs. DWB—The half-life of the different products of an atom bomb explosion enables the date of the explosion to be calculated. The concentration of fission products at Königstuhl near Heidelberg rose from nearly zero to  $2.5 \times 10^{-12}$  c.m.<sup>3</sup> on May 14, 1953, following explosion on May 8, but this amount is far too small to have any deleterious effects. (Same item as 5.9-104, Sept. 1954, MAB.) *Subject Headings:* 1. Radioactivity in the atmosphere 2. Atomic explosions 3. Königstuhl, Germany.—C.E.P.B.

7E-111

551.594.14

Shimizu, Sakae; Akagi, Hiroaki; Goto, Hiroshi et al., Survey of the radioactive contamination of the No. 5 Fukuryu Maru. *Kyoto. Univ. Institute for Chemical Research, Bulletin, Supplementary issue:* 1-3, Nov. 1954. fig., 2 tables, 4 refs. DLC—Reports results of survey of "Fukuryu Maru" with radiation monitor on March 19, April 21, and May 16, 1954. On March 19, highest contamination ( $\beta + \gamma$ ) found on wet rope on upper deck, 80-150 mr/hr. Found 50-70 mr/hr in quarter crew space. Later surveys showed decrease in contamination greater than predicted by fission-product decay law due to cleaning by rain. Using March 19 data and assuming various coefficients for fission-product decay law, it is estimated that the total  $\gamma$  dosage to the crew during their exposure from March 1 to 14 averaged from 200 to 550 r. *Subject Headings:* 1. Radioactive fallout analysis 2. Radioactive dosage. I. Okamoto, Sunao II. Ishida, Takanobu III. Kawai, Yagoro.—R. J. List.

7E-112

551.594.14:551.510.42

\*Singer, Irving A., Comparison of computed and measured ground-level dose rates from radioargon emitted by the Brookhaven reactor stack. *U. S. Brookhaven National Laboratory, BNL*, 292, T-49, May 1954. 42 p. 30 figs., 8 tables+extensive tables in appendixes, 16 refs., eqs. DWB—The nuclear reactor at Brookhaven National Laboratory is air-cooled and consequently measurable amounts of radioargon ( $A^{41}$ ) are emitted into the atmosphere. By a combination of theory and experimental data obtained from oil fog concentration measurements, an approximate solution to the problem of determining dose rates from the radioargon under various meteorological conditions has been obtained. The purpose of the paper is to compare the calculated values with measured weekly and hourly values of  $A^{41}$  at eight Health Physics stations. (Same item as 6.5-92, May 1955, MAB.) *Subject Headings:* 1. Radioargon concentration 2. Diffusion equations 3. Radioactive effluents 4. Brookhaven, N. Y.—*Author's abstract.*

7E-113

662.2:539.1:551.515.539

Steinhauser, Ferdinand, Atomenergie und Weltwetter. [Atomic energy and world weather.] *Universum*, Vienna, 9(16):481-488, Aug. 2, 1954. 3 figs., cover photo. Also his: *Atombombenexplosionen und Wettergeschehen*. [Atom bomb explosions and weather phenomena.] *Universitas*, Stuttgart, 9(11):1189-1196, Nov. 1954. Abstracted from reprint. DWB—Atomic blasts will not affect large-scale weather development. This is supported by general data showing that: 1) the order of magnitude of energy released in thermonuclear explosions is insignificant compared with that involved in large-scale atmospheric processes, 2) the energy supply from explosions is instantaneous and therefore cannot influence a continuous process like weather development, 3) the world-wide rainfall amount cannot be permanently increased by a supply of condensation nuclei (supposedly provided by atomic explosions) because (a) there are usually enough condensation nuclei present in the atmosphere, (b) the mere presence of sufficient condensation nuclei does not produce precipitation and (c) increased precipitation would have to be balanced by increased evaporation; which does not result from atomic explosions. As to planned weather modification, the author believes that this could be achieved by slow rather than explosive release of thermonuclear

energy. He leaves open the question whether such a weather modification plan would be practical and desirable. (*Same item as 6.7-178, July 1955, MAB.*) *Subject Headings:* 1. Atomic explosion effects on weather 2. Grosswetterlagen 3. Weather modification 4. Condensation nuclei.—G.T.

7E-114

551.594.14:551.510.42

Stern, Curt (*Calif. Univ. Berkeley*), **One scientist speaks up.** *Science*, 120(3131):5A, Dec. 31, 1954. DWB—Possible cumulative effects of radioactive particles introduced into the atmosphere by thermonuclear explosions, even when only experimental, are discussed in the light of Dr. ALBERT SCHWEITZER's appeal to scientists to express themselves freely for the benefit of mankind. *Subject Headings:* 1. Radioactive pollution of atmosphere 2. Radioactive fallout. I. Schweitzer, Albert.—M.R.

7E-115

551.594.14

Suito, Eiji; Takiyama, Kazuyoshi and Uyeda, Natsu, **Colloid morphological and crystalline studies of "Bikini dust" fallen on the No. 5 Fukuryu Maru by electron microscopy and diffraction methods.** *Kyoto. Univ. Institute for Chemical Research, Bulletin, Supplementary issue:* 18-28, Nov. 1954. 3 figs., 24 photos, table, 4 refs. DLC—Studies particles which fell on the "Fukuryu Maru" by microscope and X-ray analysis. Granules averaged 0.3 mm in size with specific gravity of 2.42, composed of cubic and spindle-shaped unit particles of 0.1~3 $\mu$ . Particles were calcite, whereas coral reef is aragonite, suggesting that the coral reef was evaporated, then recrystallized to calcite and aggregates of the unit particles fell. Microphotographs included. *Subject Headings:* 1. Radioactive fallout analysis.—R. J. List.

7E-116

551.554:539

Teichmann, Horst, **Wettereinfluss von Atomexplosionen als Störung periodischer Strömungen in der Stratosphäre.** [Weather influence of atomic explosions as a disturbance of periodic currents in the stratosphere.] *Naturwissenschaften*, 41(21):498, Nov. 1954. DWB—Suggests that atomic explosions, reaching into the stratosphere, cause small disturbances which may be magnified by the periodic oscillations of the streamlines there. (*Same item as 6.5-202, May 1955, MAB.*) *Subject Headings:* 1. Atomic explosion effects on weather 2. Stratospheric winds.—C.E.P.B.

7E-117

551.594.14(02)

\*U. S. Air Weather Service, **Radioactive fall-out plots.** Its *Air Weather Service Manual* 105-33. Oct. 15, 1954. 22 p. 15 figs (incl. tables) "Supersedes its AWS Manual 105-33, June 2, 1952." DWB—A detailed manual outlining procedures and illustrating methods for determining areas which only become contaminated with radioactive particles within 6 hrs after an explosion of a fission or a fusion bomb. Equipment, wind vector diagrams, ground fallout plot, and transmission of ground fallout data, constitute the major headings. Air bursts do not, as a rule, provide much fallout hazard. Surface bursts kick up a lot of dust which is carried down wind. Subsurface bursts carry into the atmosphere a tremendous amount of material: distance depends on (1) cloud height, (2) size of particles and (3) mean wind speed. Heights of 60,000 ft are estimated as the ceiling for small particles. Decay, rain washing out, and vertical currents are not considered in procedure outlined. Forecasting degree of contamination is not considered either. (*Same item as 7.4-294, April 1956, MAB.*) *Subject Headings:* 1. Radioactive fallout calculation manuals.—M.R.

7E-118

551.594.14:355

U. S. Engineer School, Fort Belvoir, Va., **Atomic weapons reference data.** March 1954. 29 p. 13 figs., 6 tables. DLC—The purpose of this pamphlet is to provide students of the Engineer School with general unclassified data concerning nuclear weapon effects sufficiently accurate to serve as reference material for the practical solution of such problems as may be engendered by atomic warfare considerations in the field. The tables and diagrams presented show blast, thermal and radiation effects of air, surface and underground bursts on troops and materials as functions of energy released, distance from explosion and wind direction. A diagram showing gamma ray attenuation in various materials is included. *Subject Headings:* 1. Atomic explosion effects 2. Military meteorology.—G.T.

7E-119

551.553.8 551.557:551.542.1

Weiller, A. R., **Les tempêtes artificielles sont-elles pour demain?** [Will artificial gales be produced tomorrow?] *La Météorologie*, Paris, 4th Ser., No. 34:127-136, April/June 1954. 12 figs., ref., 23 eqs. English and Spanish summaries p. 127. MH-BH—In this theoretical analysis of the dynamics of gradient winds, it is shown how strong winds might be induced in certain synoptic situations by sudden changes in the pressure gradient. Such changes could be caused by atomic explosions. After the thermonuclear explosions on Eniwetok in March 1954 radioactive fallout was reported in unexpected areas; the explosion was found to be twice as powerful as anticipated.

These facts indicate that the baric field may have been disturbed and strong winds produced. (Same as 6.8-256, Aug. 1955, *MAB.*) *Subject Headings:* 1. Artificial winds 2. Gradient winds 3. Atomic explosion effects on weather.—*G.T.*

7E-120

551.541:623.45

\*Yamamoto, Ryozauro, *Microbarographic oscillations produced by the explosions of hydrogen-bombs.* *Kyoto Univ. Institute for Chemical Research, Bulletin, Supplementary issue:*120-133, Nov. 1954. 8 figs., 4 tables, 5 refs. **DLC**—Reprint issued as: *Kyoto Univ. Meteorological Research Institute, Meteorological Notes*, Ser. 2, No. 1, Nov. 1954. Shorter version in: *Weather*, 10(10):321-325, Oct. 1955. **DWB**—Microbarographic records obtained at tripartite storm microbarograph station at Shionomisaki in S. Central Japan on March 27, 1954, showed speeds similar to those from Krakatoa and Great Siberian meteor (1908) which speeds approach the speed of sound whereas those from storms travel at  $\frac{1}{10}$  to  $\frac{1}{2}$  that speed. Microbarograph records calculated at 30 other places in Japan also showed high velocities, and on Nov. 1, 1952, March 1, 1954, April 26, 1954 and May 5, 1954 showed similar characteristics. Map shows stations whose location, observers and instruments are described or listed. (For fuller abstract, see 7.2-170, Feb. 1956, *MAB.*) *Subject Headings:* 1. Microbarograph oscillations 2. Explosion waves 3. Bikini H-bomb tests, 1954 4. Shionomisaki, Japan.—*M.R.*

1955

7E-121

551.594.14

Abribat, Marcel; Pouradier, Jacques and Venet, Anne-Marie, *Évolution de la radioactivité de l'atmosphère de la région parisienne.* [Evolution of atmospheric radioactivity in the Paris region.] *Académie des Sciences, Paris, Comptes Rendus*, 240 (24):2310-2312, June 13, 1955. 2 figs., 2 refs. **DWB**—Atmospheric radioactivity has been measured in Paris since November 1951. Maximum  $\beta$  activities measured during the three years were 3310 cpm for 1952, 1740 for 1953 and 104 for 1954 (measured in dust filtered out of 7000 cu m of air). The considerable decrease in  $\beta$  activity in 1954 is attributed to the fact that in that year atomic explosions took place in the Southern Hemisphere rather than in Nevada as in 1952 and 1953. It is pointed out, however, that radioactivity following experiments in Russia was also weaker in 1954 than in 1953. Similar results were obtained with the measurement of radioactivity in rain water. *Subject Headings:* 1. Radioactivity in the atmosphere 2. Paris, France.—*G.T.*

7E-122

551.594.14

Aliverti, Giuseppina (*Dir. Gabinetto di Met. ed Oceanog., Ist. Univ. Navale di Napoli*), *Le esperienze atomiche e la radioattività dell'aria.* [Atomic tests and radioactivity of the air.] *Geofisica e Meteorologia*, Genoa, 3(1,2):4, Jan./April 1955. **DWB**—A nonquantitative discussion of the natural and artificial radioactivity (of several types) in the atmosphere and the possible cumulative effects of effluents from reactors and bomb explosions. *Subject Heading:* 1. Radioactivity in the atmosphere.—*M.R.*

7E-123

526:551.501.9

American Geophysical Union, Special Committee on the Geophysical and Geological Study of Continents, [Report of] the Committee, 1952-1954. George P. Woollard, chairman. *American Geophysical Union, Transactions*, 36(4):695-708, Aug. 1955. 9 figs., 2 tables. **DWB**—Extensive report on seismic, blast, gravity, submarine gravity, radioactive dating, geothermal, magnetic, geoelectrical and tectonic studies, accompanied by data, maps showing worldwide and U. S. networks and coverage, earthquake epicenters, etc. *Subject Headings:* 1. Geodesy networks 2. Continental geophysics. I. Woollard, George P.—*M.R.*

7E-124

662.2:539.1:612.6

Andrews, Howard L. (*Natl. Cancer Inst.*), *Radioactive fallout from bomb clouds.* *Science*, Wash., D. C., 122(3167):453-456, Sept. 9, 1955. table, 5 refs., eqs. **DLC, DWB**—The author describes the procedure of evaluating meteorological conditions preceding an atomic detonation and discusses the mechanism of formation of fallout, its biological effects and the nature of and degree of the radiation hazard attributable to fallout. *Subject Headings:* 1. Radioactive fallout 2. Biological effects of radioactivity.—*I.L.D.*

7E-125

551.594.14:662.2:539.1 551.590.21

Arakawa, Akio; Fujita, T.; Ito, H. et al., *Climatic abnormalities as related to the explosions of volcano and hydrogen-bomb.* *Geophysical Magazine*, Tokyo, 26(3):231-255, March 1955. 16 figs., 4 tables, 12 refs., eqs. **MH-BH**—A statistical and synoptic study of violent volcanic eruptions, sunspot minima and cool summers in northern Japan reveals a poor relationship between sunspot activity and cool summers (1755-1954), a significant relation between volcanic eruptions and

cool summers in northern Japan, and no significant relation between sunspot activity and volcanic eruptions. It is thought that the volcanic eruptions cause blocking action the next June, and consequent lowering of hemispheric temperature. The possible contamination of the stratosphere in a manner similar to that produced by volcanic eruption and a southward deviation of the jet summer are thought to be possible consequences of the H-bomb explosions such as occurred in the spring of 1954. *Subject Headings:* 1. Abnormal summer, 1954 2. Volcanic influences 3. Sunspot effects on weather 4. Thermonuclear explosion effects 5. Japan.—M.R.

## 7E-126

551.594.1

Arnold, James R. and Al-Salih, H. Ali, Beryllium-7 produced by cosmic rays. *Science* 121(3144):451-453, April 1, 1955. 3 figs., table, refs. DLC—It was expected that star production in nitrogen and oxygen would produce  $\text{Be}^7$  and that this would eventually reach the earth in rain water. A series of samples of rain water from Chicago and Lafayette were treated to concentrate the activity and various tests showed that this was due to  $\text{Be}^7$ ; further, no change in level was detected after nuclear weapon tests and so the source was cosmic-rays. At Chicago  $6 \times 10^6$  atoms per  $\text{cm}^2$  are received in a year at the earth's surface. It appears possible to use this isotope to obtain data on processes of air movement in the troposphere and lower stratosphere. *Subject Headings:* 1. Cosmic ray effects 2. Radioactivity in rainwater 3. Isotope content of air.—*Physics Abstracts*, No. 6657, 1955.

## 7E-127

546.79:551.46

†Arrhenius, Gustaf (*Scripps Inst. of Oceanography*) and Goldberg, Edward D. (C.I.T., Pasadena Calif.), Distribution of radioactivity in pelagic clays. *Tellus*, Stockholm, 7(2):226-231, May 1955. 3 figs., 5 tables, 13 refs. DLC—An attempt is made to study the localization of radioelements in different mineral phases of pelagic clay sediments. The results so far obtained indicate that the ionium supported radium is redistributed by diffusion through the interstitial solution and that the authigenic zeolite phillipsite plays an important role as a scavenger of radioelements within the deposit. The mechanism of transfer of radioelements from the ocean to pelagic deposits is discussed and points of uncertainty in the interpretation of the distribution of gross beta-activity are indicated. *Subject Headings:* 1. Radioactivity in marine sediments 2. Radioactive dating methods 3. Marine sediments.—*Authors' abstract*.

## 7E-128

551.5:662.2:539.1

Atomic explosions and the weather. *Journal of Scientific and Industrial Research*, Sec. A, New Delhi, 14(7):344, July 1955. 2 refs. DWB, DLC—Possible effect of the enormous energy release resulting from explosions of thermonuclear bombs in the Pacific on changes of atmospheric conditions (thereby modifying the weather) are discussed and analyzed as to the energy effect, the cloud seeding effect, the electric effect as well as the effect on solar radiation. After consideration of the most plausible theories and of the best available observational evidence there appears to be no reason for believing that atomic explosions have changed the weather. *Subject Heading:* 1. Atomic explosion effects on weather.—A.M.P.

## 7E-129

551.594.14:551.578.1

Bandopadhyay, K. G.; Ghosh, G. C.; Bandopadhyay, P. et al., Radioactive nuclei in rains over Calcutta. *Science and Culture*, Calcutta, 21(5):273-275, Nov. 1955. 2 figs., 5 refs. DLC—Radioactivity of rain water was measured in Calcutta from March to Sept. 1955. Radioactivity counts are plotted against the rainy days for the entire period. An analysis of residual matter revealed the preponderance of  $\beta$ -activity and the presence of some  $\alpha$ - and  $\gamma$ -activity. *Subject Headings:* 1. Radioactivity in rainwater 2. Calcutta, India. I. Chakravarti, J. C. II. Chatterjee, S. D.—G.T.

## 7E-130

662.2:539.1:551.574.1

Best, A. C., Atomic explosions and condensation nuclei. *Meteorological Magazine*, London 84(997):201-204, July 1955. 4 refs., eqs. DWB—The supersaturation necessary for a droplet carrying an electric charge to grow indefinitely is calculated. Even with 100 electronic charges a supersaturation of 7% is necessary. Both conditions are improbable. Solid particles require a charge of 50 e.u. to be effective as condensation nuclei. A vertical current of 48 ft/sec would be necessary to maintain a humidity of 100.5%. Atomic explosions are unlikely to affect condensation at a distance. (Same item as 61-129, Sept. 1955, MAB.) *Subject Headings:* 1. Atomic explosion effects on condensation nuclei 2. Charged nuclei 3. Supersaturation.—C.E.P.B.

## 7E-131

662.2:539.1:612.6

Biological hazards of radiation. *Nature*, London, 175(4460):695-697, April 23, 1955. DWB—An account of the discussions at various levels on the genetic effects of the fallout of radioactive matter from the thermonuclear bomb. It is concluded that we have insufficient knowledge to

predict whether there is any appreciable danger, including insufficient knowledge of the movements of the atmosphere at great heights. Radioactivity of the planet has slightly increased as a result of the bomb explosions. (Same item as 6.8-82, Aug. 1955, MAB.) Subject Headings: 1. Biological effects of radioactivity 2. Radioactive fallout.—C.E.P.B.

7E-132

551.594.14

Chatterjee, Santimay, Radioactive ashes over Calcutta and a method of dating a nuclear explosion. *Atomic Scientists Journal*, London, 4(5):273-278, May 1955. 2 figs., 2 tables, 4 refs., 4 eqs. DLC—Following the Bikini H-bomb explosions weak  $\beta$  activity was measured over Calcutta in dust samples and rain water. An attempt is made at dating nuclear explosions from the  $\beta$  decay curves of the radioactive dust. Subject Headings: 1. Radioactive fallout 2. Bikini H-bomb tests, 1954 3. Calcutta, India.—G.T.

7E-133

551.594.14 662.2:539.1

Cockcroft, Sir John, Radioactive pollution from nuclear explosions. *Smokeless Air*, 94:192-196, Summer 1955. DWB—Average concentration of radioactivity in the air at ground level over Britain due to hydrogen bomb explosions is about 1% of average natural radioactivity, far too little for lethal or genetic effects. Other possibilities are also negligible. Radioactive by-products of atomic power stations can also be controlled. (Same item as 6.9-74, Sept. 1955, MAB.) Subject Headings: 1. Thermonuclear explosions 2. Radioactive fallout 3. Great Britain.—C.E.P.B.

7E-134

662.2:539.1 551.594.14

Cockcroft, Sir John, Radiological hazards from nuclear explosions and nuclear power. *Nature*, London, 175(4464):873-875, May 21, 1955. DWB—The concentration of radioactivity over England due to distant bomb explosions is about 1% of natural radioactive dust. Nearly all the radiation is absorbed by brick houses. The average dose received during a generation is estimated as less than 0.003 r; anything less than 12.5 r is harmless. Other effects such as production of nitric acid and absorption of solar radiation by dust are also harmless. The genetic effects of an atomic war would be the least of the evils. By-products of nuclear power development can be disposed of safely. (Same item as 6.8-83, Aug. 1955, MAB.) Subject Headings: 1. Radiation hazards 2. Radioactive fallout 3. England.—C.E.P.B.

7E-135

551.5:662.2:539.1

Dunning, Gordon M. (*U. S. Atomic Energy Com., Wash., D. C.*), Effects of nuclear weapons testing. *Scientific Monthly*, 81(6):265-270, Dec. 1955. 24 refs. DWB, DLC—Among other things, the author considers the possible relationships between test nuclear explosions and the weather. Some of the effects suggested are listed and disproved. Subject Heading: 1. Atomic explosion effects on weather.—I.L.D.

7E-136

551.594.14:662.2:539.1

Eisenbud, Merrill and Harley, John H. (*U. S. AEC*), Radioactive fallout in the United States. *Science*, Wash., D. C., 121(3150):677-680, May 13, 1955. 2 figs., 11 refs. DLC—During 1952, 1953 and 1954 atomic tests in Nevada and the Pacific, a network of 89 monitoring stations was maintained in the U. S. to obtain samples of radioactive fallout. The samples were obtained on 1 ft<sup>2</sup> gummed surfaces mounted on a frame 3 ft above the ground. The coating is adhesive when wet, so dust entrapped in rain drops is collected. The films are changed each day and sent to the AEC laboratory in New York, where the samples are ashed at 550-600°C and the radioactivity counted with an accuracy of  $\pm 10\%$ . Network stations are listed and manner of testing illustrated graphically. Various components such as Sr<sup>90</sup> and Sr<sup>90</sup> are discussed as to half-life, manner of production and fallout. Map of U. S. shows cumulative fallout in the U. S. from spring of 1951 to end of 1954. Values range from 21 millicuries/sq mi in Arizona to 120 in N. Mexico. Nevada is omitted from the data. Examples of heavy fallout at great distance are cited. None of the values thus far measured are considered anywhere near biologically dangerous levels. (Same item as 7.2-276, Feb. 1956, MAB.) Subject Headings: 1. Radioactive fallout networks 2. Atomic explosion effects 3. United States.—M.R.

7E-137

551.594.14:612.6

Garrigue, Hubert, Nouvelle recrudescence d'activité d'origine atomique dans l'atmosphère. [Another renewal of atmospheric radioactivity of atomic origin.] *Académie des Sciences, Paris, Comptes Rendus*, 240(13):1453-1455, March 28, 1955. 2 refs. DLC—Beta activity was measured in dust samples taken in flight and snow and rime samples taken on Puy de Dôme (1450 m). The values obtained are comparable to natural radon amounts. Although the radioactivity measured does not constitute an immediate biological hazard, an increase of such pollution might cause the

higher organisms to degenerate and eventually to disappear. *Subject Headings:* 1. Radioactivity in the atmosphere 2. Puy de Dôme, France.—G.T.

7E-138

551.594.14:551.574.9

Garrigue, Hubert. **Radioactivité de l'atmosphère.** [Radioactivity of the atmosphere.] *Ad. Académie des Sciences, Paris, Comptes Rendus*, 241(25):1971-1972, Dec. 19, 1955. table, ref. DWB—Measurements made at the ground (Puy de Dôme, 1450 m) and in flight (up to 5 km) between Nov. 12, 1955 and Nov. 29, 1955, show a marked increase in  $\beta$  rays on Nov. 25, 1955, with a maximum value equivalent to 70 particles per cc of atmosphere for 35 days. Measurements were from hoarfrost accumulated on collector. Traces were observed before and after. *Subject Headings:* 1. Radioactivity in the atmosphere 2. Radioactivity in hoarfrost 3. Puy de Dôme, France.—M.R.

7E-139

551.594.14:551.574.9

Harbour, Dave. **The cloud over sheep mountain.** *Sport Airfield*, N. Y., 134(1):30-31, July 1955. photos. DLC—Attempt to determine effect of atomic fallout from series of tests at Yucca Flat in Nevada on wild sheep, rabbits, etc. have been made and conclusion is that no serious damage has been done to wildlife in area, though some skin burns from  $\beta$  radiation might occur within 10 or 20 mi of the detonation. Extreme care has been taken in firings to see that winds would not carry hot debris to any distance. (Same item as 7.4-292, April 1956, MAB.) *Subject Headings:* 1. Radioactive fallout effects on wildlife 2. Nevada atom bomb tests 3. Yucca Flat, Nevada.—M.R.

7E-140

551.594.14:551.594.13:551.510.42:662:539.1

Harris, D. Lee (U. S. W. B., Wash., D. C.). **Effects of radioactive debris from nuclear explosions on the electrical conductivity of the lower atmosphere.** *Journal of Geophysical Research*, 60(1):45-52, March 1955. 4 figs., 12 refs., 2 eqs. Also in: U. S. Air Force. *Cambridge Research Center Geophysical Research Papers*, No. 42:140-146, Nov. 1955. DWB—An increase in the ionization near the ground due to the fall-out from a radioactive cloud formed by a nuclear explosion will increase the conductivity and lower the potential gradient in the lower atmosphere. Records of atmospheric conductivity and potential gradient from the Tucson Magnetic Observatory are compared with records of the deposition of atomic debris on the ground following the Nevada tests. The observed changes are not inconsistent with values computed from theoretical considerations. Most of the effects are confined to a very shallow layer, within a few meters of the ground. (Same item as 6.8-341, Aug. 1955, MAB.) *Subject Headings:* 1. Radioactive fallout 2. Electrical conductivity of air 3. Potential gradient 4. Thermonuclear explosion effects.—Author's abstract.

7E-141

551.510.42:551.594.14

Harris, W. E. et al. **The Measurements Section discuss radiation hazards: discussion, Feb. 1955 on A services engineer at Harwell.** *Institution of Electrical Engineers, London, Journal*, New Ser., No. 8:518-519, Aug. 1955. 3 photos. DLC—Methods of air conditioning used at Harwell to reduce radiation hazards arising from radioactive dust. *Subject Headings:* 1. Radiation safety measures 2. Air conditioning.—M.R.

7E-142

551.510.42:551.594.14

Heslep, J. M. and Bellamy, A. W. **Sampling for airborne radioactivity.** *Air Repair*, Pittsburgh Pa., 5(1):1-4, May 1955. 6 refs. DWB—Nature and source of radioactive particles, biological effects, size of particles most effective in body ( $5\mu$ ), retention and exhalation, sources of contamination of air during various phases of atomic industry, methods of sampling and analysis and problems connected therewith, constructive use of radioactive aerosols (tagging air currents for meteorological studies), networks of sampling stations and success in predicting concentrations at these stations are discussed. (Same item as 7.4-128, April 1956, MAB.) *Subject Headings:* 1. Radioactive fallout networks 2. Radioactive aerosols.—M.R.

7E-143

551.579.5:551.594.14

Hours, R. (Commissariat à l'Énergie Atomique, France). **Les traceurs radioactifs en hydrologie** [Radioactive tracers in hydrology.] *Société Hydrotechnique de France, Paris, Mémoires et Travaux*, No. 1, 1955, p. 14-24. 4 figs., table, 18 refs. English summary p. 14. DWB—Radioactive iodine and bromine can be used in tracing ground water more advantageously than by using present color tracer methods. Retention by the soil, poisoning of the soil, etc. are discussed and results of quantitative measurements tabulated and analyzed. *Subject Headings:* 1. Radioactive hydrologic tracing methods 2. Ground water movements.—M.R.

7E-144

551.594.14:551.510.42:551.508.822

Ishii, Chihiro (*Met. Res. Inst., Tokyo*). **Method of measurement of radio-active dusts in the upper air by radiosonde.** [In: International Conference on the Peaceful Uses of Atomic Energy

Geneva, 1955, [Proceedings], A/CONF.8/P/1056, July 11, 1955. 14 p. 4 figs., table, 13 refs.] **DLC**—Measurements of gamma radiation in the upper atmosphere were made by means of a balloon-borne bundle of Geiger-Müller counters which telemetered results to a ground station. Results indicate a general increase in activity with altitude above the first km, with a peaking at the tropopause level. Subtraction of a mean cosmic ray background for the latitude gives the distribution of radioactive substances in the atmosphere, which are estimated to average  $10^{-16}$  c/cc in the winter of 1955. Airplane flights with a dust impinger at one to three km gave  $2 \times 10^{-18}$  c/cc. *Subject Headings: 1. Radioactivity measurement techniques 2. Radiosonde measurement of radioactivity.*—R. J. List.

7E-145

551.594.14

Kimura Kenjiro (Tokyo Univ.), **Radiochemical analysis of radioactive dusts.** [In: International Conference on the Peaceful Uses of Atomic Energy, Geneva 1955, [Proceedings], A/CONF.8/P/1058, July 11, 1955. 33 p. 18 figs., 6 tables, refs.] **DLC**—The specific activity of the ashes which fell on the "Fukuryu Maru" at 7:00 a.m., March 1, 1954, is estimated as 1.4 c/g. A detailed and extensive account of the radiochemical analysis of the ash, including procedures and results, is given. *Subject Heading: 1. Radioactive fallout analysis.*—R. J. List.

7E-146

551.594.14

Kimura, Kenjiro; Minami, Eiiti; Saito, Nobufusa et al., **Radiochemical interpretation of the radioactive fallout.** [In: International Conference on the Peaceful Uses of Atomic Energy, Geneva 1955, [Proceedings], A/CONF.8 P 1059, July 11, 1955. 11 p. fig., 5 tables, refs.] **DLC**—Following the Nagasaki detonation in Aug. 1945, a small village 2.5 km east of the blast was contaminated, probably by rain which occurred shortly after the detonation. A detailed radiochemical analysis of the sample was made in 1951 to study the long-lived radionuclides,  $\text{Sr}^{90}$  ( $+Y^{90}$ ),  $\text{Cs}^{137}$  ( $+B^{137m}$ ) and  $\text{Ce}^{144}$  ( $+Pr^{144}$ ) were found, together with a long-lived  $\alpha$ -emitter, presumably  $\text{Pu}^{239}$ . The activity in the samples in 1951 were as much as several hundred cmp per gram at approximately  $10^6$  counting yield. *Subject Headings: 1. Radioactive fallout analysis. I. Sasaki, Yukiyo II. Kokubu, Nobuhide.*—R. J. List.

7E-147

551.5:662.2:539.1

King, J. A., **Is world weather affected by nuclear explosions?** *South Africa. Weather Bureau, News Letter*, No. 73:1-2, April 30, 1955. **DWB**—Although present data are too limited and knowledge inadequate, it is the author's opinion that no evidence exists to show that thermonuclear explosions can be held responsible for a world-wide increase in rainfall and cloudiness. None of the features of world weather occurring in the past few years have been unprecedented, therefore it is safe to say that effects of dust, sea salt particles or energy added to the atmosphere have not equalled effects occurring naturally. *Subject Headings: 1. Thermonuclear explosion effects 2. Weather modification.*—M.R.

7E-148

551.508.9

Klick, C. C.; Rabin, H.; Lambe, J. J. et al., **Simple meter for radioactive fall out.** *U. S. Naval Research Laboratory, NRL Report*, No. 4571, June 14, 1955. 7 p. 4 figs., 3 refs. **DWB**—A dose rate meter has been constructed using a battery, cadmium sulphide crystal, and parallel combination of condenser and neon flash lamp. It is sensitive over a range of 0.1 Roentgen to 1000 Roentgens/hr. is reasonably energy independent, has a flash rate proportional to gamma dose rate, and uses only commercially available components. *Subject Headings: 1. Radioactive dose rate meters 2. Radioactivity measurement techniques. I. Peake, H. J. II. Cole, P. T.*—Authors' abstract.

7E-149

551.594.14

\*Libby, W. F., **Dosages from natural radioactivity and cosmic rays.** *Science*, Wash., D. C., 122(3158):57-58, July 8, 1955. 5 tables. **DWB**—Total radiation dosages from natural background radiation in mr/yr are given for sea level, 5, 10, 15 and 20 thousand ft altitude at equator and  $55^\circ\text{N}$ , over several types of surface. Cosmic ray dosages in mr/yr are also tabulated for the same elevations. Dosages from natural radiation of the human body, and from various other types of materials, objects and X-rays; and gamma and cosmic ray data obtained in streets, buildings and in the open by several authorities are likewise tabulated and discussed. Natural dosages are variable by a factor of 100 to 1 in different conditions. Fallout dosages may exceed natural dosages for a few days. *Subject Headings: 1. Radioactivity in the atmosphere 2. Cosmic ray dosages in atmosphere.*—M.R.

7E-150

551.594.14:612.6

Luckow, L.; Widdoes, L. C. and Mesler, R. B., **Hazards due to airborne fission products; external  $\gamma$  and  $\beta$ , inhalation, and rainout.** Appendix E, from unidentified source. [1955?] 19 p.

6 figs., table, 5 refs., eqs. **DWB**—Biologically significant values of fission products from nuclear reactors are calculated and quantitative results presented in diagrams as functions of distance from reactor, wind, velocity, continuous reactor power and meteorological situation (lapse or inversion condition). Dose parameters and critical organs for various fission product isotopes are shown in a table. *Subject Headings:* 1. Radiation hazards 2. Biological effects of radioactivity.—G.T.

7E-151

551.594.14:551.506.9(793)

\*Lynch, Daniel E., **Radioactive debris in North America from Operation Teapot.** *U. S. Atomic Energy Commission, Report NYO-4659*, Aug. 1955. 3 p. fig., 3 tables, 2 refs. **DLC**—Total fallout from the Spring 1955, Nevada tests as observed at over 100 stations in North America for the period of Feb. 18–May 20, 1955 is given. Fallout in the United States ranged from 3.1 millicuries per sq mi. along the west coast to 850 millicuries per sq mi at Ely, Nevada, extrapolated to Jan. 1, 1956. (Data in the immediate area of the tests is not given.) The maximum fallout recorded in one day is 600 millicuries per sq mi, extrapolated to Jan. 1, 1956, at Ely on March 7, 1955. Moderate amounts of fallout continued beyond May 20. *Subject Headings:* 1. Radioactive fallout data 2. Ely, Nevada.—R. J. List.

7E-152

551.594.14:551.515:662:539.11

Machta, L. and Harris, D. L. (*U. S. W. B., Wash., D. C.*), **Effects of atomic explosions on weather.** *Science*, 121(3134):75–81, Jan. 21, 1955. 6 figs., 14 refs. **DWB**—Various suggested mechanisms by which atomic explosions might influence weather have been reviewed. They include the following hypotheses: that the atomic debris might serve as a cloud seeding agent, that the radioactive nature of the debris might change the electric conductivity of free atmosphere, that the dust resulting from atomic explosion might obscure the solar radiation and that the energy of the explosion might affect significantly the weather beyond the testing location. No theoretical reason has been found for believing that the above mechanisms could alter the weather significantly more than a few miles from the explosion site. Increase of tornadoes in 1953 was a reflection of greater accuracy in tornado statistics. Temperature and precipitation anomalies fail to show any relationship to atomic explosions. (*Same item as 6.8–342*, Aug. 1955, *MAB.*) *Subject Headings:* 1. Atomic explosion effects on weather 2. Weather modification.—I.L.D.

7E-153

551.594.14

Martin, Charles-Noël, L'heure H, a-t-elle sonné pour le monde? **Effets accumulatifs des explosions nucléaires.** [The H hour, has it sounded for the world? The cumulative effects of nuclear explosions.] Preface by Albert Einstein. Paris, Bernard Grasset, 1955. 254 p. photos, tables. **DLC**—The purpose of this book is to disseminate knowledge on nuclear physics and to remind scientists of the dangers of atomic experimentation. In the first part a general outline is given of the nuclear structure of matter. Pt. 2 contains an account of the experimental A and H bomb blasts of the past, while in Pt. 3 (p. 153–239) the author considers theoretically the possible future effects of continued nuclear explosions. The intense heat generated, acidity of rain water, the presence of dust in the stratosphere, radioactive fallout, harmful isotopes, and their direct and indirect meteorological and biological effects are discussed. The author contends that various products of atomic explosions may disturb the equilibrium of climatic factors and that there would be no assurance that normal conditions could be re-established. It has been argued that the energy involved in nuclear explosions is too small for meteorological effects. This argument misses the point because climatic effects are caused by a global distribution of fission products (dust, radioactive ions, nitric acid) rather than direct action of the energy released. Factual data on various phenomena connected with nuclear explosions are appended. *Subject Headings:* 1. Nuclear physics 2. Thermodynamic nuclear explosion effects. I. Einstein, Albert.—G.T.

7E-154

551.463/4:551.594.14

Miyake, Yasuo; Sugiura, Yoshio and Kameda, Kazuhisa (*Met. Res. Inst., Tokyo*), **On the distribution of the radioactivity in the sea around Bikini Atoll in June, 1954.** *Records of Oceanographic Works in Japan*, n.s., 2(1):34–44, March 1955. 8 figs., table, 6 refs. Also issued as: *Papers in Meteorology and Geophysics*, Tokyo, 5(3/4):253–263, Jan. 1955. **DWB**—Observations were made from May 15, 1954 to July 4, 1954 aboard the "Shunkotsu-Maru" of the Ministry of Agriculture and Forestry from Tokyo to Bikini Atoll. Methods of measuring radioactivity in sea water, the horizontal and vertical distribution of radioactivity in the sea around Bikini, and the relation between the sea water radioactivity and the radioactive fallout are given in detail. The actual measurements on different days and places and at various depths are presented tabularly and analyzed graphically. (*Same item as 6.10–43*, Oct. 1955, *MAB.*) *Subject Headings:* 1. Radioactivity in ocean water 2. Radioactive fallout data 3. Bikini H-bomb tests, 1954 4. Pacific Ocean.—M.R.

7E-155

551.594.14:551.578.11

Miyake, Yasuo (*Met. Res. Inst., Tokyo*), **Radioactivity in rain water and the air observed in Japan, 1954-1955.** [In: International Conference on the Peaceful Uses of Atomic Energy, Geneva 1955, [Proceedings], A/CONF.8/P/1055, July 11, 1955. 11 p. 6 figs., 10 refs.] **DLC**—Radioactivity was detected in the rain in southern Japan beginning May 14, 1954, reaching a maximum of  $5 \text{ c/l}$  on May 16 at Kyoto Univ. Trajectories indicate air came from Bikini via the Philippines to Formosa. Activity from May to Sept. 1954 was always stronger on the Pacific side of Japan than on Japan sea side, maximum values in latter area less than  $4 \text{ m}\mu\text{c/l}$ . Active material concentrated at the beginning of rain. Rain along a cold front in the wake of a typhoon on Sept. 18, 1954, was radioactive, reaching a maximum of  $0.3 \mu\text{c/l}$  on Sept. 22 at Yamagata, on northern Japan sea coast, and decreasing in activity as air from south moved in. Similar activity, also presumably from U.S.S.R. in early Nov. Dry fallout in Tokyo on Nov. 4-5, 1954, was  $5 \text{ m}\mu\text{c/m}^2/\text{day}$  and air concentrations of  $10^{-12}$ - $10^{-10} \text{ c/m}^3$  were observed near the ground at Kyoto by an electric precipitator. The highest rain activity in the spring of 1955 was  $3 \sim 4 \text{ m}\mu\text{c/l}$  with the activity of the air at Kyoto increasing when a high pressure center is above the Japan sea area or off the northeastern coast on the Pacific side. **Subject Headings:** 1. Radioactivity in rainwater 2. Radioactive fallout in Japan. 3. Japan.—*R. J. List.*

7E-156

551.463/4:551.594.14

\*Miyake, Y. and Sugiura, Y. (*both, Met. Res. Inst., Tokyo*), **The radiochemical analysis of radioisotopes in sea water collected near Bikini Atoll.** *Records of Oceanographic Works in Japan*, Tokyo, 1955, 2(2):108-112, Oct. 1955. 5 figs., 2 tables, ref. **DWB**—Results are presented of a radiochemical analysis of sea water from  $12^{\circ}18'N$ ,  $161^{\circ}3'.5E$  on June 20, 1954, 450 km N.E. of Bikini (where H-bomb tests were made during March to May 1954). Total count was 1830 cpm/l aboard "Shun-tsu-Maru," just after sampling. By Aug. 12, 1954 it had decreased to 320 cpm/l. Activity on Dec. 1, 1954 should have been 190 cpm/l. Decay curve was concluded to be  $A(t) = A_0 e^{-\lambda t}$ , where  $A(t)$  is activity,  $A_0$  a constant and  $t$  the time elapsed since explosion. Radioactivity of 5 constituents was measured from Dec. 11-22, 1954, ranging from 1100 cpm for the 55% of Ce-141, 144 to 40 cpm for the 2% of Sr-89 (90). Methods are detailed. **Subject Headings:** 1. Radioactivity in ocean water 2. Bikini H-bomb tests, 1954.—*M.R.*

7E-157

551.463/4:551.594.14

\*Miyoshi, Hisashi (*Tokyo Univ.*); Hori, Sadakiyo and Yoshida, Shozo (*both, Hydrog. Off., Marine Safety Agency, Tokyo*), **Drift and diffusion of radiologically contaminated water in the ocean.** *Records of Oceanographic Works in Japan*, Tokyo, 1955, 2(2):30-36, Oct. 1955. 4 figs., 2 tables, 7 eqs. **DWB**—Radiologically contaminated water from the lagoon on the eastern atoll of Bikini, carried by the North Equatorial current was detected by a Japanese Survey Ship (the "Shunkotsu-Maru") along the  $163^{\circ}50'E$  meridian (150 mi W of Bikini) 38 days after the last of the H-bomb tests in March-May, 1954. The material proved of value in tracing the currents and vertical eddy diffusivity which latter was found to be  $5 \text{ cm}^2/\text{sec}$  in the upper mixing layer. Contaminated water was found 800 km ENE, probably due to a counter current. Speed of fall of calcite particles of different diameters ( $5 \sim 840 \mu$ ) to be .3 to 8950 hours to depth of 500 m. **Subject Headings:** 1. Radioactivity in ocean water 2. Bikini H-bomb tests, 1954.—*M.R.*

7E-158

551.594.14:662.2:539.1:612.6

Muller, H. J. (*Zoology Dept. Indiana Univ.*), **Genetic damage produced by radiation.** *Science*, Wash., D. C., 121(3155):837-840, June 17, 1955. 8 refs. **DLC**—A pro-and-con discussion of possible cumulative genetic damage of radioactive fallout from all of the atomic tests in U. S., Pacific and U.S.S.R. or of damage from an atomic war. Even the conservative estimate of 0.1 r for each of the population of the U. S. when multiplied by 160,000,000 is said to be exactly equal to the  $100 \text{ r} \times 160,000$  people at Hiroshima, though admittedly the genetic damage would occur in more isolated instances, be spread over a longer time, and be small compared to mutations occurring naturally. Author considers mutations to be a serious factor, nevertheless, and for the worse 99 times out of 100. **Subject Headings:** 1. Biological effects of radioactivity 2. Mutations due to radioactive fallout 3. Radiation hazards.—*M.R.*

7E-159

551.510.5:551.515.8:551.594.14

Neuwirth, R. (*Met. Obs., Freiburg, Germany*), **Meteorologische Auswertung von Messungen der künstlichen Radioaktivität der Luft und des Niederschlags.** [Meteorological evaluation of measurements of artificial radioactivity in the air and in rainfall.] *Geofisica Pura e Applicata*, Milan, 32:147-158, Sept./Dec. 1955. 4 figs., 26 refs. English and German summaries, p. 147. **DWB, DLC**—German, French and American measurements of the rainfall and air activity are being evaluated. For that purpose trajectories of the experimental grounds for atomic bomb tests in Nevada up to Western Germany are drawn. By means of intermediate values the test possibility

of air paths—first only scheduled—is given. The so-called "Deposit spaces" and meridional circulations, which are significant particularly in divergence regions prove to be of especial importance. The mechanism of activation of precipitation is discussed. A connection between activity of precipitation and airmasses could only be found in individual cases. But it seems the semitropical airmasses dispose of a higher specific activity in comparison with the polar masses. *Subject Headings: 1. Upper air flow patterns 2. Radioactive fallout propagation*  
*Author's abstract.*

7E-160

662.2:51

Nishiwaki, Yasushi, *Effects of H-bomb tests in 1954.* *Atomic Scientists Journal*, London 4(5):279-288, May 1955. table, map. **DLC**—Results of various extensive measurements made in Japan in connection with nuclear tests in the Pacific are reviewed. The phenomena observed particular were: radioactivity in rainfall and in the upper atmosphere all over Japan; dust floating in the upper atmosphere; barographic oscillations resulting from shock waves; contamination of fishing boat "Fukuryu Maru" and its crew; and radioactivity in crops and fish. *Subject Headings: 1. Thermonuclear explosion effects 2. Bikini H-bomb tests, 1954 3. Japan.—G.T.*

7E-161

551.594:551.508.9:519

Ogawara, M., *On the error of radioactivity count number.* *Journal of Meteorological Research*, Tokyo, 7(8):507-509, Oct. 1955. 4 refs., 21 eqs. In Japanese. **DWB**—A mathematical treatment of the accuracy of radioactive counters is given with explanatory text in Japanese. Errors derived as functions of counting rate. *Subject Heading: 1. Radioactive counter accuracy.—G.T.*

7E-162

551.594.14:

Pozdnyakov, V., *Atomic defense in the Soviet army.* *Institute for the Study of the History Culture of the USSR, Munich, Bulletin*, 2(8):13-19, Aug. 1955. 8 refs. **DLC**—Basic considerations governing protective measures for military personnel in the U.S.S.R. are outlined. Protection from immediate and prolonged effects of atomic blasts includes personal defense and an atomic defense service which would secure the removal of troops from contaminated areas and their decontamination. Most of the information is from the Soviet army newspaper Red Star. *Subject Headings: 1. Radiation safety measure 2. Military meteorology.—G.T.*

7E-163

551.594.14:662.2:513

Preston, R. L. and Hogg, B. G., *Radioactive fall-out in Kingston, Canada.* *Nature*, London 176(4479):459, Sept. 3, 1955. fig. **DWB**—Tests of snow, rain and dust at Kingston, 2200 N.E. of U. S. nuclear testing ground, Feb. 15 to May 28, 1955, show that every explosion was followed by radioactivity, but meteorological factors outweighed the magnitude of the explosions. *Subject Headings: 1. Atomic explosion effects 2. Radioactive fallout data 3. Kingston, Canada.—C.E.P.*

7E-164

551.557:551.594:

\*Ratner, Benjamin, *Winds and fallout: a climatological appraisal.* Wash., D. C. Weather Bureau, June 1955. 19 p. 13 charts, 6 refs. **DWB**—The work is mainly concerned with frequency and strength of winds at 3 and 10 km; at 700 and 300 mb in Jan. and July, over continental U. S., and the mean geostrophic winds at 200, 100, 50 and 25 mb. A page is devoted to a diagram of fallout patterns which occurred on April 10 and 11, 1955 over Pennsylvania and a brief discussion of these and of relation of fallout to upper winds in general. Jet stream wind, seasonal conditions at the various levels, frequency of west winds, sources of errors, effect of stratosphere (height tropopause) and other relations brought out by the charts are discussed in text. *Subject Headings: 1. Upper air winds 2. Jet stream 3. Radioactive fallout propagation.—M.R.*

7E-165

551.594:

Reiter, Reinhold, *Der Emanationsgehalt der Luft in den nördlichen Kalkalpen in Abhängigkeit von atmosphärischer Schichtung und Windrichtung.* [On the emanation content of the air in the northern Chalcidic Alps in relation to atmospheric structure and wind direction.] *Naturwissenschaften*, 42(23):622-623, Dec. 1955. fig., 2 refs. **DWB**—Determinations of thoron and radon were made on Zugspitze plateau Aug.-Sept. 1955. In temperature inversions there were 5 impulses/min compared with 335 in convective weather. With SW-SE winds emanation was 3 times that with winds from W-N-E. These results are of interest for atmospheric electricity and bioclimatology. (Same item as 7.4-293, April 1956, MAB.) *Subject Headings: 1. Radioactive emanations 2. Zugspitze, Germany.—C.E.P.B.*

7E-166

551.594.14

*The role of the warden in panic prevention.* U. S. Federal Civil Defense Administration, Civil Defense Technical Bulletin, TB-7-1, rev. Sept. 1955. 4 p. Also: *Protection against fallout radiation*

*Id.*, TB-11-19, Sept. 1955. 2 p. 8 refs. Also: **Radiological instruments for civil defense.** *Ibid.*, TB-11-20, Sept. 1955. 4 p. 5 photos, 6 refs. Also: **Fallout and the winds.** *Ibid.*, TB-11-21, Sept. 1955. 7 p. 9 figs., 9 refs. **DWB**—The first three papers deal with practical and technical problems of civil defense. The last paper takes up the prediction of fallout areas and radiation levels from upper wind forecasts and climatic data on prevailing winds. Among the schematic drawings presented are diagrams comparing sizes of A-bomb, H-bomb and thunderstorm, and showing effects of particle size, height and wind over size of fallout area and a map of U. S. showing average winds between 40,000 and 80,000 ft for Jan. *Subject Headings:* 1. Radiation safety measures 2. Radioactive fallout propagation.—G.T.

7E-167

551.594.14:551.501

†Shapiro, E.; Gibbs, J.; Field, E. et al., **Development of a tracer technique.** Tracerlab, Inc., Boston, Mass., Contract AF 19(604)-1045, Final Report, Aug. 19, 1955. 77 p. 20 figs., 3 charts., 13 tables, bibliog. p. 59-60, eqs.—An extensive report on development of a radiological tracer technique which involves selection of a tracer (tritiated ethane) preparation of gas; development of a gas dispenser, an air sampler and a method of analysis. The tracer is nearly like air in molecular weight, does not constitute a health hazard, lends itself to chemical analysis and the methods of analysis are known. Field tests were made and compared with SO<sub>2</sub> tracer technique. *Subject Headings:* 1. Radioactive tracer techniques. I. Tracerlab, Inc., Boston, Mass. II. Contract AF 19(604)-1045 III. Dillon, T.—M.R.

7E-168

551.594.14:551.510.42:662.2:539.1

Sittkus, A., **Beobachtungen an radioaktiven Schwaden von atomtechnischen Versuchen im Jahre 1953/54.** [Observations of radioactive swathes from atomic experiments in 1953/54.] *Naturwissenschaften*, 42 (17):478-482, Sept. 1955. 5 figs., table, 11 refs. **DWB**—Radioactive products of an atomic explosion can be traced half or a third way round the globe. Rain and snow bring them down and the natural level on the ground may be doubled. A systematic investigation of the radioactivity of air and rainwater was carried out in and near Freiburg following the Nevada and Marshall Island explosions. The amount was very variable from day to day. A method of determining the date of an explosion is described. Use of radioactive products as indicators of atmospheric currents is discussed. (*Same item as* 7.2-119, Feb. 1956, MAB.) *Subject Heading:* 1. Radioactive fallout propagation.—C.E.P.B.

7E-169

551.541:623.454.9

Skeib, Günther, **Beobachtungen von Druckwellen bei Wasserstoffbomben-Explosionen im Jahre 1954.** [Observations of pressure waves from hydrogen bomb explosions in 1954.] *Zeitschrift für Meteorologie*, 9 (9):280-282, Sept. 1955. fig., 2 tables, 3 refs. **DLC**—The Bikini explosions of Feb. 28, March 26, April 25 and May 4, 1954 were recorded on barographs at Potsdam, Lindenberg, Vahnsdorf and Collm 11-12 hrs later as pressure waves of 0.1 to 0.2 mmHg amplitude. Barograms are reproduced. The mean velocity of the waves was 288-313 m/s. (*Same item as* 7.4-192, April 1956, MAB.) *Subject Headings:* 1. Pressure waves 2. Thermonuclear explosion effects 3. Bikini H-bomb tests, 1954 4. Germany.—C.E.P.B.

7E-170

551.509.58:662.2:539.1

Spohn, Clifford A. (*Weather Briefing Off., Nevada Test Site*), **Weather support for the atomic tests.** *Weatherwise*, Boston, 8(5):111-115, 130, Oct. 1955. 2 figs., 2 photos, table. **DWB**—In this account of the weather support provided by the U. S. Air Force Weather Service to the Atomic Energy Commission at the Nevada Test Site, the author describes the organization of the forecast unit, the basis for preparing the forecast, the obtaining of upper air data, the operational routine of forecasting for each atomic test, etc. Maps showing the special upper air sounding network for the Nevada Test Site and Weather Bureau network providing special observations for Nevada Test Site are included. *Subject Headings:* 1. Specialized forecasts 2. Atomic test weather service 3. Yucca Flat, Nevada.—I.L.D.

7E-171

551.594.14:551.506.9

\*Stewart, N. G.; Crooks, R. N. and Fisher, E. M. R., **The radiological dose to persons in the U.K. due to debris from nuclear test explosions.** Harwell, England. *Atomic Energy Research Establishment, A.E.R.E.*, HP/R 1701, June 1955. 27 p. 4 figs., 3 tables, 13 refs.—Presents a summary and an extensive interpretation of radioactivity measurements in the United Kingdom and of aircraft measurements over that area. Vast majority of particles less than 10 $\mu$ . Discusses sources of residual radiation. Cloud from nominal bomb confined by tropopause and Intertropical Convergence Zone and observations suggest that lateral diffusion virtually complete after one circuit of the earth. Debris normally first observed in the U.K. on the fifth day after a Nevada burst. Deposition removes half the material from the atmosphere in 22 days. For thermonuclear bursts,

most debris is injected into the stratosphere and diffuses slowly into the lower atmosphere. Airplane observations in the autumn of 1954 confirmed this, indicating large accumulations of fine dust in the stratosphere. Individual peak concentrations in the U.K. are generally about 5 dpm/m<sup>3</sup>, higher than the individual peak 25 dpm/m<sup>3</sup> from nominal bombs. Highest peak from thermonuclear bomb, 0.5 dpm/m<sup>3</sup>. Average concentration April 1952 to April 1955, 0.5 dpm/m<sup>3</sup>, mostly from Nevada explosions. Natural RaB and RaC averaging as high as 470 dpm/m<sup>3</sup> and peak concentrations of 1800 dpm/m<sup>3</sup> have been observed in U.K. Measurements of deposition by rain also made, 80% of the integrated gamma dose from a Nevada cloud deposited by rain due to deposition on first crossing of U.K. Exposed vaseline-coated slides, concluded that deposition by normal rainfall was 4 times that due to dry deposition. Highest daily deposit, 240 mc/sq mi, 5 days after A Nevada test. Highest from a thermonuclear test, 100 mc/sq mi. Computations of the gamma dose and the deposition of Sr<sup>90</sup> and Pu<sup>239</sup> in U.K. given. Mean gamma dose rate to exposed person 1 r/yr. Estimated gamma dose to average person in U.K. for 50-year period from all bombs prior to May 1955, 1.6 mr. Concentration of Sr<sup>90</sup> on ground on May 1, 1955, 2 mc/sq mi. *Subject Headings:* 1. Radioactive fallout data 2. Radioactivity in the atmosphere.—R. J. List.

## 7E-172

551.5:662.2:539

Sutton, Sir Oliver Graham, *Thermonuclear explosions and the weather*. *Nature*, London, 175(4451):319-321, Feb. 19, 1955. 6 refs. DWB—The summer of 1954 in Britain following H-bomb explosions in the Pacific was cool, wet and dull, but no records were broken. Long period records suggest that it was a continuation of a general trend, and aerological evidence does not show any relation to the explosions. The energy of the most violent explosion is only equal to that of our small depression. Debris thrown into the upper atmosphere was many times less than in the Krakatoa eruption, which had no effect on British weather. Radioactive nuclei are very unlikely to cause any significant increase of rainfall over a large area. (Same item as 6.6-43, June 1955 MAB.) *Subject Headings:* 1. Thermonuclear explosion effects on weather 2. Abnormal summer 1954.—C.E.P.B.

## 7E-173

551.594.14:551.578.1

Tanaevsky, Olga and Vassy, Etienne, *Radioactivité naturelle et artificielle de l'atmosphère* [Natural and artificial radioactivity of the atmosphere.] *Annales de Géophysique*, Paris, 11(4):486-490, 1955. 3 figs., table, 25 refs. DLC—Atmospheric radioactivity produces essentially discontinuous records. In calm air an accumulation of radon content usually builds up but disappears with the slightest wind. No annual periodicity is found. Rainwater collected with a special gage lately has shown considerable radioactivity of artificial origin. *Subject Headings:* 1. Radon content of atmosphere 2. Radioactivity in rainwater.—*Trans. of authors' abstract.*

## 7E-174

551.594.1

\*Tanaevsky, Olga and Vassy, Etienne, *Variations de la radioactivité naturelle et artificielle de l'atmosphère*. [Variations of natural and artificial radioactivity of the atmosphere.] *Académie des Sciences, Paris, Comptes Rendus*, 241(1):38-40, July 4, 1955. fig., table, 7 refs. DWB—Continuous (from Dec. 1953 to June 1955) measurement of atmospheric radioactivity carried out at a height of 4 m at Val Joyeux showed the absence of any relationship between the presence of radon, temperature and pressure. However, there seems to be a relationship with wind speed; radioactivity increases when the wind is slight. The radioactivity of rain and snow water collected in a special gage appears to be stronger at the beginning of the rain (from 87 impulses/min to 200 after a rainfall of 22 mm). The strongest radioactivity registered was of 724 microcuries. The established radioactivity seems to be of artificial origin due to recent atomic explosions. *Subject Headings:* 1. Radioactivity variations 2. Radioactivity in precipitation 3. Val Joyeux, France.—A.M.P.

## 7E-175

551.594.1

Tanaka, Shinjiro, *Death ash: experience of 23 Japanese fishermen*. *Japan Quarterly*, Tokyo, 2(1):36-42, Jan./March 1955. DLC—An account of the tragic fishing trip of the "Fukuryu Maru" and description of injuries suffered by its crew as a consequence of radioactive fallout which settled on the boat operating 148 km from the site of an H-bomb test on March 1, 1954. Effects of radioactive fallout on fish, vegetables, drinking water, etc., are discussed. *Subject Heading:* 1. Radioactive fallout effects.—G.T.

## 7E-176

551.594.1

Thomas, C. D.; Gainer, M. K. and Ball, T. W., *Relation of radon to non-active air contamination*. *Nature*, London, 175(4460):732-733, April 23, 1955. DWB—Interim report of measures taken in West Virginia, where coal is a common fuel. *Subject Heading:* 1. Radon content of atmosphere.—C.E.P.B.

7E-177

551.5:662.2:539.1

\*Tokyo. Meteorological Research Institute. Forecast Research Laboratory, **Climatic abnormalities as related to the explosion of volcano and H-bomb.** *Meteorological Society of Japan, Journal*, Ser. 2, 33(3):101-116, July 1955. 22 figs., 4 tables, 12 refs. In Japanese; English summary. 101. **DWB, DLC**—The effects of volcanic explosion on the climatic abnormalities are investigated statistically and synoptically. The abnormal weather during the summer season in 1954 when the large-scale H-bomb experiment was made is found to have the similar features as the climatic abnormalities caused by volcanic dust. The distribution of temperature anomalies and annual variation of it are discussed in relation to the tropospheric circulation. *Subject Headings: 1. Thermonuclear explosion effects on weather 2. Abnormal summer, 1954 3. Japan.—Author's abstract.*

7E-178

551.594.14:612.2

U. S. Atomic Energy Commission, **Effects of high-yield nuclear explosions (with) statement by Lewis L. Strauss.** Wash., D. C. U. S. Govt. Print. Off., Feb. 1955. 19 p. **DLC**—Describes the extent of fallout especially as observed during the thermonuclear test on Bikini, March 1, 1954, which contaminated an area extending some 220 miles down-wind and varying in width up to 40 mi. It is estimated that "there was sufficient radioactivity in a down-wind belt about 140 mi in length and of varying width up to 20 mi to have seriously threatened the lives of nearly all persons in the area who did not take protective measures." About one half of such persons would have been threatened at about 60 mi down-wind from the point of detonation. Effects of different types of radioactive fallout and means of protection are discussed. *Subject Headings: 1. Thermonuclear explosion effects 2. Biological effects of radioactivity 3. Bikini H-bomb tests, 1954.—G.T.*

7E-179

551.5:662.2:539.1

U. S. Congress. Joint Committee on Atomic Energy, **Health and safety problems and weather effects associated with atomic explosions.** Hearings before the Joint Committee on Atomic Energy Congress of the U. S., 84th Congress, 1st Session, on Health and safety . . . April 15, 1955. Wash., D. C., Govt. Printing Office, 1955. 60 p. 6 figs., photos. **DWB**—Contains statements by Dr. Harry Wexler (accompanied by Dr. Lester Machta) of the U. S. W. B. regarding the possible effect of nuclear tests in Pacific and in Nevada on weather, (radiation and rainfall) and statements of other experts on effects on health, amount of radioactivity in air, etc. Article by Machta and Harris from *Science*, Jan. 21, 1955 is reproduced here in entirety. Wexler presented graph showing radiation received over 20-30 year period at Table Mt., Calif., and Blue Hill, Mass., indicating pronounced effect of Mt. Spurr, Alaska, volcanic eruption and negligible effect of nuclear explosions in Pacific in 1952 and 1954. *Subject Heading: 1. Atomic explosion effects on weather.—M.R.*

7E-180

551.594.14:551.509.1(02)

U. S. Federal Civil Defense Administration, **Construction of fallout plots from coded messages provided by the U. S. Weather Bureau.** Its *Advisory Bulletin*, No. 188, May 25, 1955. 10 p. 1 table, figs. Also Supplement No. 1, Aug. 16, 1955. 2 p. fig. And Supplement No. 2, Sept. 27, 1955. 2 p., 2 attachments. **DWB**—Effective June 1, 1955 fallout messages concerning particles falling from different levels from 5000 to 80,000 feet will be currently transmitted over the U. S. Government Weather Teletype Service "C" twice a day. The coded messages give information on "the direction of potential fallout from Ground Zero and the time of surface arrival of radioactive debris applicable to all the critical target areas in the United States." This *Advisory Bulletin* contains instructions for the practical use of the Weather Bureau messages. Copies of the U. S. **Weather Bureau Upper Air Fallout Code** (see 7E-193) and of the paper **Winds and fallout** (see 7E-164) are attached. *Subject Heading: 1. Radioactive fallout calculation manuals.—G.T.*

7E-181

551.594.14:35

U. S. Federal Civil Defense Administration, **Operation Cue, the atomic test program of the Federal Civil Defense Administration in cooperation with the Atomic Energy Commission, Nevada Test Site, Spring 1955.** Wash., D. C., U. S. Govt. Printing Office, 1955. 82 p. figs., graphs, tables. **DLC**—Civil defense activities connected with atomic tests are outlined. The booklet contains description of blast, thermal and radiation effects of nuclear explosions, and diagrams for calculating mechanical, thermal and radiation hazards. Thermal effects are given as a function of thermal energy delivered, distance from explosion and atmospheric turbidity. Civil defense problems connected with fallout are discussed. *Subject Headings: 1. Radiation safety measures 2. Civilian defense.—G.T.*

7E-182

551.594.14(02)

U. S. Weather Bureau, **Fallout of radioactive debris.** Its *Circular Letter* 7-55, Feb. 16, 1955. 2 p. bound with this is: U. S. Atomic Energy Commission, **Report by the U. S. Atomic Energy Commission on the effects of high-yield nuclear explosions.** For release, Tuesday, Feb. 15, 1955. 30 p. **DWB**—The Circular Letter dated Feb. 16, 1955 and addressed to all first-order stations

gives modifications on the procedure of computing areas of radioactive debris fallout (as outlined in Circular Letter 16-54) in connection with the first AEC report on the effects of high-yield nuclear explosions. The necessary modifications are threefold and are due to be facts that: 1) The radioactive cloud extends to much greater altitudes than in case of atomic bombs; 2) The widths of the mushroom top of the radioactive cloud can be 40 mi or more; 3) The fallout can be dangerous at distances of more than 200 mi and for periods in excess of 12 hrs. Attached is **Report of AEC on the effects of high-yield nuclear explosions**, dated Feb. 15, 1955 designed to condense and correlate information, some of which already has been made public and other portions of which have been of classified nature. The report deals consecutively with blast and heat effects and protection against them, immediate nuclear radiation and residual radioactivity. *Subject Heading: 1. Radioactive fallout calculation manuals.—A.M.P.*

7E-183

551.510.42:620.92:539

†U. S. Weather Bureau, **Meteorology and atomic energy**. Prepared for the U. S. Atomic Energy Commission. Wash., D. C., July 1955. 169 p. numerous figs. (incl. photos), 152 refs. Price \$1.00 from U. S. Govt. Print. Off., Wash., D. C. DWB—This is the first major monographic contribution summarizing theoretical, observational and empirical knowledge of air pollution problems connected with atomic energy production and experimentation. The separate chapters treat the following subjects: 1) air pollution aspects of the atomic energy industry; 2) meteorology in site operations; 3) meteorological fundamentals for air pollution study; 4) an outline of atmospheric diffusion theories; behavior of 5) stack effluents; 6) explosion debris clouds; 7) fallout, washout and rainout from airborne clouds; 8) radioactive cloud dosage calculations; 9) graphical solutions of atmospheric diffusion problems; 10) reactor hazard analyses; 11) meteorological equipment and records; 12) climatological data for site selection and planning. The appendix contains a selective list of parameters, equations and conversion factors, and a list of 152 references to recent literature (mostly 1949-1954) on the above subjects, plus a subject index. A wealth of illustrative photographic material, charts, maps, sample forms, diagrams and tables add to the value of this work (For fuller abstract, see 7.1-1, Jan. 1956, M.A.B.) *Subject Headings: 1. Radioactive effluents 2. Atmospheric pollution 3. Stack meteorology. I. Pack, Donald H. II. Reichelderfer, F. W. III. Wexler, Harry IV. U. S. Atomic Energy Commission.—M.R.*

7E-184

551.594.1

Warners, C. J., **Note on radioactive compounds in the atmosphere**. *Tellus*, 7(3):403-404, Aug. 1955. table, 7 refs. DWB—Since Jan. 1, 1955, daily measurements of the radioactivity of the air have been made by the Royal Netherlands Meteorological Institute. The highest values noted were in the period April 28-30, in tropical air transported from the south, and reached  $27.4 \times 10^{-10} \mu\text{Ci}$ . Measurements of rain and snow also show considerable day-to-day variability, activities of  $8 \times 10^{-7} \mu\text{Ci}$  per ml have been observed. *Subject Headings: 1. Radioactivity in the atmosphere 2. Netherlands.—R. J. List.*

7E-185

551.5:662.2:539

**What's affecting the weather?** *Franklin Institute, Philadelphia, The Institute News*, 19(8):1, 3, March 1955. DWB—In connection with a show at Fels Planetarium, Philadelphia, a few meteorological topics are taken up, such as possible meteorological effects of nuclear explosions, the forecasting value of weather lore, and weather observation from artificial satellites. *Subject Headings: 1. Thermonuclear explosion effects on weather 2. Weather lore.—G.T.*

7E-186

551.594.14:551.577.1

Yamasaki, Fumio and Kaneko, Hideko, **On the artificial radioactivity in rain water: observation of radioactivity in rain water in Tokyo from April to Dec. 1954, and a simple method of determining the date of explosion**. *Tokyo. Scientific Research Institute, Journal*, 49(1,391):137-143, June 1955. 5 figs., 2 tables, 4 foot-refs. DWB—Rainwater analyses made for rainfall occurring between April and Dec. 1954 at Tokyo show remarkable increases in May, Sept. and Nov. An analysis of the decay curves shows that explosions of radioactive nature occurred about 10 days prior to dates of the increase in rainwater radioactivity. Methods of analyzing fallout, decay curves and determination of  $t_0$  (time of explosion) are discussed and illustrated by detailed graphs and supporting quantitative data. A negative correlation was found between rainfall intensity and radioactivity. Since the graphic method of determining  $t_0$  applies to known explosion dates, it will be satisfactory for determining unknown dates. *Subject Headings: 1. Radioactive fallout analysis 2. Radioactivity in rainwater 3. Tokyo, Japan.—M.R.*

1956

7E-187

551.594.1

Blifford, I. H., Jr., and Rosenstock, H. B., **Fallout dosages at Washington, D. C.** *Scientific Research Institute, Journal*, 123(3198):619-622, April 13, 1956. 4 figs., refs., 8 eqs. DLC—Also issued as *U. S. Naval Research*

laboratory. Report, NRL 4654, Nov. 3, 1955.—The total infinity dosage at Washington, D. C., due to fallout fission product debris from all atomic tests which took place between Jan. 1951 and May 1955 has been estimated from the measured air concentration at ground level. Within order of magnitude accuracy, this dosage was found to be about 0.2 roentgen. The Nevada tests contributed about 60% of this amount, and the Russian tests about 33%, with the remainder due to tests in the Pacific. Evidence for stratospheric holdup of activity from the thermonuclear tests of the spring of 1954 has been found. Fallout of this high altitude activity corresponds to an infinity dosage of about 0.0002 roentgen. *Subject Headings:* 1. Radioactive fallout data 2. Washington, D. C.—Authors' abstract.

7E-188

551.594.14

Garrigue, Hubert and Perrin, Albert, Trou soufflant radioactif au sommet du Puy-de-Dôme. [Radioactive air hole at the Puy de Dôme peak.] *Académie des Sciences, Paris, Comptes Rendus*, 42 10:1348-1346, March 5, 1956, table, 2 refs. DWB—A hole, 10 cm in diameter, formed naturally in the snow cover, discharges warm (+3°C), radioactive air ( $400 \text{ to } 800 \times 10^{-16} \text{ c/cm}^3$ ). *Subject Headings:* 1. Radioactive emanations 2. Puy-de-Dôme, France.—Transl. of authors' abstract.

7E-189

662.2:539.1:551.578.11:541.132.3

Harrassowitz, Hermann, Atombombenexplosionen und Regen-pH. [Atom bomb explosions and rain pH.] *Naturwissenschaften*, 43 1:11-12, Jan. 1956, 7 refs. DWB—C. N. MARTIN claimed that the nitric acid in smoke mushrooms from atom bombs is unfavorable for vegetation. The author made a number of pH determinations in rain, dew and snow in W. Germany and found values of 3.1-8.5. The acidity is probably unfavorable, but the problem is complex. A full report is in preparation. *Subject Headings:* 1. Atomic explosion effects 2. pH content of rainwater.—C.E.P.B.

7E-190

551.594.14:016

\*List, Robert J. (U. S. W. B., Wash., D. C.), Annotated bibliography on the transport and deposition of atomic debris. Pub. by the U. S. Atomic Energy Commission, Jan. 20, 1956. 27 p. Price: \$.15 from U. S. Govt. Print. Off., Wash., D. C. Issued as TID-3061. DWB—The 76 papers abstracted in this bibliography deal with sampling and measurement of dust, rain, or snow containing radioactive fission products. In addition to articles appearing in the regular American, British, French and Japanese journals, some unpublished papers of U. S. government agencies and other organizations are included. Quantitative values reported in the papers are given in the abstracts. *Subject Headings:* 1. Bibliography on radioactive fallout 2. Annotated bibliographies.—G.T.

7E-191

551.594.14:551.579

Setter, L. R. and Goldin, A. S., Radioactive fallout in surface waters. *Industrial and Engineering Chemistry*, 42 2:251-255, Feb. 1956, 3 figs., 5 tables, 3 refs. DLC—Between March 10 and Nov. 15, 1954, 79 rain and six dust samples were collected in Cincinnati, and measured for beta activity. A total of  $0.53\mu\text{c}$  per square meter was deposited during the period. The maximum accumulated activity at any one time was  $0.125\mu\text{c m}^2$  and by Nov. 16  $0.07\mu\text{c m}^2$  remained from 1954 deposition, due to decay. An additional  $0.0127\mu\text{c m}^2$  theoretically remained from 1953 deposition. Vegetation, roofing, dust, etc. was 2 to 1000 times more active than the rain. Non-filterable activity in rain averaged from 46 to 69% of total, individual values ranged from 18 to 91%. Maximum rainfall activity  $10.6\mu\text{c ml}$  on March 13. Studies of activity in cisterns and pond. Monthly average pond activity ranged from 28 to  $230\mu\text{c ml}$ , 57-92% nonfilterable. *Subject Headings:* 1. Radioactivity in surface waters 2. Cincinnati, Ohio.—R. J. List.

7E-192

551.594.14

\*Tajima, Eizo and Doke, Tadayoshi (both, St. Paul's Univ., Tokyo), Airborne radioactivity. *Science*, Wash., D. C., 123 3189:211-214, Feb. 10, 1956, 3 figs., table, 8 refs. DLC—Results of measurements of airborne radioactivity in Japan from March 16 to May 4, 1955 are reported. Daily values of radioactivity due to fission products are graphically represented in conjunction with rainfall and temperature values. Trajectories of high-pressure centers for the period investigated are plotted on a map. The weak correlation between radioactivity and rainfall amount indicates "that rainfall does not completely clean up the contaminated air." It is suggested that radioactive dust was transported by the jet stream. *Subject Headings:* 1. Radioactive fallout data 2. Radioactivity in the atmosphere 3. Japan.—G.T.

7E-193

551.509.1:551.594.14

U. S. Weather Bureau, Upper air fallout data code. Jan. 1956. 2 p. DWB—A simple upper air fallout data code for use effective Feb. 1, 1956, replacing code dated April 1955. Collections are

at 0817Z and 2017Z and the code will now be selected by RAWIN stations in the continental U.S. Data transmitted for 5000, 10,000, 20,000, 40,000, 60,000 and 80,000 ft levels includes direct toward which particles would fall and distance in statute miles from station at which particles would land which take 3 hrs to fall from the given level (to tens of miles). Additional instructions given for coding. *Subject Headings:* 1. Upper air fallout code 2. Radioactive fallout.—M.R.

## 7E-194

662.2:539.1:551.3

Weickmann, L., *Durch die Explosion von Atombomben erzeugte Wolkenformen.* [Cloud forms resulting from atom bomb explosions.] *Meteorologische Rundschau*, 9(12):1-5, Jan./Feb. 1956. 7 figs., 3 refs. DWB—Some automatic and aircraft photos of the Bikini underwater explosion are reproduced and their development discussed. A column of water 700 m across rose to a height of 2500-3000 m. Ten seconds after the explosion a great cauliflower cloud appeared at the head of the column, expanding through local saturation. At the upper edge of the troposphere (18 km) the cloud field reached 100 mi diameter. Water falling back from the cloud formed a ring of spray round the foot of the column. A central projection above the cloud field reached a height of 30-35 km. *Subject Heading:* 1. Atomic explosion clouds.—C.E.P.B.

## SUPPLEMENTARY MATERIAL

## 7E-195

551.509.59:551.594.

U. S. Office of Naval Operations, *Aerological aspects of Operation Crossroads.* Its NAVAB 50-45T-4, March 1947. 31 p. 10 figs. DWB—Describes organization and operations of the Aerological Unit which was assigned to Operation Crossroads for the purpose of preparing weather forecasts and recommendations for the Bikini atom bomb tests in the summer of 1946. The actual forecasts made are analyzed. In Ch. 5 (p. 20, 27-28) the problem of possible meteorological effects resulting from atom bomb explosions are taken up (thunderstorm generation, rainfall due to radioactive nuclei and convective cloud formation). No evidence of a widespread meteorological effect of atomic blasts was furnished by the Bikini tests. *Subject Headings:* 1. Specialized forecasts 2. Atomic test weather service.—G.T.

## 7E-196

551.594.14:662:539

Bethe, Hans; Brown, Harrison; Seitz, Frederick and Szilard, Leo. *The facts about the hydrogen bomb.* *Bulletin of the Atomic Scientists*, Chicago, 6(4):106-109, 126-127, April 1950. With criticism by David E. Lilienthal, p. 109 and Reply by L. Szilard, p. 109, 126-127. Also: Arnold, James H. *The hydrogen-cobalt bomb.* *Ibid.*, 6(10):290-292, Oct. 1950. Also: Arnold, James R., *Fall of hazard: an erratum.* *Ibid.*, 11(2):52, Feb. 1955. DLC—This summary of a radio broadcast on properties of H-bombs contains a statement by L. SZILARD according to which all human life could be extinguished by radioactive fallout. If an H-bomb would be combined with an element which would absorb all neutrons, the explosion of 500 tons of heavy hydrogen would produce the universal lethal dose of fallout radioactivity. LILIENTHAL's criticism is a "denunciation of the cult of doom." ARNOLD re-examines SZILARD's calculations and finds them basically correct, "although a full-scale effort of a major country, over many years would be required" to kill "the vast majority of the race in this way, and the danger, therefore, is not immediate." *Subject Headings:* 1. Thermonuclear explosion effects 2. Global radioactivity.—G.T.

## 7E-197

551.521:551.586:551

Cowan, Frederick F. (*Brookhaven Nat. Lab.*), *Everyday radiation.* *Physics Today*, N. Y. 5(10):10-16, Oct. 1952. 2 figs., 5 tables, 16 refs. DWB—The author gives a rough quantitative survey of various types of radiation to which the human body is currently exposed. The types of radiation considered are cosmic rays, natural radioactivity, residual activity due to A-bomb explosions, radiation from radium-bearing luminescent paint and X-rays. The effect of rainfall and of inversions on the amount of radioactivity originating in atmospheric dust particles is discussed and graphically presented. (Same item as 4.6-214, June 1952, MAB.) *Subject Headings:* 1. Radiatic effects 2. Radioactivity in the atmosphere 3. Human ecology.—G.T.

## 7E-198

551.510.42:620.92:539.1

White, Fred D., *Weather Bureau and the Atomic Energy Commission.* [In: Sanitary Engineering Conference, Chicago, 1952, Proceedings. Pub. 1952. p. 136-142. 20 refs. DWB—Meteorological services performed by the U.S.W.B. for the Atomic Energy Commission since the inception of the Manhattan Project include advice on site selection (as to atmospheric stability and weather conditions), engineering data for design and construction, meteorological scheduling of operations in some cases, reports of hazard frequency and assistance in atomic tests and in sampling over the U.S.A. after tests (25 stations collecting samples). Forecasts as well as climatological and technic

ta are provided. Meteorological research in turbulence and diffusion is outlined. It was found that surface concentrations of radioactivity are 10 to 1000 times as great during precipitation during normal fallout. Future research is projected. A number of technical papers hitherto classified or unpublished are listed. *Subject Headings:* 1. Radioactive fallout networks 2. Atomic energy meteorology 3. U. S. Weather Bureau 4. Radioactive effluents.—M.R.

7E-199

551.594.14:575.7

U. S. National Bureau of Standards, **Maximum permissible amounts of radioisotopes in the human body and maximum permissible concentrations in air and water.** Its *Handbook* No. 52, March 20, 1953. 45 p. 5 tables, eqs. bibliog. p. 34-42. Also Its: **Permissible dose from external sources of ionizing radiation.** *Handbook*, No. 59, Sept. 24, 1954. 77 p. 3 figs., refs. **DLC**—In *Handbook* 52 maximum permissible amounts of radiation for continuous exposure are tabulated (p. 14-16) for some 80 radioactive elements. Constants for calculating maximum permissible internal concentration of radioisotopes are listed on pages 18-29. In *Handbook* 59 the effects of ionizing radiation on various human organs and maximum permissible doses for continuous or occasional exposure are discussed in detail. Other *Handbooks* in this series deal with: **Recommendations for the disposal of carbon-14 wastes** (*Handbook* 53); **Protection against radiations from radium, cobalt-60 and cesium-137** (54); **Protection against betatron-synchrotron radiations up to 100 million electron volts** (55); **Safe handling of cadavers containing radioactive isotopes** (56); **Photographic osimetry of X- and gamma rays** (57); and **Radioactive-waste disposal in the ocean** (58). *Subject Headings:* 1. Radioactive permissible dosage 2. Biological effects of radioactivity.—G.T.

7E-200

551.594.14(931)

Ryder, N. V. and Watson-Munro, C. N., **The detection of radioactive dust from the British nuclear bombs of October 1953.** *New Zealand Journal of Science and Technology, Sec. B*, 36(2):155-59, Sept. 1954. 3 figs., refs. **DLC**—Thirty hours after nuclear explosion near Woomera, Australia, on October 1953, a peak in  $\beta$ -activity of 50 cpm was observed in Wellington, N. Z., on an air filter. A second peak of 6 cpm was observed a few hours later. Decay curves indicated the activity was fission product activity. *Subject Headings:* 1. Radioactive fallout data 2. Wellington, New Zealand.—R. J. List.

7E-201

551.5:539.1:662.2

Arakawa, H., **Possible atmospheric disturbances and damages to the rice-crops in northern Japan that may be caused by experimentation with nuclear weapons.** *Geophysical Magazine, Tokyo*, 26(2):125-134, Feb. 1955. 2 figs., tables, 8 refs. **DWB**—In temperature records for Japan for the last 70 years, 1884 appears as the coldest year. This may be attributed to absorption of solar radiation by dust originating in the Krakatoa eruption of 1883. Another extremely cold summer, June-July 1954, may be due to dust from nuclear explosions at Bikini, March-May 1954. *Subject Headings:* 1. Atomic explosion effects on weather 2. Abnormal summer, 1954.—G.T.

7E-202

551.594.14

Hopper, V. D. and Laby, Jean E. (both, *Univ. Melbourne*), **Electron background in imported G5 emulsions.** *Australian Journal of Physics*, Melbourne, 8(4):557-562, Dec. 1955. 3 figs., 2 tables, ref. **DLC**—Ilford G5 nuclear emulsion plates received in Melbourne every 2 weeks for 6 months were manufactured in England and shipped by air so as to arrive in Australia about 2 weeks after manufacture. Four of 12 batches showed unusually heavy electron contamination (background) when developed soon after receipt. Estimated background due to cosmic radiation on a 38 hour flight at 10-20 thousand feet will be about 1.5 Mrep, and at ground in storage <0.5 Mrep/day or a total of 10 Mrep or less. Some of the plates show a background of about this amount but some show excessive counts which could be due to irradiation at time of manufacture or storage; or from radioactive isotopes or instrument panel in flight, or from X-ray examination by customs; or from atomic debris after an explosion. The radioactivity at Val Joyeux (7E-174) on several occasions lends support to the last named theory, since the heaviest contamination corresponds with the date of shipment about April 6, on which date VASSY recorded 159C counts/m.l of rain, a value 40 or 50 times normal. Also agreement is shown between contaminated shipment on June 4, with peak values of 192 and 154 counts on June 3 and 6 respectively. *Subject Heading:* 1. Radioactive fallout effects.—M.R.

7E-203

551.594.14:551.501.9

Japan. Central Meteorological Observatory, **The system of routine observations of radioactivities in the air, rain water and sea water in Japan.** (In: International Conference on the Peaceful Uses of Atomic Energy, Geneva 1955, A/CONF.8/P/1051, [*Proceedings*], July 11, 1955. 4 p. table.) **DWB**—Names, locations and elevations of 16 Japanese stations engaged in routine sampling of radioactivity in rainwater and dust are listed and details of their operations outlined. Results of measurements and samples for radiochemical analysis are regularly sent to the Central

Meteorological Observatory at Tokyo; unusually high values of contamination are reported by Telegram. *Subject Headings:* 1. Radioactive fallout networks 2. Japan.—G.T.

## 7E-204

551.594.14:38

Lapp, Ralph E., Civil defense faces new peril. *Bulletin of the Atomic Scientists*, Chicago, 10(9):349-351, Nov. 1954. 2 refs. Also his: Radioactive fall-out. *Ibid.*, 11(2):45-51, Feb. 1955. 3 figs. Also his: Radioactive fall-out III. *Ibid.*, 11(6):206-209, 230, June 1955. Also his: Global fall-out. *Ibid.*, 11(9):339-343, Nov. 1955. 2 tables, 8 refs. Also his: "Fall-out": another dimension in atomic killing power. *New Republic*, Wash., D. C., 132(7):8-12, Feb. 1955. DLC—In this series of four articles (the one in *New Republic* is identical with that in the Feb. 1955 *Bulletin*) all aspects of radioactive fallout are thoroughly discussed on the basis of published information. Estimates are made of the area of fallout, persistence of the hazard and global atmospheric contamination. Biological effects and possible protective measures are considered. The importance of thorough public information on all properties of radioactive fallout is stressed. *Subject Headings:* 1. Radioactive fallout 2. Civilian defense 3. Atomic explosion effects.—G.T.

## 7E-205

551.594.14:38

Lapp, Ralph E., Fall-out and candor. *Bulletin of the Atomic Scientists*, Chicago, 11(5):170-200, May 1955. DLC—The author criticizes the U. S. Government's excessive secrecy in dealing with civil defense problems connected with possible effects of nuclear explosions. He objects to the official AEC fall-out release of Feb. 15, 1955 that (a) it is not candid on the persistence of fall-out, (b) it does not define the nature of the superbomb, (c) it glosses over the internal hazard of fall-out particles and (d) it is irrelevant with respect to genetic effects of fallout radiation. (For the AEC report see 7E-178). *Subject Headings:* 1. Radioactive fallout 2. Civilian defense.—G.T.

## 7E-206

551.594.14:551.463/4

Miyake, Yasuo, On the distribution of radioactivity in the north Pacific Ocean in 1954-1955 (In: International Conference on the Peaceful Uses of Atomic Energy, Geneva 1955, [Proceedings] A/CONF.8/P/1057, July 11, 1955. 11 p. 6 figs., table, 8 refs.) DWB—Sea-water radioactivity measurements made around the Bikini test site are summed up. Horizontal and vertical radioactivity distribution is shown in diagrams. Relation between sea-water activity and fallout is discussed. *Subject Headings:* 1. Radioactivity in ocean water 2. Bikini H-bomb tests.—G.T.

## 7E-207

551.594.14:662:539.1

Rotblat, J., The hydrogen-uranium bomb. *Atomic Scientists Journal*, London, 4(4):224-228, March 1955. Reprinted in: *Bulletin of the Atomic Scientists*, Chicago, 11(5):171-172, 177, May 1955. DLC—On the basis of facts communicated in the U. S. Atomic Energy Commission release of Feb. 1955 (see 7E-178) and other reports, the author speculates on the possible nature of the H-bomb. He calculates that as much as 80% of the power released in an H-bomb explosion may be derived from uranium fission. If this is the case, radioactivity presents a major problem. According to the author's estimate, 75 twenty-megaton bombs exploded over a period of 30 years (i.e. at the rate of  $2\frac{1}{2}$  tests a year) would double the natural level of radiation and thus approach a critical value from a genetic point of view. *Subject Headings:* 1. Thermonuclear explosion effects 2. Global radioactivity.—G.T.

## 7E-208

551.594.14:35

U. S. Congress. Senate. Committee on Armed Services, Civil defense program. Hearings before the Subcommittee on Civil Defense of the Committee on Armed Services, 84th Congress, First Session, on operations and policies of the civil defense program, Feb. 22, 26, March 3, 4 and 8, 1955. Pt. 1 and Appendix. Wash., D. C., U. S. Govt. Printing Office, 1955. 377 p. figs., photo, tables. Also: Candor in Congress: the Kefauver hearings. *Bulletin of the Atomic Scientists*, Chicago, 11(5):181-184, May 1955. DLC—The main purpose of these hearings was to examine the administration of the 1950 Civil Defense Act, and more particularly, to consider problems arising from radioactive fallout following H-bomb detonations. Physical properties, propagation and biological effects of radioactive fallout, other effects of thermonuclear bombs, and the present status of various civil defense programs are thoroughly discussed in all their aspects by such authorities as W. F. LIBBY (Commissioner, U. S. Atomic Energy Comm.), V. PETERSON (Administrator, Fed. Civil Defense Admin.), A. S. FLEMING (Dir., Office of Defense Mobilization), J. C. BUGHER (Dir. of Biology and Medicine, U. S. AEC) and others, with Senators KEFAUVER, SYMINGTON, JACKSON, SALTONSTALL and SMITH as members of the Subcommittee. Thus, even though the physical factors involved are treated only in general terms, this document is probably the most complete and most informative single source available to date on fallout and other H-bomb effects in relation to civil defense. Publication of this type of information was, in fact, one of the aims of the Subcommittee, and to this end several documents (such as AEC reports, articles by R. E. Lapp, etc.) are added as Exhibits 1 to 18. The article in the *Bulletin* gives excerpts from the Feb. 22 session. *Subject Headings:* 1. Civilian defense 2. Radioactive fallout 3. Congressional hearings.—G.T.

7E-209

551.510.42:628.53:551.594.14

Wexler, H.; Machta, L.; Pack, D. H.; and White, F. D. (all U. S. Weather Bureau), **Atomic energy and meteorology**. (In: International Conference on the Peaceful Uses of Atomic Energy, Geneva 1955, [Proceedings], A/CONF.8/P276, June 23, 1955. 28 p. 9 figs., 26 refs., 14 eqs.)  
 DWB—The role of meteorology in site selection and plant design for nuclear reactors is outlined. The various factors involved in the atmospheric diffusion of gases (physical state of effluent, geographical and orographical effects, wind, temperature gradient and precipitation) are discussed and the use of theoretical diffusion equations is explained. The practical problems of radioactive meteorological tracers, of reactor site selection and of the analysis of environmental hazards from reactors are considered. The diagrams and charts presented show the type of meteorological information used in nuclear plant studies. *Subject Headings: 1. Radioactive effluents 2. Stack meteorology.—G.T.*

7E-210

551.594.14

List, R. J., **Radioactive fallout in North America from Operation Teapot**. (To be published by U. S. Atomic Energy Commission, Washington, D. C., 1956.) Meteorological trajectories of debris from the Nevada atomic tests in the Spring of 1955 are given, together with the daily fallout at over 100 gummed film stations in North America for the period Feb. 18–May 20, 1955. Experiments indicate that on dry days, inverted and vertical gummed films collect about 40% as much as normal horizontal films; on days with precipitation, about 1 to 4% as much. Radioautographs of individual rain drops indicate that during a period of fallout at Chicago, about three drops in a hundred were radioactive. *Subject Headings: 1. Radioactive fallout data 2. United States.—R. J. List.*

7E-211

551.594.14:551.508.94

Schumann, G., **Untersuchung der Radioaktivität der Atmosphäre mit der Filtermethode**. [Investigation of atmospheric radioactivity by the filter method.] *Archiv für Meteorologie, Geophysik und Bioklimatologie*, Ser. A, Vienna, 9(2):204–223, 1956. 7 figs., 24 refs., 10 eqs. German, English and French summaries p. 204–205. DWB—Radioactive aerosol is caught by a filter which is then placed inside a counter; procedure is described. Observations were made at ground level near Heidelberg (130 and 565 m). Quantitative estimates are given of the various Ra and Th products (including atom bomb products,  $10^{-12}$ – $10^{-13}$  curie/m<sup>3</sup>). There were considerable variations which are attributed to the effect of weather on ground emanations. Precipitation and fronts greatly decrease activity. Relations are also found to pressure, time of day and vertical air movements. Measurements were also made in air sucked from boreholes some meters deep, and related to geological structure. *Subject Heading: 1. Radioactivity measurement techniques.—C.E.P.B.*

7E-212

551.594.14:681.177

U. S. National Bureau of Standards, **Radioactive fallout computer**. Its *Technical News Bulletin*, 40(4):56–58, April 1956. Photos, diagrs. DLC—A "special purpose computer developed for predicting the geographical fallout pattern resulting from a nuclear explosion" is described. Meteorological data and information on properties of the bomb exploded are fed into the machine which then produced an oscilloscope pattern representing the fallout distribution and intensities. By laying a (transparent) map over the oscilloscope, radioactive intensities may be obtained up to 500 miles from ground zero. Photographs of the instrument panel and oscilloscope and two simplified schematic diagrams are presented. *Subject Heading: 1. Radioactive fallout computers.—G.T.*

7E-213

662.2:539.1:77.9

Handel Film Corporation (Hollywood, Calif.), **Atom and the weather**. Film, 12½ minutes, rent \$10.—This film illustrates why tests of atomic weapons have no effect on the weather; how radioactive fallout is carefully traced to protect the public and how radioactivity from atomic tests is used as a research tool by the weatherman. *Subject Headings: 1. Atomic explosion effects 2. Educational films.—From Educational Film Guide.*

7E-214

551.594.14:662.2:539.1

Blifford, I. H., Jr.; Lockhart, L. B., Jr. and Baus, R. A. (all, U. S. Naval Research Lab.), **Relationship between air concentration of radioactive fission products and fallout**. *Nature*, London, 177(4517):990–992, May 26, 1956. fig., 2 tables, ref. DWB—A comparison is made between the daily concentrations of fission products collected by gummed paper and by air filter, at Washington Dec. 1954–May 1955. The fallout averaged  $2.3 \times 10^3$  ft/day for days without rain and  $30 \times 10^3$  for rainy days, but with great variations. There was little correlation with concentration in the air, nearly all the fallout was in one week when the concentration was not especially high. *Subject Headings: 1. Atomic explosion effects 2. Radioactivity in the atmosphere 3. Washington, D. C.—C.E.P.B.*

# PART III. REVIEWS OF RECENT IMPORTANT METEOROLOGICAL MATERIAL, AND METEOROLOGICAL ARTICLES APPEARING IN RECENTLY ISSUED PUBLICATIONS

**Note:** The references to reviews of new books or monographs and the contents of periodicals included in this section are for information only and will not be listed in the monthly indexes until abstracted. When material is furnished in advance of publication, the pagination may be omitted.

## A. REVIEWS OF IMPORTANT METEOROLOGICAL MATERIAL

- Alisov, B. P.; Berlin, I. A. and Mikhel', V. M.: **Kurs klimatologii, chast' 3** [Course in climatology Pt. 3]. Ed. by E. S. Rubinshtein. Leningrad, Gidrometeoizdat, 1954. Review by A. I. Tokmanov in *Meteorologiya i Gidrologiya*, Leningrad, No. 5:61-63, Sept./Oct. 1955. (See 6.11-5, Nov. 1955, MAB.)
- Bartholomew, John: **Advanced Atlas of Modern Geography**. New Series, 3rd ed. London, Meiklejohn, 1953. 102 p. of maps. 51 p. of index. Price, 30 sh. Review by R. E. Lacy in *Weather*, London, 11(3):96, March 1956.
- Bellamy, J.: **Four dimensional flight planning**. [In] *Journal of Navigation*, 4(3), Sept. 1954. Review by F. Cerasuolo in *Rivista di Meteorologia Aeronautica*, Rome, 15(2):39, April/June 1955. (See 6.7-91, July 1955, MAB.)
- Compendium of Meteorology**, ed. by Thomas F. Malone. Boston, American Meteorological Society, 1951. 1334 p. Review by László Felmery in *Időjárás*, Budapest, 59(5):299-300, Sept./Oct. 1955. (See 3.3-1, March 1952, MAB.)
- Germany. Deutscher Wetterdienst in der US-Zone: **Klima-Atlas von Bayern** [Climatic atlas of Bavaria]. Bad Kissingen, Zentralamt, 1952. Scale of map 1:1,000,000. 47×50 cm. Review by Adam Schmuck in *Przegląd Geograficzny*, Warsaw, 27(1):156-158, 1955. (See 4.2-4, Feb. 1953, MAB.)
- Germany. Deutsche Demokratische Republik. Meteorologischer und Hydrologischer Dienst: **Klima-Atlas für das Gebiet der Deutschen Demokratischen Republik** [Climatic atlas for the German Democratic Republic]. Berlin, Akademie Verlag, 1953. Scale of map 1:1,000,000. 42×56 cm. Review by Adam Schmuck in *Przegląd Geograficzny*, Warsaw, 27(1):154-156, 1955. (See 5.4-2, April 1954, MAB.)
- Gustafson, A. F.: **The error in rawin computations due to neglecting the earth's curvature**. [In] *American Meteorological Society, Bulletin*, (7):295-300, 1954. Review by F. Rispoli in *Rivista di Meteorologia Aeronautica*, 15(2):40-41, April/June 1955. (See 6.6-57, June 1955, MAB.)
- Hood, Peter: **The atmosphere**. London, Oxford Univ. Press and Geoffrey Cumberlege, 1952. 64 p. Price, 8 sh. 6 d. Review by [D. G. Hurley?] in *Weather*, London, 11(2):59-60, Feb. 1956. (See 4.6-15, June 1953, MAB.)
- L'Institut Royal Météorologique de Belgique [The Royal Meteorological Institute of Belgium]. Brussels, pub. by the Institute, 1954. 216 p. Review by Luigi Pellisari in *Rivista di Meteorologia Aeronautica* 15(2):44, April/June 1955. Review by J. R. Rivet in *World Meteorological Organization, WMO Bulletin*, 5(1):38, Jan. 1956. (See 6.10-10, Oct. 1955, MAB.)
- Istoshin, IU. V.: **Okeanografiya** [Oceanography]. Leningrad, Gidrometeoizdat, 1953. Review by L. G. Toporkov in *Meteorologiya i Gidrologiya*, Leningrad, No. 5:64-66, Sept./Oct. 1955. (See 6.5-6, May 1955, MAB.)
- Kashin, K. I. and Gritsenko, M. V.: **Ob izmenenii davleniia u zemnoi poverkhnosti** [Change of pressure at earth's surface]. [In] *Meteorologiya i Gidrologiya*, Leningrad, No. 5, Sept./Oct. 1954. Review by N. N. Romanov in *ibid.*, No. 6:59-60, Nov./Dec. 1955.
- Kochin, Nikolaï Evgrafovich; Kibel', I. A. and Roze, N. V.: **Theoretische Hydromechanik, Bd. 2** [Theoretical hydromechanics, vol. 2]. Trans. from Russian and technically edited by K. Krienes. Berlin, Akademie-Verlag, 1955. 569 p. Price, DM 48. Review by O. G. Sutton

- in *Meteorological Magazine*, London, 85(1004):60-61, Feb. 1956. (For review of original Russian, see 6.5-7, May 1955, *MAB*.)
- Condrat'ev, K. I. A.: **Luchistaia energii solntsa** [Radiational energy of the sun]. Ed. by P. N. Tverskii. Leningrad, Gidrometeoizdat, 1954. Review by M. E. Berliand; N. A. Efimova and I. D. Ianishevskii in *Meteorologiya i Gidrologiya*, Leningrad, No. 5:63-64, Sept./Oct. 1955.
- Krivský, Ladislav and Krivská, B.: **Klima Ondrejova po astronomickou potrebu** [Climate of Ondrejov for astronomical purposes]. [In] *Meteorologické Zprávy*, Prague, 6(5):133-139, 1953. Review by Janusz Paszyński in *Przegląd Geograficzny*, Warsaw, 27(1):162-163, 1955.
- Kyriazopoulos, Basil D.: **Degree of wintriness**. *Thessalonike. Univ. Meteorological Institute, Meteorologica*, No. 1, 1954. 25 p. illus. Review by H. H. Lamb in *Meteorological Magazine*, London, 85(1004):61, Feb. 1956.
- Lundegårdh, Henrik: **Klima und Boden in ihrer Wirkung auf das Pflanzen-Leben**, [Climate and soil in their influence on plant life]. 4th rev. ed. Jena, G. Fischer, 1954. Review by Michał Strzemiński in *Przegląd Geograficzny*, Warsaw, 27(1):163-164, 1944.
- Minkel'dei, M. A.: **M. M. Pomortsev: pervyi russkii aerolog** [M. M. Pomorotsev: the first Russian aerologist]. Leningrad, Gidrometeoizdat, 1954. Review by A. Kh. Khrgian in *Meteorologiya i Gidrologiya*, Leningrad, No. 6:58-59, Nov./Dec. 1955.
- Physical Society of London: **Reports on Progress in Physics**, Vol. 17. 1954. Ed. by A. C. Stickland. 280 p. Price, £ 2, 10 sh. Review by E. R. Cohen in *Physics Today*, N. Y., 9(3):24, March 1956.
- Riazanov, V. A. (ed.): **Predel'no dopustimye kontsentratsii atmosferykh zagraznenii** [Safe concentrations of atmospheric pollutants]. 2nd ed. Moscow, Medgiz, 1955. Review by A. I. Shafrir in *Gigiena i Sanitariia*, Moscow, 21(1):59-60, Jan. 1956.
- Sapozhnikova, S.: **Mikroklimat i klimat lokalny** [Microclimate and local climate]. Warsaw, Państwowe Wydawnictwa Rolnicze i Leśne, 1953. 221 p. Review by Janusz Paszyński in *Przegląd Geograficzny*, Warsaw, 27(1):158-162, 1955. Review by St. Zych in *Przegląd Meteorologiczny i Hydrologiczny*, Warsaw, 7(1/2):92, 1954.
- Shamov, G. I.: **Rechnye nanosy** [River deposits]. Leningrad, Gidrometeoizdat, 1954. Review by I. A. Chebotarev in *Meteorologiya i Gidrologiya*, Leningrad, No. 6:57-58, Nov./Dec. 1955.
- Shaw, Sir William Napier: **Selected Meteorological Papers**. Lond., Macdonald, 1955. 276 p. Review by R. Bilancini in *Rivista di Meteorologia Aeronautica*, Rome, 15(2):43-44, April/June 1955. Review by D. A. Davies in *World Meteorological Organization, WMO Bulletin*, 5(1):39, Jan. 1956. (See 7.1-2, Jan. 1956, *MAB*.)
- Sverdrup, Harald U. and Munk, Walter: **Veter, volnenie i zyb': teoreticheskie osnovy prognoza** [Wind, sea and swell: theoretical basis for forecasting]. [A chapter from *Osnovy predskazaniia vetrovyykh voln, zyi i priboia*. (Principles of forecasting wind, swell and surge.) Moscow, I.I.L., 1951.] Translation from English ed. by V. B. Shtokman. Review by A. A. Ivanov in *Akademiia Nauk SSSR, Izvestiia, Ser. Geofiz.*, No. 1:117-118, 1956. (For abstract of original English, see 5K-40, Nov. 1954, *MAB*.)
- Tricart, Jean: **Climat, vegetation, sols et morphologie** [Climate, vegetation, soils and morphology]. 50e anniversaire du Laboratoire de Géographie, Rennes, 1952. Review by Jan Dylik in *Przegląd Geograficzny*, Warsaw, 27(2):400, 1955.
- Vaeth, J. Gordon: **200 miles up**. 2nd ed. N. Y., Ronald Press, 1955. 261 p. Price, \$5.00. Review by E. P. Martz in *Physics Today*, N. Y., 9(3):20, March 1956.
- Wisniewski, Wacław: **Atlas opadów atmosferycznych w Polsce 1891-1930** [Atmospheric precipitation atlas of Poland, 1891-1930]. Warsaw, Państwowy Instytut Hydrologiczno-Meteorologiczny, 1953. 51 p. 14 maps. Review by Janusz Paszyński in *Przegląd Geograficzny*, Warsaw, 27(1):151-154, 1955.

## B. METEOROLOGICAL ARTICLES APPEARING IN RECENTLY ISSUED PUBLICATIONS

*Acta Physica Polonica*, Warsaw, Vol. 3, No. 3, 1955

- Tison, L. J.: **Antoine Dobrowolski et l'expédition de la "Belgica,"** [Antoine Dobrowolski and the expedition of the "Belgica"], p. 101-102
- Smorsarski, Władysław: **La pression atmosphérique et la température du sol sous une couche de neige**, [Atmospheric pressure and the temperature of the soil under snow cover], p. 103-109
- Kajetanowicz, Zbigniew: **Observations hydrologiques dans un système homogène**, [Hydrological observation in a homogeneous system], p. 110-114
- Michnowski, Stanisław: **Wpływ wyładowań z ostroży na wartość natężenia pola elektrycznego przy powierzchni ziemi**, [Influence of point discharge currents on the earth's electric field], p. 115-130

- Gryglewicz, Zofia and Wojtczak, Bozenna: *Aktywność sejsmiczna w 1954 r.*, [Seismic activity in 1954], p. 131-137  
 Olczak, T.: [Obituary of] *Profesor Dr Tadeusz Banachiewicz, 1882-1954*, p. 138-141

## Vol. 3, No. 4, 1955

- Olczak, Tadeusz: *Über die Säkularänderungen des Erdmagnetismus in Polen im zeitraum von 1901,0 bis 1935,0*, [Secular variation of geomagnetism in Poland 1901-1935], p. 145-154  
 Czyzewski, O.; De Mezer, J. and Strzałkowski, A.: *Observations of solar radio radiation during the eclipse of June 30, 1954*, Pt. 1, p. 155-160  
 Teisseyre, Roman: *Optico-geometrical approximation for seismic waves in non-homogeneous media*, p. 161-166  
 Bac, Stanisław and Marciłonek, Stanisław: *La condensation de la vapeur d'eau dans le sable et dans le gravier en vue des conditions climatiques en Pologne*, [Condensation of water vapor in sand and in gravel under the climatic conditions of Poland], p. 176-194  
 Wierzbicka, Zuzanna: *Badanie promieniotwórczości  $\gamma$  i  $\beta$  próbek skał*, [Investigation of radioactivity of Y and B samples of rocks], p. 195-207  
 Przybyszewski, Eugeniusz: *O korelacji między charakterystykami magnetycznymi C i liczbami wolfa*, [Correlation between magnetic C characteristics and Wolf numbers], p. 208-212

## Akademii Nauk SSSR, Izvestiia, Ser. Geofizicheskaiia, No. 6, Nov./Dec. 1955

- Sretenskii, L. N.: *Zadacha Koshi-Puassona dlia poverkhnosti razdela dvukh tekushchikh potokov*, [The Cauchy-Poisson method for the discontinuity surface between two streams], p. 505-513  
 Timofeev, M. P.: *K teorii advektivnykh tumanov*, [Theory of advective fogs], p. 514-520  
 Brejdo, Ts. G.: *Issledovaniimekhnizma adsorbtsii ionov kapliami vody*, [Investigation of the mechanics of adsorption of ions by water drops], p. 521-528  
 Krasnogorskaia, N. V.: *Fotoelektricheskii metod issledovaniia raspredeleniia razmerov chastits osadkov*, [Photoelectrical method of investigating the size distribution of particles of precipitation], p. 529-537  
 Laikhtman, D. L.: *O fizicheskikh printsipakh normirovaniia orosheniia*, [Physical principles of the regulation of irrigation], p. 540-546  
 Shvets, M. E.: *O kondensatsii vodianogo para v atmosfere*, [Condensation of water vapor in the atmosphere], p. 547-551  
 Krylov, P. A.: *Aktinometr Mikhel'sona kak absoliutnyi pribor*, [The Michelson actinometer as an absolute instrument], p. 552-556  
 Ivanov, A. A.: *Izmenchivost' vetrovykh voln morei i okeanov*, [The variability of wind waves in seas and oceans], p. 557-560

## Akademii Nauk SSSR, Izvestiia, Ser. Geofizicheskaiia, No. 1, Jan. 1956

- Kazanskii, A. B. and Monin, A. S.: *Turbulentnost' v prizemnykh inversiiakh*, [Turbulences in inversions near the ground], p. 79-86  
 Brejdo, Ts. G.: *Adsorbtsiia ionov kapliami vody v potoke vozdukh*, [Adsorption of ions by water drops in an air current], p. 87-91  
 Muchnick, V. M. and Shmukler, A. Kh.: *K teorii grozy Vorkmena-Reinoldsa*, [Thunderstorm theory of Workman and Reynolds], p. 112-113  
 Litvinov, I. V.: *O spektre dozhdiia*, [Rain spectrum], p. 114-116  
 Ivanov, A. A.: [Review of] *Sverdrup, H. and Munk, W.: Veter, volnenie i zyb': teoreticheskie osnovy prognoza*, [Wind, sea and swell: theoretical foundations of forecasting], p. 117-118

## Akademii Nauk SSSR, Geofizicheskii Institut, Trudy, No. 22(149), 1954

- Podolskii, A. S.: *K voprosu o barometricheskom nivelirovanii*, [Barometric leveling], p. 117-126

## No. 23(150), 1954

- Kuznetsov, E. S.: *Vychislenie koeffitsientov pogloshcheniia vodianogo para pri otkloneniakh ot zakona Buge*, [Calculation of the absorption coefficient of water vapor in the case of departure from the Bouguer Law], p. 3-25  
 Kuznetsov, E. S.: *O pogloshchenii radiatsii solntsa zemnoi atmosferoi*, [Absorption of solar radiation by the earth's atmosphere], p. 26-64

- Feigel'son, E. M.: **Pogloshchenie solnechnoi energii v atmosfere pri nalichii oblakov**, [Absorption of solar energy in the atmosphere in the presence of clouds], p. 65-91
- Feigel'son, E. M.: **Opreделение vodnosti oblakov po ikh rasseivaiushchei sposobnosti**, [Determination of water content of clouds by their scattering], p. 92-105
- Feigel'son, E. M.: **Opreделение vodnosti i vlazhnosti oblakov po pogloshcheniiu luchistoi energii**, [Determination of water content and humidity of clouds by absorption of solar energy], p. 106-118
- Malkevich, M. S.: **K voprosu o zashchite rastenii ot zamorozkov dymovymi zavesami**, [Protection of plants from frosts by smoke screens], p. 119-133
- Krasikov, P. N. and Smirnov, N. S.: **Primenenie dymov dlia zashchity tsytusovykh kul'tur ot zamorozkov**, [Use of smoke to protect citrus plants from frost], p. 134-151

## No. 24(151), 1954

- Obukhov, A. M.: **Statisticheskoe opisanie nepreryvnykh polei**, [Statistical description of continuous fields], p. 1-42
- Krechmer, S. I.: **Metodika izmereniia mikropul'satsii skorosti vetra i temperatury v atmosfere**, [Method of measuring micropulsations of wind velocity and temperature in the atmosphere], p. 43-111
- Iaglom, A. M.: **Ob uchete inertsi meteorologicheskikh priborov pri izmereniiakh v turbulentnoi atmosfere**, [Calculation of the inertia of meteorological instruments during measurements in a turbulent atmosphere], p. 112-162
- Monin, A. S. and Obukhov, A. M.: **Osnovnye zakonomernosti turbulentnogo peremeshivaniia v prizemnom sloe atmosfery**, [Basic laws of the turbulent mixing in the layer of the atmosphere near the ground], p. 163-187

## No. 25(152), 1954

- Bonchkovskii, V. F.: **Izmeneniia gradienta elektricheskogo potentsiala atmosfery kak odin iz vozmozhnykh predvestnikov zemletriasenii**, [Change in the atmospheric electrical potential gradient as one of the possible precursors of earthquakes], p. 192-206

## American Geophysical Union, Transactions, Vol. 37, No. 1, Feb. 1956

- Zmuda, Alfred J.: **Limiting form of Taylor series used in extrapolating components of the geomagnetic intensity**, p. 9-12
- Chiu, Wan-cheng and Rib, Louis N.: **Rate of dissipation of energy and the energy spectrum in a low-speed turbulent jet**, p. 13-26
- Van Dorn, Wm. G.: **A portable Tsunami recorder**, p. 27-30
- Saito, Yasukazu: **Theory of the transient state concerning upwelling and coastal current**, p. 38-42
- Penman, H. L.: **Estimating evaporation**, p. 43-46
- Bottomley, G. A.: **Free oscillations of Lake Wakatipu, New Zealand**, p. 51-55
- Heidel, S. G.: **Progressive lag of sediment concentration with flood waves**, p. 56-66
- Scott, V. H.: **Relative infiltration rates of burned and unburned upland soils**, p. 67-69
- Flaxman, Elliott M. and Hobba, Robert L.: **Discussion of [their]: Some factors affecting rates of sedimentation in the Columbia river basin**, p. 110-112

## American Meteorological Society, Bulletin, Vol. 37, No. 3, March 1956

- Havens, James M. and Baum, Werner A.: **Frequency distributions of predominant tropopause heights along 80°W in summer**, p. 87-93
- Increased demands for water worry U. S. experts**, p. 93
- Warner, J. and Bigg, E. K.: **Effects of air temperature and pressure on the decay of silver iodide**, p. 94-95
- Neumann, Gerhard: **Notes on the horizontal circulation of ocean currents**, p. 96-100
- Professor Rossby cited as outstanding scientist**, p. 100
- Hosler, Charles R.: **A study of easterly waves in the Gulf of Mexico**, p. 101-107
- Myers, R. F.: **A weather information telemeter system**, p. 108-117
- Robert Kimble Souter**, p. 117
- Dr. Greenleaf Whittier Pickard**, p. 117
- Rand, William M., Jr.: **Dewey and Almy Chemical Company—manufacturers of meteorological balloons**, p. 118-120

- Kaplan, Henry G.: *An analysis of the freezing precipitation situation of December 10-11, 1954*, p. 121-124  
**Illinois groups highlight Society's midwest activities**, p. 125-126

Vol. 37, No. 4, April 1956

- Foster, Donald S. and Bates, Ferdinand C.: *A hail size forecasting technique*, p. 135-141  
 Penndorf, Rudolf: *Luminous reflectance (visual albedo) of natural objects*, p. 142-144  
 Ward, Neil B.: *Temperature inversion as a factor in formation of tornadoes*, p. 145-151  
 [Obituary of] The Rev. James B. Macelwane, p. 151  
 Tepper, Morris and Eggert, William E.: *Tornado proximity traces*, p. 152-159  
 Schultz, Herbert B. and Brooks, Frederick A.: *A spot climate recorder*, p. 160-165  
 Stecker, Ernest J.: *Advanced meteorological-instrument development in the Beckman and Whitley organization*, p. 166-169  
 Dean, Gordon A. and Palmer, C. E.: *The need for upper wind observations on the equator*, p. 170-171  
**Problems of tropics studied at Ceylon**, p. 171  
 American Meteorological Society: *Joint 144th National Meeting of the A.M.S. and the 37th Annual Meeting of the American Geophysical Union (Section of Meteorology)*, Wash. D. C., April 30-May 4, 1956, p. 172-187  
**News from our Branches**, p. 188-190

*Australian Journal of Physics*, Melbourne, Vol. 8, No. 3, Sept. 1955

- Loughhead, R. E.: *Hydromagnetic stability of a current layer*, p. 319-328  
 Ellyett, C. D. and Roth, K. W.: *Radar determination of meteor showers in the southern hemisphere*, p. 390-401

Vol. 8, No. 4, Dec. 1955

- Moran, P. A. P.: *Statistical design of an experiment to test the stimulation of rain*, p. 440-448  
 Christiansen, W. N. and Warburton, J. A.: *The distribution of radio brightness over the solar disk at a wavelength of 21 centimetres, Pt. 3, The quiet sun: two-dimensional observations*, p. 474-486  
 Swarup, G. and Parthasarathy, R.: *Solar brightness distribution at a wavelength of 60 centimetres, Pt. 1, The quiet sun*, p. 487-497  
 Slee, O. B.: *Apparent intensity variations of the radio source Hydra-A*, p. 498-507  
 Harvey, J. A.: *Movement of sporadic E ionization*, p. 523-534  
 Taylor, R. J.: *Some observations of wind velocity autocorrelations in the lowest layers of the atmosphere*, p. 535-544  
 Csanady, G. T.: *Dispersal of dust particles from elevated sources*, p. 545-550  
 Thomas, J. A. and Svenson, A. C.: *Lunar tide in sporadic E at Brisbane*, p. 554-556  
 Hopper, V. D. and Laby, Jean E.: *Electron background in imported G5 emulsions*, p. 557-562

*Ciel et Terre*, Brussels, Vol. 71, No. 11/12, Nov./Dec. 1955

- Defrise, P.: *Notions de mecanique de l'atmosphere (Elements de meteorologie, chapitre V)*, [Notions of mechanics of the atmosphere (Elements of meteorology, Ch. 5)], p. 365-396  
 Sneyers, R.: *Le temps en 1954*, [Weather in 1954], p. 397-413  
 Dogniaux, R.: *Congres international pour l'utilisation de l'energie solaire, Tucson et Phoenix-Arizona, U.S.A., Novembre 1955*, [International congress for the utilization of solar energy, Tucson and Phoenix, Arizona, Nov. 1955], p. 426-427  
 Sneyers, R.: *Le temps en Septembre [and] en Octobre, 1955*, [Weather in Sept. and Oct. 1955], p. 437-440

*Ecology*, Durham, North Carolina, Vol. 37, No. 1, Jan. 1956

- Shanks, Royal E.: *Altitudinal and microclimatic relationships of soil temperature under natural vegetation*, p. 1-7  
 Oosting, H. J. and Hess, D. W.: *Microclimate and a relic stand of *Tsuga Canadensis* in the lower Piedmont of North Carolina*, p. 28-39  
 Potter, Loren D.: *Yearly soil temperatures in eastern North Dakota*, p. 62-70  
 Fowler, Robert L.; Desrosiers, Russell and Hopp, Henry: *Evaluation of certain factors affecting the yield of cacao in Ecuador*, p. 75-81

Goodnight, Clarence J. and Goodnight, Marie L.: Some observations in a tropical rain forest in Chiapas, Mexico, p. 139-150

**lőjárás, Budapest, Vol. 59, No. 4, July/Aug. 1955**

Pinter, Laszlo: Az őszi búza termésátlagának összefüggése a főbb meteorológiai tényezőkkel, [Correlation between the average crop of winter wheat and the principal meteorological factors], p. 193-203

Koo, Chen-Chao: A Tibeti-fennsík dinamikus hatása a keletázsiai légkörzésre, [Dynamic effect of the Tibet plateau on the atmospheric circulation over East Asia], p. 204-211

Péczely, György: A makroszinoptikus helyzetek tipizálása Magyarország számára, [Typing of large scale synoptic situations for Hungary], p. 212-217

Kiss, István: Az aerob és anaerob jellegű légzés vizsgálatának szerepe az időérzékenység kutatásában, [Role of the study of aerobic and anaerobic breathing in weather sensitivity research], p. 218-223

Czelnai, L. Rudolf: A Balaton partmenti cirkulációs rendszerének néhány sajátossága, [A few peculiarities of the circulation over the shore-line of Lake Balaton], p. 224-229

Andó, Mihály: Adatok a homoktalaj hőmérsékletéhez, [Data on sand soil temperature], p. 230-234

Kiss, Árpád: Adatok a futóhomok mikroklímájához, [Data on the microclimate of quicksand], p. 235-238

Péczely, György: A Magyar Meteorológiai Társaság szegedi vándorgyűlése, [Meeting of the Hungarian Meteorological Society in Szeged], p. 239-242

Bacsó, Nándor: Csehszlovák meteorológusok látogatása, [Visit of Czechoslovak meteorologists], p. 247

Ozorai, Zoltán: Rendkívüli időjárási események Júliusban—, [Unusual weather development in July (1955)], p. 247

Bodolai, István: A csapadékképződés aerológiai-szinoptikai feltételei, [Synoptic aerological conditions of precipitation formation], p. 248-249

K., J.: Láng Sándor kandidátusi értekezésének nyilvános vitája, [Public debate on the thesis (Ph.D.) of S. Lang], p. 249

Aujeszky, László: Augusztusi havaseső Magyarországon, [Rain mixed with snow in August in Hungary], p. 250

Békeffy, József: Nemzetközi geofizikai év 1957-58-ban, [International Geophysical Year, 1957/1958], p. 250-251

Czelnai, L. Rudolf: A Meteorológiai Világszervezet a szélenergia feltárásáért, [World Meteorological Organization for wind energy research], p. 251-252

Vancsó, Imre: Ritka szivárvány, [Unusual rainbow], p. 252

Bacsó, Nándor: Rendkívüli felhőszakadás Budapesten 1955. Augusztus 14-én, [Extraordinary cloudburst in Budapest, Aug. 14, 1955], p. 252-253

Vancsó, Imre: Fönszerűkiszáradás Tapolcán, [Föhn-like drying in Tapolca], p. 253

A., R. and J., K.: Mezezetes villámcsapás Budán 1778 Július 29-én, [Remarkable lightning stroke in Buda on July 29, 1778], p. 253-255

Czelnai, L. Rudolf: Az Energiagazdálkodási Tudos-mányos Egyesület Szélenergia Munkabizottságának megalakulása, [Establishment of a Work Committee on Wind Energy at the Scientific Society for Energy Supply], p. 255-256

Bacsó, Nándor: Felhőtölcsérek Budapest fölött 1955. Augusztus 15-én, [Funnel clouds over Budapest, Aug. 15, 1955], p. 256

**Japan. Central Meteorological Observatory, Tokyo, Memoirs of Industrial Meteorology, Vol. 19, No. 1, Dec. 1955**

Hayami, I. and Oka, C.: On the "Shiraho" damage of paddy rice caused by the Typhoon June (No. 5412) in Ōita Prefecture, p. 1-9

Ōkubo, I.: On salty wind injury in Hakodate City and its vicinity, caused by the "Typhoon 5415," September 1954, p. 11-14

Ohashi, K.: On the effect of making smoke screens for protection against frost, p. 15-17

Fukushima, Japan. Weather Station: On the nocturnal temperature variation surrounding in the orchards on a frosty night, pt. 1, p. 19-30

Maruyama, E. and Takasuna, M.: On the arrangement for measuring the thermal diffusivity, p. 31-34

Kusakabe, M.: On the soil moisture observation at Ōwada, pt. 2, p. 35-50

Japan. Central Meteorological Observatory, Fukuoka District: Meteorological study on large-scale generation of electricity by wind power, pt. 1, p. 51-70

Koyano, M.: Flowering dates of the cherry (*P. yedoensis*) in 1955, p. 71-76

**Journal of Glaciology, London, Vol. 2, No. 19, March 1956**

- Nusser, Franz: **Problems of sea ice research**, p. 619-623  
 Haefeli, R. and Brentani, F.: **Observations in a cold ice cap**, Pt. 2, p. 623-630  
 Gold, Lorne W.: **New snow and ice research laboratory in Canada**, p. 635-637  
 Sweeting, Marjorie and Groom, Gillian: **Notes on the glacier fluctuations in Bünsow Land and central Vestspitsbergen**, p. 640-641  
 Galloway, R. W.: **Mechanical measurement of glacier motion**, p. 642-644  
 Mercer, J. H.: **The Grinnell and Terra Nivea ice caps, Baffin Island**, p. 653-656  
 Loewe, F.: **Contributions to the glaciology of the Antarctic**, p. 657-665  
 Harrison, A. E.: **Glacial activity in the western United States**, p. 666-668  
 Hubley, Richard C.: **Glaciers of the Washington Cascade and Olympic mountains; their present activity and its relation to local climatic trends**, p. 669-674  
 Harrison, A. E.: **Fluctuations of the Nisqually Glacier, Mt. Rainier, Washington, since 1750**, p. 675-683

**Journal of Meteorological Research, Tokyo, Vol. 7, No. 10, Dec. 1955.**

- Ito, S.: **Dynamical study on the development of trough (Studies on the divergence analysis Pt. 1)**, p. 609-615  
 Neyama, Y.: **The relationship between the change of tropopause height at Marcus and the rainfall in West Japan**, p. 616-623  
 Saito, R. and Igarashi, K.: **The harmonic analysis of tidal observations by IBM machines**, p. 624-632  
 Ogata, Y. and Tamura, Y.: **The sea fog over the open sea**, pt. 1, p. 633-642  
 Yoshino, I.: **On the cold trough with the heavy rain in July 1952**, p. 643-649  
 Yoshida, S. and Saito, K.: **Some experiments on totalizers**, p. 650-662  
 Kondo, G. and Uchikawa, K.: **Kite-balloon observations of atmospheric electricity in the lower atmosphere**, p. 663-670  
 Ito, S.: **A note on the divergence equation**, p. 671  
 Nakayama, A.: **On the so-called secondary orographic rainfall**, pt. 4, p. 672-677  
 Nakamura, I.: **On the distribution of snow cover at Hida Region**, p. 678-682  
 Kasamura, Y.: **On the local föhn observed at Ooita**, p. 683-685

**Vol. 7, No. 11, Dec. 1955**

- Takahashi, K. and Iida, M.: **Classification of 5-day mean 700-mb anomaly charts for the Eastern Asia**, p. 687-695  
 Asakura, T.: **The relationship of anomaly chart of 5-day mean 700-mb height to anomaly of 5-day mean surface temperature**, p. 696-704  
 Hirose, M.; Okuta, M. and Asakura, T.: **Relationship of 5-day mean 700-mb anomaly pattern to amount of precipitation**, p. 705-710  
 Arai, Y. and Nakamura, N.: **The relationship between 5-day mean 700-mb anomaly chart and the weather change at the surface**, p. 711-716  
 Sugiura, S.: **Forecasting of heavy rainfall by premigram**, p. 717-725  
 Nagao, T.: **Characters of weather group and its application to long-range weather forecasting**, pt. 9, p. 726-733  
 Inoue, R. and Sanbongi, R.: **On the catching characteristics of a snow gage**, p. 734-739  
 Hisamoto, S.: **Meteorological high tide in Tokyo due to typhoons**, pt. 2, p. 740-745  
 Ogawara, M.: **A method of testing the difference between Poisson parameters and its application to the observation method of radioactivity count number**, p. 746-747  
 Kido, T.: **On the dense fog at Ueno**, pt. 2, p. 748-750  
 Seki, K.: **On the forecasting of avalanche in Hokuriku District**, pt. 1, p. 751-753

**Vol. 7, No. 12, Jan. 1956**

- Ando, M.: **Study of seasonal forecasting with reference to the Tohoku District (The general circulation observed from the variations of the mass of air over the Northern Hemisphere, Pt. 1)**, p. 755-764  
 Watanabe, K.: **The utility of dropsonde data observed in typhoon center**, p. 765-769  
 Saito, R.: **On the homogeneity of observed values of wind speed**, p. 770-778  
 Kano, M.: **Does the forced diffusion of water vapor due to the electric field of a small charged droplet affect on its growth?**, p. 779-784  
 Akita, I.: **On the gust occurred in the Northern Kanto Plain on February 5, 1944**, p. 785-789  
 Yajima, Y.: **Pressure effect on thermometers**, Pt. 2, p. 790-793

- Daidōji, S.: **Weather at the vicinity of Torishima under the winter monsoon**, p. 794-796  
 Narita, G. and Masuyama, R.: **On the influence of topography upon the wind direction at Wakkanai**, p. 797-799  
 Seki, K.: **On the forecasting of avalanche in Hokuriku District, Pt. 2**, p. 800-810

**Low Temperature Science, Ser. A, Physical Sciences, Sapporo, Japan, Vol. 14, 1955**

- Kuroiwa, Daisuke: **Growth of snow crystals in supercooled cloud: on the role of minute water droplets**, p. 1-13  
 Ono, Taketoshi: **On the effect of electric field on the crystallization of minute water droplets suspended in chloroform**, p. 15-24  
 Tabata, Tadashi: **A measurement of the visco-elastic constants of sea-ice**, p. 25-31  
 Ishida, Tamotsu and Shimizu, Hiroshi: **Determination of the air flow resistance through snow layer, Pt. 1**, p. 33-42  
 Huzioka, Tosio and Kinoshita, Seiiti: **Friction between snow and a model sledge (Studies on the resistance of snow sledge, Pt. 3)**, p. 43-54  
 Yosida, Zyungo: **A study on the determination of liquid water content of snow by centrifuge**, p. 55-75  
 Kojima, Kenji: **Viscous compression of natural snow-layer, Pt. 1**, p. 77-93  
 Kinoshita, Siti: **Break-down of snow by impulsive force, Pt. 1**, p. 95-116  
 Tabata, Tadashi and Suzuki, Yosio: **Studies on recording fog water, Pt. 2**, p. 117-123  
 Mastumura, Nobuo: **On the ratio of Cl-Mg in fog water (preliminary report)**, p. 125-133  
 Oura, Hirobumi: **Torsional test on a pipe of hard Polyvinylchloride at low temperature**, p. 135-148  
 Kusunoki, Kou: **Observations on the horizontal and vertical distribution of chlorinity of sea-ice**, p. 149-150  
 Suzuki, Yosio: **Observations of ice crystals formed on sea surface**, p. 151-154  
 Kusunoki, Kou: **Recent advances in the study of sea ice**, p. 155-184

**Low Temperature Science, Ser. B, Biological Sciences, Sapporo, Japan, Vol. 13, 1955**

- Aoki, Kiyoshi: **Analysis of the freezing process of living organisms, pt. 12, The freezing curve of the twig of mulberry tree**, p. 1-12  
 Aoki, Kiyoshi: **On the artificial hardening of the twig in mulberry tree**, p. 13-20  
 Sakai, Akira: **The relationship between the developmental process and the frost hardiness of the mulberry tree**, p. 21-32  
 Sakai, Akira: **The seasonal changes of the frost hardiness and the physiological station of the cortical parenchym cells**, p. 33-42  
 Sakai, Akira: **A method for testing the survival of the twig**, p. 43-50  
 Aoki, Kyoshi: **The initiation of the freezing in insect (preliminary note)**, p. 51-58  
 Nei, Tokio; Nakagawa, Isamu and Mori, Genji: **Mechanism of drying during the freezing-drying: analysis of drying process by estimating the water content of materials (preliminary note)**, p. 59-65

**Meteorological Magazine, Vol. 85, No. 1006, April 1956**

- James Durward, C.M.G., M.A., p. 97  
 Clarkson, L. S.: **Variation with time of winds at 40,000 ft. and 50,000 ft. over Singapore**, p. 99  
 Booth, R. E.: **Weather of 1955**, p. 101  
 Hay, R. F. M.: **Air temperatures during snowfall at Ocean Weather Station I**, p. 107  
 Fritz, S.: **Opacity of the atmosphere**, p. 110  
 Watkins, L. H.: **Variation between measurements of rainfall made with a grid of gauges**, p. 120  
**Changes in B.B.C. weather forecasts**, p. 121  
 Hicks, J. A.: **Exceptionally severe thunderstorm**, p. 122  
**Beiträge zur Physik der Atmosphäre**, p. 123  
 Craddock, J. M.: [Review of] L. Mavridis: **On the mathematical expression of the annual variation of temperature**, p. 124

**Monthly Weather Review, Wash., D. C., Vol. 84, No. 1, Jan. 1956**

- Colón, José A.: **On the formation of Hurricane Alice, 1955: with notes on other cold-season tropical storms**, p. 1-14  
 Mitchell, J. Murray, Jr.: **Strong surface winds at Big Delta, Alaska: an example of orographic influence on local weather**, p. 15-24  
 Klein, William H.: **The weather and circulation of Jan. 1956: a month with a record low index**, p. 25-34

McQueen, Henry R. and Keith, Hubert C.: *The ice storm of Jan. 7-10, 1956 over the Northeastern United States*, p. 35-45

**Priroda**, Moscow, Vol. 44, No. 11, Nov. 1955

Grigor'ev, A. A. and Abramov, L. S.: *Puti razvitiia sovetskoi geografii: po itogam vtorogo s'ezda Geograficheskogo obshchestva*, [Paths of development of Soviet geographical results of 2nd Congress of the Geographical Society of the U.S.S.R.], p. 47-55

Prokhaev, V. I.: *Termicheskie anomalii v dolinakh Zhigulevskikh gor*, [Thermal anomalies in the valleys of the Zhigulev mountains], p. 89-91

Moiseev, A. P.: *Slozhnoe galo redkikh form*, [Complex halo of unusual forms], p. 114

Gorlenko, M. V.: *Primenenie solnechnoi energii dlia bor'by s pyl'noi golovnei pshenitsy*, [Application of solar energy to prevent wheat rust], p. 115-116

Vol. 44, No. 12, Dec. 1955

Kalashnikov, A. G.: *Mezhdunarodnyi Geofizicheskii God*, [International Geophysical Year], p. 1-12

Seifer, A. L.: *Morskaia korroziiia metallov*, [Marine corrosion of metals], p. 78-79

Patalev, A. V.: *Morozoboinnye treshchiny v gruntakh*, [Frost fissures in soils], p. 84-85

Nikolaev, V. A. and Rauner, Iu. L.: *Rozy vetrov na snegu*, [Wind roses on snow], p. 109-111

Zavarina, M. V.: *Kholodnyi sukhovet*, [Cold dry-wind], p. 110

Shishkina, L. A.: *Iskluchitel'nyi gololed*, [Exceptional glaze], p. 113-114

Sapozhnikova, S. A.: *O bor'be s neblagopriiatnymi osobennostiami klimata*, [Prevention of unfavorable climatic characteristics], p. 121-122

Vol. 45, No. 1, Jan. 1956

Burkhanov, V. F.: *Sovetskaia Antarkticheskaia ekspeditsiia*, [The Soviet Antarctic Expedition], p. 9-12

Al'pert, Ia. L.: *Ionosfera*, [The ionosphere], p. 13-23

Khromov, S. P.: *Kolebaniia klimata i sovremennoe poteplenie*, [Climatic variations and contemporary warming up], p. 24-34

Alpers, V. V.: *Iadernye chastitsy v fotograficheskoi emul'sii*, [Nuclear particles and photographic emulsions], p. 83-86

Alekseeva, K. N.: *Sled molnii*, [Traces of lightning], p. 115

Dolgoshov, V. I.: *Osobennosti ianvaria*, [Peculiarities of January], p. 127-128

**Przegląd Meteorologiczny i Hydrologiczny**, Warsaw, Vol. 8, No. 3/4, 1955

Milata, Władysław: *Temperatura powietrza w Krakowie*, [Air temperature in Cracow], p. 199-209

Milata, Władysław: *Synoptyka wielkich opadów atmosferycznych*, [Synoptic aspects of extensive precipitation], p. 201-217

Zakrent, Stefan: *Wyniki pomiarów natężenia promieniowania słonecznego w Zakopanem I na Kasprowym wierchu*, [Results of measurements of the intensity of solar radiation at Zakopane and at Kasprowy Wierch], p. 219-224

Liana, Franciszek: *Pomiary promieniowania nadfioletowego w Zakopanem I na Kasprowym Wierchu*, [Measurements of ultra-violet radiation at Zakopane and at Kasprowy Wierch], p. 225-226

Michalczewski, Jerzy: *Usłonecznienie i zachmurzenie Zakopanego*, [Cloud amount and duration of sunshine at Zakopane], p. 227-233

Orlicz, Michał and Orliczowa, Jadwiga: *Inwersje temperatury na północnym skłonie Tatr*, [Temperature inversions over the northern slopes of the Tatra mountains], p. 235-255

Chomicz, Kazimierz: *Deszcz ulewne w Zakopanem*, [Showers at Zakopane], p. 257-263

Kimickiewicz, Eugeniusz: *Z dziejów powstania i rozwoju służby meteorologicznej dla obsługi turystyki*, [Contribution to the history of the establishment and development of meteorology in the tourist service], p. 265-270

Winid, Bogodar: *Międzynarodowe bibliografie meteorologiczne*, [International meteorological bibliography], p. 276-280

**Revista de Geofísica**, Madrid, Vol. 14, No. 56, Oct./Dec. 1955

Oriol Cardús, J.: *Sondeos ionosféricos*, [Ionospheric soundings], p. 285-312

Rodríguez Franco, Pedro: *Notas sobre las corrientes de chorro*, [Notes on the jet stream], p. 313-346

- Font Tullot, Inocencio: **Efectos de las depresiones frías en el tiempo de las Islas Canarias**, [Effects of cold lows on the weather of the Canary Islands], p. 347-362
- Oriol Cardús, J.: **Nota relativa a la actividad solar y geomagnética**, [Note on solar and geomagnetic activity], p. 363-372
- Gaibar-Puertas, C.: **Actividades y progresos de la E.A.E.G.**, [Activities and progress of the European Association of Exploration Geophysicists], p. 373-393
- Sans Huelin, Guillermo: **Ciclo de conferencias relativas al Año Geofísico Internacional 1957-1958**, [Cycle of conferences on the 1957/1958 International Geophysical Year], p. 395-409
- Due Rojo, Antonio: **La Unión Geofísica Americana**, [The American Geophysical Union], p. 411-415
- Sans Huelin, Guillermo: **Desarrollo de las técnicas experimentales por medio de cohetes**, [Development of experimental techniques by means of rockets], p. 417-419

**Revista Meteorológica**, Montevideo, Vol. 13, No. 47, Dec. 1954

- Jagsich, Juan: **Regimen hídrico de nuestra atmósfera**, [Hydrologic cycle of the atmosphere], p. 73-104

Vol. 13, No. 48, June 1955

- Orecchia Buro, Helido: **Modalidad normal horaria de la velocidad del viento en el clima de Montevideo**, [Normal hourly regime of wind velocity in the climate of Montevideo], p. 4-13
- Bergeiro Hargain, José María: **Actualización de los valores climatológicos normales, correspondientes a Montevideo**, [Compilation of the normal climatological values of Montevideo], p. 15-24
- Battioni Chiarino, J. A.: **Definición y descripción de meteoros**, [Definition and description of meteors], p. 25-36

**Revista Orientación Meteorológica**, Montevideo, No. 8, Sept. 1955

- Ricci, Juan Carlos: **Lo que pude comprobar**, [What we can prove], p. 3-4
- Bergeiro Hargain, José M.: **Hacia el pronóstico popular del tiempo atmosférico**, [Looking forward to popular forecasting of atmospheric weather], p. 7-15
- Burstin, Jacobo: **Cultura meteorológica en el interior**, [Diffusion of meteorological knowledge in the interior], p. 19-20
- Berta, Alberto Jorge: **Pararrayos campesino**, [Lightning rods for the farm], p. 21-22
- Ferrer, Manuel Silva: **Hibernación artificial**, [Artificial hibernation], p. 23-26
- Piriz, Nestor A.: **Veleta zig-zag**, [Zig-zag wind vane], p. 27-28
- Avegno, Carlos Alberto: **Red de observadores**, [Observers network], p. 29-31
- Berta, Alberto Jorge: **Un aparato útil: electroscopio**, [The electroscope: a useful apparatus], p. 33-35
- Mattos, Roque R.: **Tiempo, clima y producción**, [Weather, climate and production], p. 38-40

**Rivista di Meteorologia Aeronautica**, Rome, Vol. 15, No. 2, April/June 1955

- Polli, Silvio: **I cicli climatici di 5,6 e 8,0 anni e la loro realtà fisica**, [Climatic cycles of 5.6 and 8.0 years and their physical reality], p. 3-12
- Palmieri, Sabino: **Il metodo di Fjörtoft per la preparazione delle topografie previste di 500 mb**, [The Fjörtoft method for the construction of prebaratic 500 mb. contour charts], p. 13-31
- de Pasquale, Oreste: **Idee ed applicazioni precorritrici di oltre 30 anni addietro sulle "correni a getto"**, [Anticipation of the Jet Stream concept and theory thirty years ago], p. 32-34
- Bernacca, Edmondo: **Il tempo in Italia nel trimestre gennaio-marzo 1955**, [Weather in Italy, Jan./March 1955], p. 35-37
- Morasca, Nicola: **A proposito del dispositivo per la indicazione e la registrazione continua del contenuto di acqua liquida di una nebbia o di una nube studiato da G. Fea**, [On the apparatus used by G. Fea for observation and continuous recording of liquid water content of fog or cloud], p. 38
- Bilancini, Raoul: [Obituary of] **Mario Tenani**, p. 63
- Bilancini, Raoul: [Obituary of] **P. Saverio Francesco Zanon**, p. 63-64
- Bilancini, Raoul: [Obituary of] **Augusto Schmauss**, p. 64
- Pellisari, L.: **L'Anno Geofísico Internazionale**, [International Geophysical Year], p. 65-66
- Pellisari, L.: **Due secoli di ricerche sulle cause del fulmine**, [Two centuries of research on the causes of lightning], p. 66-67

- Pellisari, L.: **Pioggia artificiale nel Madagascar**, [Artificial rainfall in Madagascar], p. 67-68
- Pellisari, L.: **Igrometri perfezionati per radiosonde**, [Hygrometers perfected for radiosonde], p. 68
- Pellisari, L.: **Contro le formazioni di ghiaccio sugli aerei**, [Prevention of ice formation on aeroplanes], p. 68-69
- Pellisari, L.: **Palloni sonda per segnalare i movimenti degli uragani**, [Balloon soundings indicate the movements of hurricanes], p. 69
- Pellisari, L.: **Un radar che segnala le formazioni temporalesche**, [A radar which indicates thunder storm formations], p. 69

Vol. 15, No. 3/4, July/Dec. 1955

- Serra, Antonio: **Su alcune caratteristiche stagionali delle correnti atmosferiche nell'alta troposfera e bassa stratosfera sull'isola di Sardegna e sul Mediterraneo occidentale**, [Some seasonal characteristics of the atmospheric circulation in the upper troposphere and the lower stratosphere over Sardinia and the western Mediterranean], p. 3-22
- Serra, Antonio: **Il vento medio nell'alta troposfera e nella bassa stratosfera in Sardegna**, [The mean wind in the upper troposphere and the lower stratosphere over Sardinia], p. 23-29
- Urbani, Marcello: **Su una classificazione di tipi di tempo in Europa**, [A classification of weather types in Europe], p. 30-37
- Paracchini, Salvatore: **"Compasso" per la determinazione pratica del vento geostrofico e per la ricerca delle distanze fra isobare o isoipse nelle normali carte del tempo al suolo e alle quote**, [A "compass" for practical determination of the geostrophic wind and for research on the distance between isobars or isohypses on ordinary weather maps for the surface and upper levels], p. 38-40
- Bernacca, Edmondo: **Il tempo in Italia nel trimestre Aprile-Giugno 1955**, [Weather in Italy April-June, 1955], p. 41-42

Western Snow Conference, Salt Lake City, April 19-21, 1954, Proceedings of the twenty-second annual meeting. pub. Oct. 1954

- Orville, Howard T.: **Aims and activities of the U. S. Advisory Committee on Weather Control**, p. 1-4
- Van Ornum, Delbert G.: **Long range weather forecasting**, p. 4-9
- Hales, J. Vern; Hoefler, Thomas E. and Peck, Eugene L.: **Evaluation of rain making experiments in Utah**, p. 10-18
- Langbein, W. G.: **How long should gaging stations be operated**, p. 19-26
- Somers, W. P.: **Statistical analysis of streamflow relationships**, p. 26-32
- Troxell, Harold C.: **The influence of ground-water storage on the runoff in Southern California**, p. 33-40
- Peck, Eugene L.: **Low winter streamflow as an index to short and long term carry-over effects in water supply forecasting**, p. 41-48
- Murray, William E.: **Some upstream aspects of the 1952 spring floods in Utah**, p. 48-54
- Boyer, Peter B.: **Heat exchange and melt of late season snow patches in heavy forest**, p. 54-70
- Craddock, George W.: **Water yield from snow as affected by consumptive water losses**, p. 70-77
- Bissell, L. M. and Earl, K. D.: **Volume inflow forecasting procedures, Hungry Horse reservoir in Montana**, p. 74-82
- Codd, A. R. and Nelson, M. W.: **Use of aircraft in snow surveying**, p. 83-85
- Koelzer, Victor A.: **Use of melt-season snow surveys**, p. 86-89
- Dean, W. W.; Frost, W. T. and Kuehl, D. W.: **Effect upon seasonal runoff forecasts of measurement errors in basic data**, p. 90-94

Wetter und Leben, Vienna, Vol. 7, No. 7, 1955

- Steinhauser, F.: **Über die Abhängigkeit der Tagesschwankung der Temperatur von der Sonnenscheindauer in Wien**, (The dependence of the daily variation in temperature at Vienna on sunshine duration), p. 141-151
- Piccardi, Giorgio: **Neue Resultate mit dem anorganischen Test zum Studium von Umwelteinflüssen—Ein vereinfachter Test (P-Test)**, [New results of an inorganic test for the study of environmental influences—a simplified test (P-test)], p. 151-152
- Piccardi, Giorgio and Danti, Mario: **Wirkung einer Metall-Abschirmung, ein biologischer Test**, (Action of a metal shield; a biological test), p. 152-154
- Heigel, Karl: **Erfahrungen mit der "Carbid-Methode" zur raschen Bestimmung der Bodenfeuchte**, [Experiments with the "Carbide-method" of quick determination of soil moisture], p. 154-156.

Untersteiner, N.: Sogwirkungen in einer Biwakhöhle im Hochgebirge, [Wind suction effects in a bivouac cave in the Alps], p. 156-157

etter und Leben, Vienna, Vol. 7, No. 8/11, 1955, Bericht über die internationale Tagung für Angewandte Meteorologie in Obertraun vom 19. bis 21. September 1955

Steinhauser, F.: Möglichkeiten und grenzen der modernen wettervorhersage, [Possibilities and limits of modern forecasting], p. 169-175

Reidat, R.: Was kann die meteorologie der technik bieten? [What can meteorology offer technology?], p. 176-185

Bruckmayer, F.: Bautechnik und meteorologische werte, [Construction methods and meteorological values], p. 186-193

Liebsch, F.: Die bedeutung des amtlichen wetterberichtes für den betrieb der Osterr. bundesbahnen, [Importance of official weather services for the operation of the Austrian national railroads], p. 194-195

Råstad, H.: Erfahrungen über vereisung von fernleitungen in Norwegischen gebirgen, [Experiences on icing of telephone wires in the Norwegian mountains], p. 196-199

Dirmhirn, I.: Himmelsstrahlung im bauwesen, [Sky radiation in building design], p. 200-201

Sauberer, F.: Über die bedeutung der strahlungsbilanzmessung für die bautechnik, [Importance of radiation balance measurement in the building industry], p. 201-202

Friedrich, W.: Praktische studien zum dämmerungsproblem, [Practical studies on the twilight problem], p. 202

Friedrich, W.: Das autobahnprojekt und die witterungsverhältnisse im Wienerwald, [Highway project and weather conditions in the Vienna woods], p. 203-205

Reidat, R.: Raumklimatische messungen in schulen, [Climatological measurements in schools], p. 205-206

Steinhauser, F.: Isoplethen der globalbeleuchtungsstärke in Wien, [Isopleths of global illumination intensity], p. 207

Undt, W.: Der tagesgang des raumklimas, [Daily variation of room climates], p. 207-209

Dirmhirn, Inge: Die reflektions auf den abschmelzvorgang der gletscher, [Effect of reflection on glacier ablation], p. 209

Fischmeister, V.: Bestimmung des wasserwertes einer schneedecke mit radioaktiven stoffen, [Determination of the water equivalent of snow cover with radioactive substances], p. 210-211

Grunow, J.: Zur definition und beobachtungstechnik von nebelfrostablagerungen, [Definition and observation technique of rime deposit], p. 211-212

Saar, R.: Meteorologisch-physikalische Beobachtungen in den Dachsteinrieseneishöhlen, Oberösterreich, [Physico-meteorological observations in the Dachstein giant ice caves in Upper Austria], p. 213-219

Morton, F.: Aus Hallstatts vorgeschichte (Kurzer auszug), [From the early history of Hallstatt], p. 220-221

Schnelle, F.: Die meteorologie hilft der land und forstwirtschaft, [Meteorology aids agriculture and forestry], p. 222

Ramsauer, B.: Agrarmeteorologie und kulturtechnik, [Agrometeorology and agricultural engineering], p. 236-240

Aulitzky, H.: Die bedeutung meteorologischer und kleinklimatischer unterlagen für aufforstungen im hochgebirge, [The importance of meteorological and microclimatic bases for alpine afforestation], p. 241-252

Eckel, O.: Temperaturprobleme der Alpenseen, [Temperature problems in the Alpine lakes], p. 253-256

Sauberer, F.: Über die agrarmeteorologie und die phänologie in Österreich, [On agrometeorology and phenology in Austria], p. 257-258

Reuter, H.: Zur praxis der frostprognose, [Practical frost forecasting], p. 258-259

Jesser, E.: Erfahrungen mit der 14-uhr temperatur bei der bodenschätzung in Österreich, [Experiences in the use of 14-H temperature in soil evaluation in Austria], p. 259-260

Steinhauser, F.: Flächenanteil bestimmter niederschlagsstufen in Österreich, [Areal distribution of specified precipitation amounts in Austria], p. 261-262

Grunow, J.: Erfassung zusätzlicher niederschlagsmessungen am waldboden aus nebelablagerungen, [Measurement of additional precipitation from fog deposits on forest soil], p. 262-263

Saar, R.: Zur klimatologischen erforschung der karsthochflächen, [Climatological investigation of karst plateaus], p. 263

Mörkofer, W.: Gesichtspunkte der kurortklimatologie, [Viewpoints on health resort climatology], p. 264-267

- Poppinger, J.: **Fremdenverkehr und klima**, [Climate and the tourist trade], p. 268-269
- Ollinger, H.: **Die verwertung klimatischer erkenntnisse in der landesplanung**, [The use of climatological concepts in regional planning], p. 270-274
- Gregor, A.: **Ein behelf zur klassifikation des expositions-klimas**, [An aid for the classification of exposure climate], p. 275-276
- Trauner, L. and Goldberg, J.: **Vorschlag zur klimatischen bewertung von kurorten**, [A suggestion for the climatic evaluation of health resorts], p. 276-277
- Steinhäuser, F.: **Karten der sonnenscheindauer in Österreich in den einzelnen jahreszeiten**, [Seasonal charts of sunshine duration in Austria], p. 277-278
- Weiss, E.: **Luftverunreinigung durch industrieabgase in Linz**, [Atmospheric pollution by industrial waste gases in Linz], p. 278
- Undt, W.: **Die praktische zusammenarbeit bei der erforschung des heilklimas**, [Practical cooperation in research on health climate], p. 279-280
- Pasic, H.: **Mikroklimatische untersuchungen im kurort Srebrenica (Ostbosnien)**, [Microclimatic research in the health resort Srebrenica, East Bosnia], p. 281-282
- Reifferscheid, H.: **Prüfung der wirksamkeit von luftdesinfektionsmitteln mit hilfe von konimetrischen keimgehaltsbestimmungen**, [Testing the effectiveness of air disinfectants by means of konimetric germ-content determination], p. 282-283
- Reifferscheid, H.: **Untersuchungen der wärmehaltefähigkeit einiger natürlicher und künstlicher faserstoffe**, [Investigations of heat capacity of some natural and artificial fiber fabrics], p. 283-284
- Sauberer, F.: **Zum thema kleinklimatologie und landesplanung**, [On microclimatology and regional planning], p. 284-285

**Yugoslavia. Hidrometeorološka Služba, Vesnik, Vol. 4, No. 3/4, July/Dec. 1955**

- Perović, M.: **Svetska Meteorološka organizacija, II, Kongres organizacije**, [World Meteorological Organization: Organization of the Second Congress], p. 75-79
- Ratković, B.: **Agrometeorološka aktivnost u Zapadnoj Nemačkoj i Francuskoj**, [Agrometeorological activity in West Germany and France], p. 79-87
- Petrović, R.: **Izveštaj o radu u Nemačkoj i Švajcarskoj, 1954/55**, [Account of a journey in Germany and Switzerland, 1954/55], p. 88-95
- Radošević, M. D.: **Svetleće telo u atmosferi nad Jugoslavijom, 25. Oktobra 1954**, [Luminous object in the atmosphere over Yugoslavia, Oct. 25, 1954], p. 95-100
- Kolić, B.: **Grmljavinske nepogode u FNRJ u 1951 godini**, [Thunderstorms and foul weather in Yugoslavia, 1951], p. 101-106
- Čadež, Marjan: **Pripreme za Geofizičku godinu**, [Preparations for the Geophysical Year], p. 116-117
- Iz Biblioteke SUHMS-e**, [From the Yugoslav Hydrometeorological Service Library], p. 130-131

**Zeitschrift für Gletscherkunde und Glazialgeologie, Innsbruck, Vol. 3, No. 2, 1956**

- Förtsch, O. and Vidal, H.: **Vorausberechnung des Rückganges der Ostalpengletscher. Veranschaulicht am Hintereisferner (Ötztaler Alpen)**, [Precalculation of the retreat of Eastern Alpine glaciers, as exemplified by the Hintereis glacier], p. 171-180
- Pillewizer, Wolfgang: **Der Rakhiot-Gletscher am Nanga Parbat im Jahre 1954**, [The Rakhiot glacier, Nanga Parbat, in 1954], p. 181-194
- Prey, S.: **Die eiszeitlichen Gletscher im Traunstein-Zwillingskogel-Kamm und im Almtal bei Gmunden, Oberösterreich**, [The Ice Age glaciers on the Traunstein-Zwillingskogel-crest and in the Alpine meadow near Gmunden, Upper Austria], p. 213-234
- Lichtenberger, Elisabeth: **Stadiaie Gletscherstände in den Schladminger Tauern (Steiermark)**, [Glacial stadia in the Schladminger Tauer], p. 235-244
- Ambach, W.: **Über den nächtlichen Wärmeumsatz der gefrorenen Gletscheroberfläche**, [The nocturnal heat exchange of the frozen glacier surface], p. 247-248
- Ebers, Edith: **Der bayerische Anteil des Salzach-Gletschers. Vorläufige Bericht**, [The Bavarian part of the Salzach glacier. Preliminary report], p. 255-256

## PART IV. AUTHOR AND SUBJECT INDEXES

In this section will be found reference to the number given at the head of each abstract or entry. In Part I each entry begins with the number 7.5, and in Part II in the Bibliography on Radioactivity the Atmosphere each entry begins with the number and letter 7E. This index is divided into three parts:

### Index of Authors

### Index of Subjects

### Index of Geographic Locations

## INDEX OF AUTHORS

- Abramova, E. I., 7.5-61  
 Aribat, Marcel, 7E-38, 7E-39,  
 7E-59, 7E-121  
 Akademia Nauk SSSR, Iz-  
 vestia, 7.5-23  
 Akagi, Hiroaki, 7E-95, 7E-96,  
 7E-111  
 Albrecht, Hans J., 7.5-83  
 Aliverti, G., 7E-5, 7E-12, 7E-  
 19, 7E-122  
 Alpert, Léo, 7.5-129  
 Al-Salih, H. A., 7E-126  
 American Geophysical Union,  
 7E-123  
 American Meteorological So-  
 ciety, 7.5-32  
 Andersson, N. E., 7.5-82  
 Andreeva, N. A., 7.5-84  
 Andrews, H. L., 7E-124  
 Anderson, W., 7E-83  
 Annuaire Hydrologique de la  
 France d'Oùtre-Mer, 7.5-72  
 Arakawa, Akio, 7E-125  
 Arakawa, Hidetoshi, 7.5-77,  
 7.5-156, 7E-201  
 Arkhangel'skiĭ, V. L., 7.5-107  
 Arnason, G., 7.5-157  
 Arnold, J. R., 7E-126, 73-196  
 Arrhenius, Gustaf, 7E-127  
 Ashmore, S. E., 7.5-239, 7.5-240  
 Asp, M. O., 7.5-130  
 Aujeszky, László (*trans.*), 7.5-  
 99, 7.5-171  
 Ayer, H. E., 7E-80  
 Azzi, Girolamo, 7.5-231  
 Ball, T. W., 7E-176  
 Bandopadhyay, K. G., 7E-129  
 Bandopadhyay, P., 7E-129  
 Bannon, J. K., 7.5-191  
 Barnett, K. M., 7.5-50  
 Barrett, Earl, 7.5-205  
 Barth, H., 7.5-55  
 Bartha, Lajos, 7.5-225  
 Basu, Binayak, 7E-84  
 Bates, Charles C., 7E-93  
 Baumann, H., 7.5-54  
 Baus, R. A., 7E-214  
 Bayer, Karel, 7.5-152  
 Beers, Norman R., 7E-15  
 Beiser, Arthur, 7.5-253  
 Belcher, D. J., 7E-40  
 Bell, Carlos G., Jr., 7E-79  
 Bellamy, A. W., 7E-142  
 Berger-Landefeldt, U., 7.5-78,  
 7.5-87  
 Best, A. C., 7E-130  
 Bethe, H., 7E-196  
 Bhattacharyya, R. L., 7E-84  
 Bigg, E. K., 7.5-103  
 Blaney, Harry F., 7.5-194  
 Blifford, Irving H., 7E-41, 7E-  
 187, 7E-214  
 Blue Hill Met. Observatory  
 7.5-17  
 Böhme, W., 7.5-108  
 Bohner, Rudolf, 7.5-12  
 Bolelli, Ed., 7.5-195  
 Bolotinskaia, M. Sh., 7.5-95  
 Bontrond, E. A., 7.5-101  
 Boule, Carmen, 7.5-233  
 Brewer, A. W., 7.5-104, 7.5-142  
 Brogan, Lee, 7.5-261  
 Brooks, Charles F., 7.5-17  
 Brown, H., 7E-196  
 Bryson, Reid A., 7.5-184  
 Budyko, M. I., 7.5-141, 7.5-  
 193, 7.5-196  
 Buettner, Konrad, 7E-26  
 Bumpus, Dean F., 7.5-185  
 Burton, Alan C., 7.5-9  
 Businger, J. A., 7.5-109  
 Cabannes, Jean, 7E-16  
 Cammack, R. H., 7.5-51  
 Canada, Met. Div., 7.5-69,  
 7.5-70, 7.5-92  
 Capell, John C., 7.5-56  
 Carlson, Wilbur F., 7.5-124  
 Carmichael, H., 7E-13  
 Chakrawarti, J. C., 7E-129  
 Chapin, Henry, 7.5-10  
 Charnock, H., 7.5-187  
 Chatterjee, S. D., 7E-84, 7E-  
 129, 7E-132  
 Chekalovskii, E. F., 7.5-220  
 Chernick, J., 7E-27  
 Cherubin, L. J., 7E-28  
 Chigirinskiĭ, P. F., 7.5-219  
 Cigna, A., 7E-77  
 Clark, Herbert M., 7E-85, 7E-  
 97  
 Clodman, J., 7.5-181, 7.5-192  
 Cockcroft, Sir John, 7E-133,  
 7E-134  
 Cole, P. T., 7E-148  
 Conforto, B., 7.5-161  
 Contract AF 19(122)-470, 7.5-  
 254  
 Contract AF 19(604)-449, 7.5-  
 159  
 Contract AF 19(604)-1045, 7E-  
 167  
 Contract N189s-96835, 7.5-124  
 Contract N6onr-264(06), 7.5-  
 148  
 Contract N7onr-405, Task 1,  
 7E-58  
 Contract W-31-109 Eng-52,  
 7E-28  
 Contract W-31-109 Eng-52,  
 7E-87  
 Corby, G. A., 7.5-49, 7.5-178  
 Cornell Univ. School of Elec.  
 Engr., 7.5-148  
 Cowan, F. P., 7E-197  
 Crabbe, J. A., 7.5-240  
 Crooks, R. N., 7E-171  
 Currie, B. W., 7.5-172  
 Czyszczek, W., 7.5-245  
 Dammann, W., 7.5-221  
 Damon, P. E., 7E-60, 7E-86  
 Dampier, W., 7.5-27  
 Davos, Switzerland. For-  
 schungs-Institut für Hochge-  
 birgsklima und Tuberkulose,  
 7.5-18

- Roche, A., 7E-71  
 Roll, H., 7E-79  
 Rosa, G., 7E-5  
 Rose, D. C., 7E-54  
 Rosen, M. W., 7E-81  
 Rosenstock, H. B., 7E-41, 7E-187  
 Rotblat, J., 7E-207  
 Rutherford, 7E-1  
 Ryder, N. V., 7E-200
- Saito, N., 7E-146  
 Sakayanagi, Y., 7E-86  
 Sanders, F., 7E-138  
 Sans Heulin, G., 7E-25  
 Santomauro, L., 7E-77  
 Sasaki, Y., 7E-146  
 Sato, Y., 7E-86  
 Sawyer, J. S., 7E-116  
 Schellenberger, G., 7E-55  
 Schmidt, Wilhelm, 7E-3  
 Schneider-Carius, K., 7E-206  
 Schofield, R. K., 7E-30  
 Schröder, R., 7E-207  
 Schultz, H. E., 7E-97  
 Schultz, Melvin L., 7E-7  
 Schumann, G., 7E-67, 7E-110, 7E-211  
 Schweitzer, A., 7E-114  
 Science News Letter, 7E-21, 7E-186, 7E-255, 7E-109  
 Scorer, R. S., 7E-49, 7E-170, 7E-174, 7E-240  
 Seitz, F., 7E-196  
 Serebreny, S. M., 7E-124, 7E-125  
 Setter, L. R., 7E-104, 7E-191  
 Shamos, M. H., 7E-62  
 Shapiro, E., 7E-167  
 Shapiro, S., 7E-14  
 Shenton, L. R., 7E-175  
 Shigematsu, T., 7E-92  
 Shimizu, S., 7E-92, 7E-111  
 Sible, N. J., 7E-261  
 Sidorov, V. I., 7E-190  
 Siksná, R., 7E-23  
 Singer, I. A., 7E-112  
 Sittkus, A., 7E-78, 7E-168  
 Skeib, G., 7E-169  
 Skumanich, A., 7E-117  
 Smith, E. J., 7E-200  
 Smith, F. G. W., 7E-10  
 Sneyers, R., 7E-64  
 Société Hydrotechnique de France, 7E-72  
 Soil Mechanics Conference, Dec. 1950, Montreal, 7E-164  
 Sokolov, A. A., 7E-216  
 South Africa. Weather Bureau, 7E-120  
 Spohn, C. A., 7E-170  
 Stålfelt, M. G., 7E-198  
 Staley, D. O., 7E-151
- Stefanizzi, A., 7E-24  
 Steinhäuser, F., 7E-140, 7E-113  
 Stern, C., 7E-114  
 Stewart, N. G., 7E-171  
 Stiefelmaier, C. A., 7E-126  
 Straka, H., 7E-227  
 Strauss, F. A., 7E-217  
 Sugura, Y., 7E-154, 7E-156  
 Suito, E., 7E-115  
 Suraud, P., 7E-137  
 Sutcliffe, R. C., 7E-119  
 Sutton, Sir O. G., 7E-172  
 Swift, G., 7E-10  
 Szilard, L., 7E-196
- Tajima, E., 7E-192  
 Takahashi, H., 7E-92  
 Takahashi, T., 7E-147  
 Takiyama, K., 7E-115  
 Tanaevsky, O., 7E-173, 7E-174  
 Tanaka, S., 7E-175  
 Tannehill, I., 7E-94  
 Tao, K., 7E-260  
 Teichmann, H., 7E-116  
 Terra, Helsinki, 7E-36  
 Terrell, J. R., 7E-144  
 Thayer, J., 7E-10  
 Thomas, A. C., 7E-131  
 Thomas, C. D., 7E-176  
 Thomas, H. A., Jr., 7E-79  
 Thornthwaite, C. W., 7E-88  
 Tizuka, T., 7E-247  
 Tokyo. Meteorol. Res. Inst. Forecast Res. Lab., 7E-77  
 Tonks, L., 7E-87  
 Topor, N., 7E-99  
 Toyooka, Japan. Weather Station, 7E-204  
 Tracerlab, Inc., Boston, 7E-167  
 Tsivoglou, E. C., 7E-80  
 Tunnicliffe, P. R., 7E-13  
 Turner, Allan R., 7E-209  
 Turner, R. C., 7E-83  
 Turner, R. G., 7E-254  
 Twomey, S., 7E-200
- Uberoi, M. S., 7E-176  
 Undt, W., 7E-229  
 U. S. Air Weather Service, 7E-47, 7E-48, 7E-117  
 U. S. Atomic Energy Commission, 7E-25, 7E-57, 7E-81, 7E-82, 7E-178, 7E-183  
 U. S. Brookhaven National Lab., 7E-14  
 U. S. Bureau of Labor Statistics, 7E-14  
 U. S. Congress. Joint Committee on Atomic Energy, 7E-179
- U. S. Congress. Senate, Committee on Armed Services, 7E-202  
 U. S. Dept. of Defense, 7E-11  
 U. S. Engineer School, Fort Belvoir, Va., 7E-118  
 U. S. Federal Civil Defense Administration, 7E-166, 7E-180, 7E-181  
 U. S. Hydrographic Office, 7E-46  
 U. S. Natl. Bur. of Standards, 7E-199, 7E-212  
 U. S. Off. of Naval Operations, 7E-195  
 U. S. Office of Naval Research, London, 7E-56  
 U. S. School of Aviation Medicine, 7E-26  
 U. S. Scientific Lab., Los Alamos, N. M., 7E-25  
 U. S. Weather Bureau, 7E-14, 7E-223, 7E-224, 7E-49, 7E-182, 7E-183, 7E-193  
 Uppsala. Universitet. Meteorologiska Institutionen, 7E-75  
 Urey, H. C., 7E-226  
 Uyeda, N., 7E-115
- Vámos, R., 7E-230  
 Vancour, R. P., 7E-20  
 van Dijk, W., 7E-180  
 Van Houten, L. F., 7E-3  
 Van Isacker, J., 7E-177  
 Vassy, E., 7E-173, 7E-174  
 Venet, A. M., 7E-38, 7E-39, 7E-121  
 Verkholtzef-Wegener, A., 7E-145  
 Volz, F., 7E-15  
 Vowinkel, E., 7E-232  
 Vuorela, L., 7E-157
- Wadey, W. G., 7E-78  
 Waibel, K., 7E-202, 7E-203  
 Wait, G. R., 7E-4  
 Wakisaka, G., 7E-95, 7E-96  
 Wallington, C. E., 7E-178  
 Warners, C. J., 7E-184  
 Watson-Munro, C. N., 7E-200  
 Weather Services, Inc., Boston, 7E-159  
 Webb, J. H., 7E-18  
 Weickmann, L., 7E-194  
 Weiller, A. R., 7E-119  
 Weiss, M. M., 7E-57  
 Western Snow Conference, Salt Lake City, April 19-21, 1954, 7E-26  
 Wexler, H., 7E-183, 7E-209  
 White, F. D., 7E-198, 7E-209  
 Widdoes, L. C., 7E-150  
 Wiegman, E. J., 7E-124

iese, H., 7.5-106  
iesner, J. B., 7.5-1  
ilkening, M. H., 7E-58  
ilkins, E. W., 7E-49  
ippermann, F., 7.5-118  
ittmann, W., 7E-93  
olf, F., 7.5-249

Wolf, Paul M., 7.5-127  
Woollard, G. P., 7E-124  
Xanthakis, J., 7.5-153  
Yamamoto, R., 7E-120  
Yamasaki, F., 7E-186

Yoshida, N., 7.5-259  
Yoshida, Shozo, 7E-157  
Yoshioka, T., 7.5-154  
Yosida, Z., 7.5-215  
Zharkov, S. N., 7.5-8  
Zingg, Th., 7.5-71

## INDEX OF SUBJECTS

Abnormal summer, 1954, 7E-125, 7E-172, 7E-177, 7E-201  
Acoustical upper wind measurement, 7.5-261  
Advection effects on cloudiness, 7.5-111  
Aerobiology, 7.5-51  
Aeronautical meteorology, 7.5-50, 7.5-173  
Aeronautical meteorology textbooks, 7.5-5  
Aerosols, 7E-58  
Agricultural geography, 7.5-11  
Agricultural meteorology, 7.5-54, 7.5-55  
Agrometeorological services, 7.5-53  
Air conditioning, 7E-141  
Air flow models, 7.5-116  
Air flow over mountains, 7.5-178  
Air mass movements, 7E-56, 7E-57  
Air masses, 7.5-135, 7.5-181  
Air navigation, 7.5-126  
Air sampling and analysis, 7E-31, 7E-89  
Airplane sampling of radioactivity, 7E-16, 7E-17, 7E-64, 7E-65, 7E-89  
Airplane soundings, 7.5-142  
Airways climatic data, 7.5-73  
Amateur forecasting, 7.5-8  
Anemometers, 7.5-88  
Annotated bibliographies, 7E-190  
Annual meteorological data summaries, 7.5-69, 7.5-70, 7.5-75  
Annual observatory reports, 7.5-18  
Annual physico-chemical variations, 7.5-235  
Annual sea water temperature variations, 7.5-167  
Annual service reports, 7.5-17  
Antarctic circulation charts, 7.5-169  
Anticyclone structure, 7.5-133  
Artificial precipitation, 7E-31  
Artificial winds, 7E-119  
Atlantic jet stream, 7.5-123

Atmospheric circulation, 7.5-119, 7.5-193  
Atmospheric circulation theory, 7.5-108  
Atmospheric electricity, 7.5-244  
Atmospheric electricity measurement, 7.5-243  
Atmospheric pollution, 7E-13, 7E-15, 7E-22, 7E-183  
Atmospheric pollution studies, 7E-14  
Atomic energy meteorology, 7E-198  
Atomic explosion clouds, 7E-194  
Atomic explosion effects, 7E-18, 7E-25, 7E-46, 7E-81, 7E-101, 7E-118, 7E-136, 7E-163, 7E-189, 7E-204, 7E-213, 7E-214  
Atomic explosion effects on condensation nuclei, 7E-130  
Atomic explosion effects on weather, 7E-33, 7E-72, 7E-76, 7E-91, 7E-105, 7E-113, 7E-116, 7E-119, 7E-128, 7E-135, 7E-152, 7E-179, 7E-201  
Atomic explosions, 7E-30, 7E-36, 7E-67 to 7E-69, 7E-77, 7E-84, 7E-93, 7E-110  
Atomic heat effects, 7E-26  
Atomic test weather service, 7E-170, 7E-195  
Auroral drift, 7.5-252  
Auroral physics, 7.5-253, 7.5-254  
Austausch, 7E-35  
Austausch coefficient, 7.5-151  
Author indexes, 7.5-36  
Avalanche warning service, 7.5-71  
Aviation medicine, 7E-26  
Bacsák, G., 7.5-225  
Base surge, 7E-34  
Bellani pyranometer, 7.5-85  
Bibliographies of textbooks, 7.5-35  
Bibliography of translations, 7.5-32

Bibliography on radioactive fallout, 7E-190  
Bikini atom bomb tests, 7E-11, 7E-30, 7E-34, 7E-206  
Bikini H-bomb tests, 1954, 7E-102, 7E-106, 7E-120, 7E-132, 7E-154, 7E-156, 7E-157, 7E-160, 7E-169, 7E-178  
Bioclimatology, 7.5-228, 7.5-230  
Bioclimatology of cold regions, 7.5-9  
Biography, 7.5-28, 7.5-29, 7.5-31  
Biological effects of radioactivity, 7E-8, 7E-98, 7E-124, 7E-131, 7E-150, 7E-158, 7E-178, 7E-199  
Bismuth oxychloride precipitation, 7.5-235  
Blue Hill Observatory, 7.5-16, 7.5-17  
Bolometers, 7.5-83  
Bouguer's halo, 7.5-237  
Brookhaven Nat. Lab., Upton, N. Y., 7E-57  
Charged nuclei, 7E-130  
Chemical analysis of rainfall, 7.5-205  
Chemical climatology, 7.5-205  
Chemical composition of precipitation, 7.5-205  
Cherry blossom phenology, 7.5-77  
Chlorinity, 7.5-167  
Circulation type frequencies, 7.5-152  
Cirrus forecasting, 7.5-110  
Civilian defense, 7E-181, 7E-204, 7E-205, 7E-208  
Climate of Auburn, Alabama, 7.5-223  
Climate of El Salvador, 7.5-74  
Climate of Formosa, 7.5-222  
Climate of Hungary, 7.5-11  
Climate of St. Moritz, 7.5-12  
Climate of Troy, Alabama, 7.5-224  
Climate of White Sea area, 7.5-46

- Climatic changes, 7.5-226  
 Climatic data, 7.5-74, 7.5-202  
 Climatic data summaries, 7.5-70, 7.5-223  
 Climatic variations, 7E-105  
 Climatological research, 7.5-221  
 Climatotherapy, 7.5-229  
 Cloud formations, 7E-34  
 Cloud physics, 7.5-17  
 Cloud seeding evaluation, 7.5-102  
 Cold spells, 7.5-208  
 Colloid coagulation, 7.5-234  
 Comparative climatic data, 7.5-69  
 Compendium articles, 7E-35  
 Condensation nuclei, 7E-31, 7E-113  
 Congressional hearings, 7E-208  
 Conservation, 7.5-2  
 Continental geophysics, 7E-123  
 Continentiality, 7.5-231  
 Convection, 7.5-117  
 Convective heat transfer, 7.5-176  
 Convergence and divergence, 7.5-180  
 Coriolis force, 7.5-113  
 Corona discharge hygrometer, 7.5-82  
 Corpuscular radiation, 7.5-133, 7.5-146  
 Cosmic influences, 7.5-233  
 Cosmic ray dosages in atmosphere, 7E-149  
 Cosmic ray effects, 7E-75, 7E-126  
 Currents in Gulf of Finland, 7.5-37  
 Cyclogenesis, 7.5-114  
 Cyclone development, 7.5-128  
 Cyclone dynamics, 7.5-128  
  
 Davos. Switzerland. Forschungs-institut, 7.5-18  
 Dead reckoning computers, 7.5-47  
 Debates, 7.5-225  
 Definitions, 7.5-163  
 Degree days, 7.5-149  
 Dew formation, 7.5-201  
 Dew measurement techniques, 7.5-201  
 Dew point hygrometers, 7.5-87  
 Dew recorders, 7.5-201  
 Diffusion equations, 7E-3, 7E-112  
 Discontinuity surfaces, 7.5-134  
 Diurnal potential gradient, 7.5-245  
 Diurnal temperature variations, 7.5-151  
  
 Diurnal turbulent exchange variations, 7E-37  
 Double theodolite soundings, 7.5-80  
 Dry spells, 7.5-208  
 Dust sampling, 7E-48  
 Dynamic meteorology, 7.5-108  
 Dynamics of the atmosphere, 7.5-119  
  
 Earth temperatures, 7.5-161  
 East-west auroral motion, 7.5-252  
 Educational films, 7E-213  
 Effective radiation, 7.5-84  
 Electric hygrometers, 7.5-62  
 Electrical charges on raindrops, 7.5-251  
 Electrical conductivity of air, 7E-40  
 Electrojet stream theory, 7.5-252  
 Electromagnetic wave propagation, 7.5-256  
 Electrometers, 7.5-243  
 Electrostatic precipitators, 7E-58  
 Elementary meteorology, 7.5-3  
 Emanometry, 7E-35  
 Energy balance, 7.5-115  
 Evaporation, 7.5-198  
 Evaporation measurement, 7.5-196  
 Evaporation of snow, 7.5-197  
 Evaporimeters, 7.5-85, 7.5-89  
 Evapotranspiration, 7.5-194, 7.5-195  
 Exchange coefficient, 7E-37  
 Explosion waves, 7E-120  
  
 F2 critical frequency anomalies, 7.5-159  
 Fairgrieve, J., 7.5-28  
 Fire weather forecasting, 7.5-56  
 Fire weather forecasts, 7.5-57  
 Flight studies, 7.5-58, 7.5-59  
 Floods, 7.5-131  
 Fluid mechanics, 7.5-177  
 Föhn development, 7.5-182  
 Föhn weather, 7.5-182  
 Föhn winds, 7.5-183  
 Fog formation, 7.5-204  
 Forecast accuracy, 7.5-95  
 Forecasters manuals, 7.5-92  
 Forecasting techniques, 7.5-158  
 Forest effects on precipitation, 7.5-211  
 Forest hydrometeorology, 7.5-211  
 Forest snow pack, 7.5-219  
 Freezing nuclei, 7.5-200  
 Frequency distributions, 7.5-64  
  
 Frictional layer, 7.5-107  
 Frontal development, 7.5-81  
 Frontal passage effects, 7.5-136  
 Frost heaving, 7.5-164  
  
 Gamma ray anomalies, 7E-10  
 Gammameters, 7E-51  
 Gauss, Carl Friedrich, 7.5-10  
 Geodesy networks, 7E-123  
 Geomagnetic disturbances, 7.5-106  
 Geomagnetic variations, 7.5-159  
 Geomagnetism, 7.5-29  
 Geophysical conferences, 7.5-23, 7.5-25  
 Geophysical manpower, 7.5-10  
 Geostrophic wind field, 7.5-10  
 Geostrophic winds, 7.5-192  
 German Hydrographic Institute, 7.5-40  
 Geysers, 7.5-161  
 Glacial periods, 7.5-226  
 Gliding congresses, 7.5-49  
 Global precipitation variations, 7E-44  
 Global radiation measurements, 7.5-85  
 Global radioactivity, 7E-10, 7E-207  
 Glories, 7.5-237  
 Gradient winds, 7E-119  
 Grating spectrometers, 7.5-81  
 Grosswetterlagen, 7E-113  
 Ground water movements, 7.5-143  
  
 Hail, 7.5-249  
 Hailstorm conditions, 7.5-161  
 Halo observations, 7.5-231, 7.5-241  
 Halos, 7.5-240  
 Health resorts, 7.5-229  
 Heat balance, 7.5-139, 7.5-141  
 Heat balance of lakes, 7.5-161  
 Heat exchange sea-atmosphere, 7.5-167  
 High altitude observatories, 7.5-236  
 Historical climates, 7.5-77  
 History of Kew Observatory, 7.5-19  
 History of meteorology, 7.5-21  
 History of rainbooms, 7.5-238  
 Hot spells, 7.5-208  
 Human ecology, 7E-197  
 Hydrography, 7.5-165  
 Hydrologic cycle, 7.5-2, 7.5-195  
 Hydrologic data, 7.5-12  
 Hydrologic regime, 7.5-44  
 Hydrology bibliographies, 7.5-33

- Climatology yearbooks, 7.5-72  
 Hydrometeorological data, 7.5-72  
 Hydrometeorology, 7.5-33  
 Images, 7.5-225  
 Lag of transmission lines, 7.5-202, 7.5-203  
 Illumination intensity, 7.5-140  
 Infrared spectroscopy, 7.5-254  
 Infrared transmission calculations, 7.5-143  
 Infrared transmission through raindrops, 7.5-144  
 Instability criteria, 7.5-110  
 Instrument manuals, 7.5-47, 7E-57  
 Insularity, 7.5-231  
 Integral equations, 7.5-110  
 Interplanetary flights, 7.5-81  
 Interplanetary magnetic field, 7.5-253  
 Intertropical meteorology, 7.5-137  
 Ion production rate with height, 7.5-248  
 Ionization, 7E-4, 7E-19, 7E-20, 7E-35, 7E-71  
 Ionization chamber, 7E-12  
 Ionospheric currents, 7.5-106  
 Ionospheric winds, 7.5-252  
 Irrigation, 7.5-52, 7.5-194, 7.5-209  
 Isentropic dust trajectories, 7E-88  
 Isobaric surfaces, 7.5-181  
 Isothermal atmosphere, 7.5-248  
 Isotopes in the atmosphere, 7E-126  
 Japanese radiosonde, 7.5-91  
 Jet stream, 7E-68, 7E-164  
 Jet stream flying, 7.5-123  
 Jet stream navigation, 7.5-125  
 Jet stream profiles, 7.5-121  
 Jet stream structure, 7.5-125  
 Jet stream variations, 7.5-122, 7.5-126  
 Joint Numerical Weather Prediction Project, 7.5-94  
 Jupiter, 7.5-255  
 Juvenile literature, 7.5-7  
 Kinetic energy spectrum in atmosphere, 7.5-118  
 Lake influences, 7.5-168, 7.5-216  
 Lee waves, 7.5-178  
 Lightning counters, 7.5-250  
 Lightning discharges, 7.5-247  
 Local wind surveys, 7.5-58, 7.5-59  
 Local winds, 7.5-183  
 Long period records, 7.5-130, 7.5-156, 7.5-188  
 Long range forecasting, 7.5-95 to 7.5-97, 7.5-99, 7.5-150  
 Long wave theory application, 7.5-56  
 Low level turbulence, 7.5-173  
 Lunar monthly tides, 7.5-171  
 Magnetic storms, 7.5-146  
 Magnetic variations, 7.5-22  
 Magneto-hydrodynamic waves, 7.5-113  
 Marine meteorological data, 7.5-76  
 Marine meteorological observations, 7.5-79  
 Marine meteorology, 7.5-42  
 Marine sediments, 7E-127  
 Mean seasonal pressure charts for Southern Hemisphere, 7.5-169  
 Medical climatology, 7.5-9, 7.5-229  
 "Meerkatze," 7.5-79  
 Meridional profiles, 7.5-120  
 Meteor trail drift, 7.5-65  
 Meteoric dust, 7.5-200  
 Meteorological education, 7.5-14  
 Meteorological effects on col-loids, 7.5-234  
 Meteorological effects on radio-active springs, 7E-94  
 Meteorological effects on radio-activity, 7E-52  
 Meteorological manpower, 7.5-14  
 Meteorological observatories, 7.5-16  
 Meteorological stations, 7.5-20  
 Meteorological symposia, 7.5-24  
 Meteorology book catalogs, 7.5-34  
 Meteorology textbooks for pilots, 7.5-5  
 Microbaric waves, 7.5-136  
 Microbarograph oscillations, 7E-120  
 Micrometeorological instru-ments, 7.5-87  
 Micrometeorological networks, 7E-48  
 Mie theory, 7.5-144  
 Military meteorology, 7E-118, 7E-162  
 Mobile weather stations, 7.5-78  
 Moisture exchange, 7.5-193  
 Monsoon forecasting, 7.5-98  
 Monthly data bulletins, 7.5-73, 7.5-75  
 Monthly mean pressure charts, 7.5-120  
 Mountain effects, 7.5-244  
 Mountain-valley wind pat-terns, 7.5-59  
 Mountain-valley wind studies, 7.5-58  
 Mutations due to radioactive fallout, 7E-158  
 Nitrogen spectra, 7.5-254  
 National Reactor Testing Sta-tion, Idaho, 7E-48, 7E-49  
 Nevada atom bomb tests, 7E-139  
 New York University, 7.5-41  
 Noctilucent clouds, 7.5-242  
 Northern Hemisphere normal temperature charts, 7.5-157  
 Nuclear emulsions, 7E-74  
 Nuclear physics, 7E-153  
 Nuclei, 7.5-15  
 Nuclei and radioactivity, 7E-5, 7E-7  
 Nuclei in free air, 7.5-199  
 Nuclei theories, 7E-5  
 Numerical forecasting, 7.5-157  
 Observational data, 7.5-73, 7.5-75, 7.5-149  
 Ocean currents, 7.5-180, 7.5-185  
 Ocean swell, 7.5-41  
 Ocean wave research, 7.5-41, 7.5-189  
 Oceanographic education, 7.5-38  
 Oceanographic research, 7.5-38, 7.5-40, 7.5-43  
 Off shore oil industry, 7.5-189  
 Orographic influences, 7.5-107  
 Ozone distribution in upper atmosphere, 7.5-104  
 Ozone variations, 7.5-105  
 pH content of precipitation, 7.5-205  
 pH content of rainwater, 7E-189  
 Pacific jet stream, 7.5-122, 7.5-123, 7.5-124  
 Paleoclimates, 7.5-225  
 Pan Indian Ocean Science Congress, 7.5-24  
 Parry arc, 7.5-240  
 Periodical indexes, 7.5-36  
 Permafrost, 7.5-163  
 Physiological effects, 7.5-228  
 Pilot balloon accuracy, 7.5-80  
 Plant climate measuring truck, 7.5-78  
 Plant diseases, 7.5-230  
 Plant transpiration measure-ment, 7.5-82

- Polar fronts, 7.5-124  
 Pollen analysis, 7.5-227  
 Popular meteorology, 7.5-4, 7.5-6 to 7.5-8  
 Popular science books, 7.5-2  
 Potential gradient, 7E-140  
 Potential gradient meters, 7.5-245  
 Potential gradient observations, 7.5-199  
 Potential gradient variations, 7.5-246, 7.5-247  
 Precipitation calculations, 7.5-61  
 Precipitation effects on radar echoes, 7.5-68  
 Precipitation effects on radioactivity, 7E-44  
 Precipitation normals, 7.5-149  
 Precipitation variability, 7.5-61  
 Pressure forecasting, 7.5-101  
 Pressure oscillations, 7.5-170  
 Pressure variations, 7.5-101, 7.5-150  
 Pressure waves, 7E-169  
 Professional meteorologists, 7.5-14  
 Progress in meteorology, 7.5-94  
 Public health, 7E-13  
 Punched card methods, 7.5-62  
 Punched card programs, 7.5-62  
 Pyrgometers, 7.5-84  
 Pyrheliometers, 7.5-84  
 Quasi-stationary circulation, 7.5-108  
 Rabbits, 7.5-228  
 Radar echoes, 7.5-68  
 Radar research, 7.5-17  
 Radar wind accuracy, 7.5-66  
 Radiation bioclimatology, 7.5-18  
 Radiation balance, 7.5-139  
 Radiation effects, 7E-197  
 Radiation flux in upper air, 7.5-142  
 Radiation hazards, 7E-87, 7E-134, 7E-150, 7E-158  
 Radiation safety measures, 7E-53, 7E-141, 7E-162, 7E-166, 7E-181  
 Radio astronomy, 7.5-148  
 Radio echoes from meteors, 7.5-67  
 Radio fading, 7.5-258, 7.5-259  
 Radio fading instruments, 7.5-258  
 Radio interferometer observations, 7.5-148  
 Radio meteor observations, 7.5-67  
 Radio noise, 7.5-147, 7.5-255  
 Radio transmission ducts, 7.5-259  
 Radio wave diffraction, 7.5-259  
 Radio wave propagation, 7.5-256  
 Radio wave scattering, 7.5-257  
 Radioactive aerosols, 7E-73, 7E-142  
 Radioactive condensation nuclei, 7E-30  
 Radioactive counter accuracy, 7E-161  
 Radioactive dating methods, 7E-127  
 Radioactive diffusion, 7E-37, 7E-55, 7E-87  
 Radioactive dosage, 7E-111  
 Radioactive dose rate meters, 7E-148  
 Radioactive effluents, 7E-14, 7E-15, 7E-22, 7E-48, 7E-49, 7E-57, 7E-112, 7E-183, 7E-198, 7E-209  
 Radioactive emanation distribution, 7E-3, 7E-9  
 Radioactive emanations, 7E-1, 7E-70, 7E-165, 7E-188  
 Radioactive fallout, 7E-10, 7E-84, 7E-88, 7E-100, 7E-101, 7E-106, 7E-114, 7E-124, 7E-131 to 7E-134, 7E-140, 7E-163, 7E-193, 7E-204, 7E-205  
 Radioactive fallout analysis, 7E-95, 7E-96, 7E-98, 7E-111, 7E-115, 7E-145, 7E-146, 7E-186  
 Radioactive fallout calculation manuals, 7E-117, 7E-180, 7E-182  
 Radioactive fallout composition, 7E-92, 7E-102  
 Radioactive fallout computers, 7E-212  
 Radioactive fallout data, 7E-16, 7E-28, 7E-54, 7E-59, 7E-60, 7E-104, 7E-151, 7E-154, 7E-155, 7E-171, 7E-187, 7E-192, 7E-200, 7E-210  
 Radioactive fallout effects, 7E-175, 7E-202  
 Radioactive fallout effects on wildlife, 7E-139  
 Radioactive fallout networks, 7E-53, 7E-56, 7E-61, 7E-81, 7E-136, 7E-142, 7E-198, 7E-203  
 Radioactive fallout propagation, 7E-45, 7E-99, 7E-159, 7E-164, 7E-166, 7E-168  
 Radioactive hydrologic tracing methods, 7E-143  
 Radioactive permissible age, 7E-199  
 Radioactive pollution of atmosphere, 7E-114  
 Radioactive rainout, 7E-7E-62, 7E-85, 7E-97  
 Radioactive snow gages, 7E-43, 7E-108  
 Radioactive soil moisture instruments, 7E-40  
 Radioactive tracer techniques, 7E-47, 7E-167  
 Radioactivity in hailstorms, 7E-93  
 Radioactivity in hoarfrost, 138  
 Radioactivity in marine sediments, 7E-127  
 Radioactivity in ocean waters, 7E-154, 7E-156, 7E-157, 7E-206  
 Radioactivity in packaging materials, 7E-18  
 Radioactivity in precipitation, 7E-47, 7E-77, 7E-82, 7E-104, 7E-174  
 Radioactivity in rainwater, 7E-38, 7E-39, 7E-84, 7E-86, 7E-109, 7E-126, 7E-111, 7E-155, 7E-173, 7E-186  
 Radioactivity in reservoirs, 7E-97  
 Radioactivity in snow, 7E-36, 7E-63, 7E-65, 7E-101  
 Radioactivity in surface waters, 7E-79, 7E-191  
 Radioactivity in the atmosphere, 7E-2, 7E-4 to 7E-10, 7E-13, 7E-17, 7E-19 to 7E-21, 7E-24, 7E-28, 7E-29 to 7E-31, 7E-35, 7E-41, 7E-42, 7E-45, 7E-47, 7E-50 to 7E-52, 7E-56, 7E-58, 7E-64, 7E-65, 7E-67, 7E-69, 7E-71, 7E-78, 7E-90, 7E-110, 7E-121, 7E-122, 7E-137, 7E-138, 7E-140, 7E-171, 7E-184, 7E-192, 7E-197, 7E-214  
 Radioactivity measurement techniques, 7E-12, 7E-22, 7E-57, 7E-66, 7E-74, 7E-80, 7E-99, 7E-144, 7E-146, 7E-211  
 Radioactivity variations, 7E-174  
 Radioargon concentration, 7E-22, 7E-112  
 Radiocarbon in the atmosphere, 7E-75  
 Radiosonde corrections, 7.5-94  
 Radiosonde data, 7.5-73  
 Radiosonde errors, 7.5-91

- diodes measurement of radioactivity, 7E-144
- diodes pyranometers, 7.5-33
- diodes, 7.5-90
- don anomalies, 7E-90
- don content of atmosphere, 7E-58, 7E-83, 7E-107, 7E-173, 7E-176
- don content of soil air, 7E-94
- don content of springs, 7E-94
- rainbow theory, 7.5-238
- rainfall intensity distribution, 7.5-206
- rainfall singularities, 7.5-200
- rainwater analysis, 7E-38, 7E-86
- rainy seasons, 7.5-207
- rainy spells, 7.5-208
- random walk, 7.5-175
- rain data, 7.5-73
- refraction of electromagnetic waves, 7.5-256
- resistance thermometers, 7.5-87, 7.5-162
- reviews, 7.5-192, 7.5-198
- reviews of meteorology books, 7.5-35
- Reynolds number, 7.5-177
- rice, 7.5-230
- rice culture, 7.5-52
- river discharge calculations, 7.5-220
- river flow, 7.5-216
- Rockets, 7.5-81
- Rothamsted Experimental Station, 7.5-30
- runoff evaluation, 7.5-63
- Russian meteorological literature, 7.5-32
- sailing directions, 7.5-45, 7.5-46
- salinity distribution, 7.5-44
- satellite observatories, 7.5-81
- scattering function, 7.5-15
- science textbooks, 7.5-3
- sea resources, 7.5-10
- sea temperature, 7.5-180
- sea temperature data, 7.5-165, 7.5-166
- seawater salinity data, 7.5-166
- Seiches, 7.5-184
- severe winters, 7.5-156
- spheres from planets, 7.5-255
- shower conditions, 7.5-160
- Skelton, P. N., 7.5-31
- sky light color, 7.5-15
- slide rules, 7.5-47
- snow composition, 7.5-215
- snow conference proceedings, 7.5-26
- snow cover, 7.5-214
- snow cover depth, 7.5-61
- snow crystals, 7.5-212
- snow line and dew point, 7.5-214
- snow melt, 7.5-197, 7.5-213
- snow radioactivity analysis, 7E-36, 7E-63
- snow research institutes, 7.5-71
- snow surveys, 7.5-217
- snowfall data, 7.5-213
- soil conservation, 7.5-186, 7.5-209
- soil density instruments, 7E-40
- soil mechanics, 7.5-164
- soil moisture studies, 7.5-30
- soil temperature under snow, 7.5-162
- solar activity, 7.5-133
- solar activity research, 7.5-21
- solar atmosphere, 7.5-117
- solar atmospheric turbulence, 7.5-176
- solar disturbances, 7.5-148
- solar influences, 7.5-235
- solar physics, 7.5-236
- solar power resources, 7.5-10
- solar radiation instruments, 7.5-83
- solar radiation transformation, 7.5-141
- solar radio frequency radiation, 7.5-148
- solar radio noise, 7.5-147
- solar-terrestrial relationships, 7.5-236
- solar-terrestrial time delays, 7.5-253
- southern Hemisphere Project (South Africa), 7.5-94, 7.5-120
- southwest monsoon onset, 7.5-98
- specialized forecasts, 7E-170, 7E-195
- stack meteorology, 7E-14, 7E-15, 7E-49, 7E-183, 7E-209
- statistical studies, 7.5-64, 7.5-155
- statistical techniques, 7.5-102, 7.5-206
- storms in Canadian prairies, 7.5-172
- stratospheric winds, 7.5-105, 7.5-191, 7E-116
- subject indexes, 7.5-36
- subtropical jet stream, 7.5-122
- sunspot cycles, 7.5-159
- sunspot effects on temperature, 7.5-153
- sunspot effects on weather, 7E-125
- supersaturation, 7E-130
- synoptic case histories, 7.5-134
- synoptic climatology, 7.5-135, 7.5-232
- synoptic networks, 7.5-93
- synoptic transmissions, 7.5-93
- synoptic types, 7.5-99
- telemetering systems, 7E-43, 7E-108
- tele-pyranometers, 7.5-83
- temperature cycles, 7.5-153
- temperature drop, 7.5-230
- temperature effects on nuclear reactors, 7E-27
- temperature frequencies, 7.5-155
- temperature normals, 7.5-149
- temperature-precipitation relations, 7.5-154
- temperature variations, 7.5-150, 7.5-154
- temperatures in Greece, 7.5-13
- Texas Agricultural and Mechanical College, 7.5-38
- textbooks, 7E-25
- thermodynamics of dew formation, 7.5-201
- thermonuclear explosion effects, 7E-100, 7E-103, 7E-125, 7E-140, 7E-147, 7E-153, 7E-160, 7E-169, 7E-178, 7E-196, 7E-207
- thermonuclear explosion effects on weather, 7E-172, 7E-177, 7E-185
- thermonuclear explosions, 7E-133
- thunderstorm dynamics, 7.5-132
- thunderstorm electricity, 7.5-249
- thunderstorm forecasting, 7.5-160
- thunderstorms, 7.5-131
- Tokyo-Honolulu air route, 7.5-126
- tornado frequencies, 7E-91
- tornado observation, 7.5-129
- tornado track charts, 7.5-130
- tornadoes (June 1953), 7E-72
- translations, 7.5-32
- transpiration meters, 7.5-82
- tree growth pattern and rainfall types, 7.5-210
- tree ring-rainfall relationships, 7.5-210
- tritium measurement, 7E-109
- troposphere, 7.5-257
- tropospheric advection, 7.5-111
- tropospheric propagation, 7.5-1

- Tropospheric refraction, 7.5-260  
 Turbidity, 7.5-15  
 Turbulence, 7.5-174  
 Turbulence in the frictional layer, 7.5-109, 7.5-173  
 Turbulence spectrum, 7.5-112  
 Turbulence theory, 7.5-175, 7E-55  
 Turbulent diffusion, 7E-22  
 Turbulent flow, 7.5-177  
 Turbulent transfer of heat, 7.5-112  
 Turbulent transfer of momentum, 7.5-112  
 Twilight phenomena, 7.5-103  
 Ulloa's ring, 7.5-237  
 Ultraviolet radiation, 7.5-145  
 Umkehr effect, 7.5-145  
 U.S.S.R. Geophysical Institute, 7.5-23  
 U. S. Weather Bureau, 7E-198  
 Upper air fallout code, 7E-193  
 Upper air flow patterns, 7E-93, 7E-159  
 Upper air pressure, 7.5-192  
 Upper air temperature periodicities, 7.5-159  
 Upper air temperature variations, 7.5-103  
 Upper air temperatures, 7.5-103  
 Upper air wind measurement, 7.5-65, 7.5-80  
 Upper air winds, 7.5-192, 7E-69, 7E-164  
 Uppsala University, Sweden, 7.5-75  
 Uranium mines, 7E-80  
 Vertical temperature gradient, 7.5-13, 7.5-157  
 Vertical wind velocity, 7.5-80  
 Volcanic influences, 7.5-245, 7E-125  
 Vorticity equations, 7.5-114  
 Water content of snow pack, 7E-108  
 Water level variations, 7.5-12, 7.5-89  
 Water supply forecasts, 7.5-217  
 Water supply from snow, 7.5-219  
 Water supply survey, 7.5-218  
 Water vapor transfer, 7.5-193  
 waves in the westerlies, 7.5-127  
 Weather broadcasts, 7.5-4  
 Weather lore, 7.5-8, 7E-185  
 Weather modification, 7E-7E-147, 7E-152  
 Weather ship data, 7.5-66, 76  
 Weather type symbols, 7.5-18  
 Weather types, 7.5-232  
 Wind conditions in Canada, Arctic, 7.5-172  
 Wind driven currents, 7.5-185  
 Wind effects on lakes, 7.5-185  
 Wind effects on water level, 7.5-188  
 Wind erosion, 7.5-186  
 Wind forecast verification, 7.5-57  
 Wind generators, 7.5-190  
 Wind profile measurements, 7.5-88  
 Wind profile theory, 7.5-109  
 Wind profiles, 7.5-107  
 Wind shift line, 7.5-173  
 Wind speed maximum, 7.5-187  
 Wind-wave relationships, 7.5-187  
 Wind waves, 7.5-189  
 Winter flying hazards, 7.5-40  
 WMO. Commission for Aerology, 7.5-90  
 Zonal index, 7.5-120

## INDEX OF GEOGRAPHICAL LOCATIONS

- ARCTIC, 7.5  
 Canadian Arctic, 7.5-172  
 Soviet Arctic, 7.5-190  
 Cape Zhelanina, 7.5-190  
 NORTH AMERICA  
 Canada, 7.5-4, 7.5-39, 7.5-164  
 British Columbia  
 Vancouver, 7.5-70  
 Ontario  
 Kingston, 7E-163  
 Ottawa, 7E-54  
 Prairie Provinces, 7.5-172  
 Saskatchewan, 7.5-209  
 Regina, 7.5-69  
 United States, 7.5-48, 7.5-159, 7.5-150, 7.5-194, 7E-99, 7E-136, 7E-210  
 Alabama  
 Auburn, 7.5-223  
 Troy, 7.5-224  
 Arkansas, 7.5-130  
 Fayetteville, 7E-60  
 California  
 Big Creek Drainage, 7.5-59  
 Sierra Nevada Range, 7.5-217  
 Upper Sacramento Basin, 7.5-58  
 Colorado  
 Climax, 7.5-236  
 Great Plains, 7.5-186  
 Idaho, 7E-48, 7E-49  
 Indiana  
 Vincennes, 7E-18  
 Massachusetts, 7E-79  
 Michigan  
 Ann Arbor, 7E-36  
 Nevada  
 Ely, 7E-151  
 Yucca Flat, 7E-139, 7E-170  
 New Mexico, 7.5-210, 7.5-261  
 Socorro, 7E-58  
 New York, 7E-97  
 Brookhaven, 7E-14, 7E-15, 7E-22, 7E-112  
 Hannibal, 7E-82  
 New York, 7E-20, 7E-21, 7E-62  
 Schenectady, 7E-28  
 Troy, 7E-85  
 Ohio  
 Cincinnati, 7E-104, 7E-191  
 Columbus, 7.5-25  
 Oklahoma  
 Tulsa, 7E-10  
 Oregon, 7.5-56  
 Texas  
 Houston, 7E-11  
 Washington, D. C., 7E-97, 7E-187, 7E-214  
 Washington State, 7.5-58  
 Western United States, 7.5-26  
 Central America, 7.5-207  
 El Salvador, 7.5-74  
 Panama, 7.5-129  
 Caribbean Area  
 Gulf of Mexico, 7.5-52, 7.5-189  
 West Indies, 7.5-207  
 SOUTH AMERICA  
 Colombia, 7.5-207  
 Venezuela, 7.5-207

- TROPE**  
**Alps**  
 Swiss Alps, 7.5-12, 7.5-206  
**Austria**  
 Lake Traunsee, 7.5-168  
 Salzburg Province, 7E-107  
 Vienna, 7.5-140  
 Unter-Tullnerbach, 7.5-235  
 Zugspitze, 7.5-244  
**Belgium**  
 Evre, 7.5-90  
**British Isles**, 7.5-53, 7.5-218, 7E-133  
 England, 7E-42, 7E-134  
 Cambridge, 7.5-250  
 Central England, 7.5-156  
 Greenwich, 7.5-20  
 Kew Observatory, 7.5-19, 7.5-115, 7.5-139  
 London, 7.5-208  
 Salisbury Plain, 7.5-102  
 Ireland, 7.5-73  
 Valentia, 7.5-73  
**Czechoslovakia**, 7.5-183  
 Milešovka, 7.5-152  
 Tatra Mountains, 7.5-183  
**Finland**, 7.5-166, 7.5-197  
**France**, 7E-16, 7E-17, 7E-30, 7E-31, 7E-65, 7E-90  
 French overseas colonies, 7.5-72  
 Paris, 7E-38, 7E-39, 7E-59, 7E-121  
 Puy-de-Dôme, 7E-6, 7E-32, 7E-42, 7E-63, 7E-89, 7E-137, 7E-188  
 Val Joyeux, 7E-174  
**Germany**, 7.5-33, 7E-169  
 Black Forest  
 Feldberg, 7.5-203  
 Freiburg, 7E-69  
 Königsstuhl, 7E-67, 7E-110  
 Maintz, 7.5-15  
 Munich, 7.5-160  
 Niemegk, 7.5-22  
 West Germany, 7.5-62  
 Zugspitze, 7E-165  
**Greece**, 7.5-13  
**Gulf of Bothnia**, 7.5-165  
**Gulf of Finland**, 7.5-37  
**Hungary**, 7.5-11, 7.5-230  
**Italy**, 7.5-161, 7E-77  
 Sicily  
 Palermo, 7.5-80  
**Netherlands**, 7E-184  
**Norway**, 7.5-104, 7.5-205  
**Poland**, 7.5-183  
 Silesia, 7.5-213  
 Swider, 7.5-245  
 Vistula Bay, 7.5-188  
**Rumania**, 7.5-99  
**Sweden**, 7.5-205  
 Stockholm, 7E-23  
**Switzerland**, 7.5-71  
 Arosa, 7.5-15  
 St. Moritz, 7.5-12  
 Swiss Alps, 7.5-12, 7.5-206  
 Weissfluchjoch, 7.5-71  
**U.S.S.R.**, 7.5-216  
**White Sea**, 7.5-46  
**Yugoslavia**  
 Belgrade, 7.5-155  
 Kredarica Mountain, 7.5-214
- ASIA**  
**Asiatic U.S.S.R.**  
 Aral Sea, 7.5-44  
 Azov Sea, 7.5-44  
 Caspian Sea, 7.5-44  
 Eastern Siberia, 7.5-107  
**China**, 7.5-45  
**Formosa**, 7.5-222  
**India**, 7.5-43, 7.5-98  
 Calcutta, 7E-84, 7E-129, 7E-132  
**Iraq**, 7.5-121  
**Japan**, 7.5-162, 7.5-204, 7.5-246, 7.5-259, 7E-102, 7E-125, 7E-155, 7E-160, 7E-177, 7E-192, 7E-203  
 Aikawa, 7.5-154  
 Arima, 7E-94  
 Gotonada, 7.5-167  
 Kyoto, 7.5-77  
 Northern Japan, 7.5-156  
 Shionomisaki, 7E-120  
 Tokyo, 7E-186  
 Toyooka Basin, 7.5-204  
**AFRICA**, 7.5-137  
**Arabia**  
 Sharjah, 7.5-131  
**Egypt**, 7.5-121  
**French Africa**, 7.5-72  
 Morocco, 7.5-195  
**Nigeria**  
 Ibadan, 7.5-51  
**South Africa**  
 Pretoria, 7.5-232
- AUSTRALASIA**  
**Australia**  
 Alice Springs, 7.5-103  
 Tasmania, 7.5-173  
 Western Australia  
 Perth, 7.5-24  
 South Australia  
 Woomera, 7E-88  
**New Zealand**  
 Wellington, 7E-88, 7E-200
- ANTARCTICA**, 7.5-169  
**OCEANS, SEAS AND ISLANDS**  
**Atlantic Ocean**  
 North Atlantic, 7.5-76  
 Western North Atlantic, 7.5-185  
**Indian Ocean**, 7.5-180  
 Ceylon, 7.5-135  
**Pacific Ocean**, 7.5-124  
 Eastern Pacific, 7.5-122  
 Marshall Islands  
 Bikini, 7E-34  
 Western North Pacific, 7.5-125

